# Dialogs and Windows with Qt

Qt 3.0

Copyright © 2001 Trolltech AS. All rights reserved.

TROLLTECH, Qt and the Trolltech logo are registered trademarks of Trolltech AS. Linux is a registered trademark of Linus Torvalds. UNIX is a registered trademark of X/Open Company Ltd. Mac is a registered trademark of Apple Computer Inc. MS Windows is a registered trademark of Microsoft Corporation. All other products named are trademarks of their respective owners.

The definitive Qt documentation is provided in HTML format supplied with Qt, and available online at http://doc.trolltech.com. This PDF file was generated automatically from the HTML source as a convenience to users, although PDF is not an official Qt documentation format.

# **Contents**

QColorDialog Class Reference
QCustomMenuItem Class Reference
QDesktopWidget Class Reference
QDialog Class Reference
QDockArea Class Reference
QDockWindow Class Reference
QFileDialog Class Reference
QFileIconProvider Class Reference
QInputDialog Class Reference
QMainWindow Class Reference
QMenuBar Class Reference
QMenuData Class Reference
QMessageBox Class Reference
QPopupMenu Class Reference
QProgressDialog Class Reference
QTabDialog Class Reference
QToolBar Class Reference
QToolButton Class Reference
QToolTip Class Reference
QToolTipGroup Class Reference
QWizard Class Reference
QWorkspace Class Reference
Index

The QColorDialog class provides a dialog widget for specifying colors.

#include <qcolordialog.h>
Inherits QDialog [p. 12].

# Static Public Members

- QColor **getColor** (const QColor & initial = white, QWidget \* parent = 0, const char \* name = 0)
- QRgb getRgba (QRgb initial, bool \* ok = 0, QWidget \* parent = 0, const char \* name = 0)
- int customCount ()
- QRgb customColor(int i)
- void **setCustomColor** (int i, QRgb c)


# **Detailed Description**

The QColorDialog class provides a dialog widget for specifying colors.

The color dialog's function is to allow users to choose colors - for instance, you might use this in a drawing program to allow the user to set the brush color.

This version of Qt provides only modal color dialogs. The static getColor() function shows the dialog and allows the user to specify a color, whereas getRgba() does the same but allows the user to specify a color with an alpha channel (transparency) value.

The user can store customCount() different custom colors. The custom colors are shared by all color dialogs, and remembered during the execution of the program. Use setCustomColor() to set the custom colors, and use customColor() to get them.



See also Dialog Classes and Graphics Classes.

#### **Member Function Documentation**

#### QRgb QColorDialog::customColor(inti)[static]

Returns custom color number i as a QRgb.

## int QColorDialog::customCount() [static]

Returns the number of custom colors supported by QColorDialog. All color dialogs share the same custom colors.

# QColor QColorDialog::getColor (const QColor & initial = white, QWidget \* parent = 0, const char \* name = 0) [static]

Pops up a modal color dialog, lets the user choose a color, and returns that color. The color is initially set to *initial*. The dialog is a child of *parent* and is called *name*. Returns an invalid (see QColor::isValid()) color if the user cancels the dialog. All colors allocated by the dialog will be deallocated before this function returns.

Example: scribble/scribble.cpp.

# QRgb QColorDialog::getRgba (QRgb initial, bool \* ok = 0, QWidget \* parent = 0, const char \* name = 0) [static]

Pops up a modal color dialog to allow the user to choose a color and an alpha channel value. The color+alpha is initially set to *initial*. The dialog is a child of *parent* and called *name*.

If ok is non-null, \*ok is set to TRUE if the user clicked OK, and FALSE if the user clicked Cancel.

If the user clicks Cancel, the *initial* value is returned.

# void QColorDialog::setCustomColor(int i, QRgb c) [static]

Sets custom color number i to the QRgb value c.

# QCustomMenuItem Class Reference

The QCustomMenuItem class is an abstract base class for custom menu items in popup menus.

#include <qmenudata.h>

Inherits Qt [Additional Functionality with Qt].

#### **Public Members**

- QCustomMenuItem ()
- virtual ~QCustomMenuItem ()
- virtual bool fullSpan () const
- virtual bool isSeparator () const
- virtual void **setFont** (const QFont & font)
- virtual void paint (QPainter \* p, const QColorGroup & cg, bool act, bool enabled, int x, int y, int w, int h)
- virtual OSize **sizeHint**()

# **Detailed Description**

The QCustomMenuItem class is an abstract base class for custom menu items in popup menus.

A custom menu item is a menu item that is defined by two purely virtual functions, paint() and sizeHint(). The size hint tells the menu how much space it needs to reserve for this item, and paint is called whenever the item needs painting.

This simple mechanism allows you to create all kinds of application specific menu items. Examples are items showing different fonts in a word processor or menus that allow the selection of drawing utilities in a vector drawing program.

A custom item is inserted into a popup menu with QPopupMenu::insertItem().

By default, a custom item can also have an icon set and a keyboard accelerator. You can reimplement fullSpan() to return TRUE if you want the item to span the entire popup menu width. This is particularly useful for labels.

If you want the custom item to be treated just as a separator, reimplement is Separator() to return TRUE.

Note that you can insert pixmaps or bitmaps as items into a popup menu without needing to create a QCustomMenu-Item. However, custom menu items offer more flexibility, and — especially important with windows style — provide the possibility of drawing the item with a different color when it is highlighted.

menu/menu.cpp shows a simply example how custom menu items can be used.



See also QMenuData [p. 87], QPopupMenu [p. 115] and Miscellaneous Classes.

#### **Member Function Documentation**

QCustomMenuItem::QCustomMenuItem()

Constructs a OCustomMenuItem

QCustomMenuItem::~QCustomMenuItem() [virtual]

Destroys a QCustomMenuItem

#### bool QCustomMenuItem::fullSpan() const [virtual]

Returns TRUE if this item wants to span the entire popup menu width. The default is FALSE, meaning that the menu may show an icon and an accelerator key for this item as well.

### bool QCustomMenuItem::isSeparator() const [virtual]

Returns TRUE if this item is just a separator; otherwise returns FALSE.

## void QCustomMenuItem::paint ( QPainter \* p, const QColorGroup & cg, bool act, bool enabled, int x, int y, int w, int h ) [virtual]

Paints this item. When this function is invoked, the painter p is set to the right font and the right foreground color suitable for a menu item text using color group cg. The item is active if act is TRUE and enabled if enabled is TRUE. The geometry values x, y, w and h specify where to draw the item.

Do not draw any background, this has already been done by the popup menu according to the current GUI style.

#### void QCustomMenuItem::setFont(const QFont & font) [virtual]

Sets the font of the custom menu item to font.

This function is called whenever the font in the popup menu changes. For menu items that show their own individual font entry, you want to ignore this.

# QSize QCustomMenuItem::sizeHint() [virtual]

Returns the size hint of this item.

# **QDesktopWidget Class Reference**

The QDesktopWidget class provides access to screen information on multi-head systems.

#include <qdesktopwidget.h>

Inherits QWidget [Widgets with Qt].

#### **Public Members**

- QDesktopWidget ()
- ~QDesktopWidget ()
- bool isVirtualDesktop () const
- int numScreens() const
- int **primaryScreen**() const
- int screenNumber (QWidget \* widget = 0) const
- int screenNumber (const QPoint & point) const
- QWidget \* screen (int screen = -1)
- const QRect & screenGeometry (int screen = -1) const

# **Detailed Description**

The QDesktopWidget class provides access to screen information on multi-head systems.

Systems with more than one graphics card and monitor can manage the physical screen space available either as multiple desktops, or as a large virtual desktop, which usually has the size of the bounding rectangle of all the screens (see isVirtualDesktop()). For an application, one of the available screens is the primary screen, i.e. the screen where the main widget resides (see primaryScreen()). All windows opened in the context of the application have to be constrained to the boundaries of the primary screen; for example, it would be inconvenient if a dialog box popped up on a different screen, or split over two screens.

The QDesktopWidget provides information about the geometry of the available screens with screenGeometry(). The number of screens available is returned by numScreens(). The screen number that a particular point or widget is located in is returned by screenNumber().

Widgets provided by Qt use this class, for example, to place tooltips, menus and dialog boxes according to the parent or application widget.

Applications can use this class to save window positions, or to place child widgets on one screen.

See also Advanced Widgets and Environment Classes.

#### **Member Function Documentation**

## QDesktopWidget::QDesktopWidget()

Creates the desktop widget.

If the system supports a virtual desktop, this widget will have the size of the virtual desktop; otherwise this widget will have the size of the primary screen.

#### QDesktopWidget::~QDesktopWidget()

Destroy the object and free allocated resources.

## bool QDesktopWidget::isVirtualDesktop() const

Returns TRUE if the system manages the available screens in a virtual desktop; otherwise returns FALSE.

For virtual desktops, screen() will always return the same widget. The size of the virtual desktop is the size of this desktop widget.

#### int QDesktopWidget::numScreens() const

Returns the number of available screens.

See also primaryScreen() [p. 10].

#### int QDesktopWidget::primaryScreen() const

Returns the index of the primary screen.

See also numScreens() [p. 10].

#### QWidget \* QDesktopWidget::screen (int screen = -1)

Returns a widget that represents the screen with index *screen*. This widget can be used to draw directly on the desktop, using an unclipped painter like this:

```
QPainter paint( QApplication::desktop()->screen( 0 ), TRUE );
paint.draw...
...
paint.end();
```

If the system uses a virtual desktop, the returned widget will have the geometry of the entire virtual desktop i.e. bounding every *screen*.

See also primaryScreen() [p. 10], numScreens() [p. 10] and isVirtualDesktop() [p. 10].

## const QRect & QDesktopWidget::screenGeometry (int screen = -1) const

Returns the geometry of the screen with index screen.

See also screenNumber() [p. 11].

### int QDesktopWidget::screenNumber(QWidget \* widget = 0) const

Returns the index of the screen that contains the largest part of *widget*, or -1 if the widget not on a screen. See also primaryScreen() [p. 10].

## int QDesktopWidget::screenNumber (const QPoint & point) const

This is an overloaded member function, provided for convenience. It behaves essentially like the above function. Returns the index of the screen that contains *point*, or -1 if no screen contains the point. See also primaryScreen() [p. 10].

The QDialog class is the base class of dialog windows.

#include <qdialog.h>

Inherits QWidget [Widgets with Qt].

Inherited by QColorDialog [p. 3], QErrorMessage [Additional Functionality with Qt], QFileDialog [p. 34], QFontDialog [Additional Functionality with Qt], QInputDialog [p. 54], QMessageBox [p. 101], QProgressDialog [p. 131], QTabDialog [p. 139] and QWizard [p. 171].

#### **Public Members**

- **QDialog** ( QWidget \* parent = 0, const char \* name = 0, bool modal = FALSE, WFlags f = 0 )
- **■** ~QDialog()
- enum **DialogCode** { Rejected, Accepted }
- int result() const
- virtual void **show** ()
- void **setOrientation** (Orientation orientation)
- Orientation orientation () const
- void **setExtension** ( QWidget \* extension )
- QWidget \* extension () const
- void setSizeGripEnabled (bool)
- bool isSizeGripEnabled() const

#### **Public Slots**

■ int exec()

# **Properties**

■ bool **sizeGripEnabled** — whether the size grip is enabled

#### **Protected Members**

■ void **setResult** (int i)

#### **Protected Slots**

- virtual void **done** (int r)
- virtual void accept ()
- virtual void reject()
- void **showExtension** (bool showIt)

# **Detailed Description**

The QDialog class is the base class of dialog windows.

A dialog window is a top-level window mostly used for short-term tasks and brief communications with the user. QDialogs may be modal or modeless. QDialogs can have default buttons, support extensibility and may provide a return value. QDialogs can have a QSizeGrip in their lower-right corner, using setSizeGripEnabled().

Note that QDialog uses the parent widget slightly differently from other classes in Qt. A dialog is always a top-level widget, but if it has a parent, its default location is centered on top of the parent. It will also share the parent's taskbar entry, for example.

There are three kinds of dialog that are useful:

- 1. A modal dialog is a dialog that blocks input to other visible windows in the same application: users must finish interacting with the dialog and close it before they can access any other window in the application. Modal dialogs have their own local event loop. Dialogs which are used to request a filename from the user or which are used to set application preferences are usually modal. Call exec() to display a modal dialog. When the user closes the dialog, exec() will provide a useful return value, and the flow of control will follow on from the exec() call at this time. Typically we connect a default button, e.g. "OK", to the accept() slot and a "Cancel" button to the reject() slot, to get the dialog to close and return the appropriate value. Alternatively you can connect to the done() slot, passing it Accepted or Rejected.
- 2. A **modeless** dialog is a dialog that operates independently of other windows in the same application. Find and replace dialogs in word-processors are often modeless to allow the user to interact with both the application's main window and the dialog. Call show() to display a modeless dialog. show() returns immediately so the flow of control will continue in the calling code. In practice you will often call show() and come to the end of the function in which show() is called with control returning to the main event loop.
- 3. A "semi-modal" dialog is a modal dialog that returns control to the caller immediately. Semi-modal dialogs do not have their own event loop, so you will need to call QApplication::processEvents() periodically to give the semi-modal dialog the opportunity to process its events. A progress dialog (e.g. QProgressDialog) is an example, where you only want the user to be able to interact with the progress dialog, e.g. to cancel a long running operation, but need to actually carry out the operation. Semi-modal dialogs are displayed by setting the modal flag to TRUE and calling the show() function.

**Default button** A dialog's "default" button is the button that's pressed when the user presses Enter or Return. This button is used to signify that the user accepts the dialog's settings and wishes to close the dialog. Use QPushButton::setDefault(), QPushButton::isDefault() and QPushButton::autoDefault() to set and control the dialog's default button.

**Extensibility** Extensibility is the ability to show the dialog in two ways: a partial dialog that shows the most commonly used options, and a full dialog that shows all the options. Typically an extensible dialog will initially appear as a partial dialog, but with a "More" button. If the user clicks the "More" button, the full dialog will appear. Extensibility is controlled with setExtension(), setOrientation() and showExtension().

**Return value (modal dialogs)** Modal dialogs are often used in situations where a return value is required; for example to indicate whether the user pressed OK or Cancel. A dialog can be closed by calling the accept() or the reject() slots,

and exec() will return Accepted or Rejected as appropriate. After the exec() call has returned the result is available from result().

#### **Examples**

A modal dialog.

A modeless dialog. After the show() call, control returns to the main event loop.

```
int main( int argc, char **argv )
{
    QApplication a( argc, argv );
    int scale = 10;

    LifeDialog *life = new LifeDialog( scale );
    a.setMainWidget( life );
    life->setCaption("Qt Example - Life");
    life->show();

    return a.exec();
}
```

See the QProgressDialog [p. 131] documentation for an example of a semi-modal dialog.

See also QTabDialog [p. 139], QWidget [Widgets with Qt], QProgressDialog [p. 131], GUI Design Handbook: Dialogs, Standard, Abstract Widget Classes and Dialog Classes.

# **Member Type Documentation**

## QDialog::DialogCode

The value returned by a modal dialog.

```
• QDialog::Accepted
```

• QDialog::Rejected

#### **Member Function Documentation**

# QDialog::QDialog (QWidget \* parent = 0, const char \* name = 0, bool modal = FALSE, WFlags f = 0)

Constructs a dialog called name, with parent parent.

If modal is FALSE (the default), the dialog is modeless and should be displayed with show(). If modal is TRUE and the dialog is displayed with exec(), the dialog is modal, i.e. blocks input to other windows. If modal is TRUE and the dialog is displayed show(), the dialog is semi-modal.

The widget flags f are passed on to the QWidget constructor.

If, for example, you don't want a What's this button in the titlebar of the dialog, pass WStyle\_Customize | WStyle NormalBorder | WStyle Title | WStyle SysMenu in f.

We recommend that you always pass a non-null parent.

See also QWidget::setWFlags() [Widgets with Qt] and Qt::WidgetFlags [Additional Functionality with Qt].

## QDialog::~QDialog()

Destroys the QDialog, deleting all its children.

## void QDialog::accept() [virtual protected slot]

Hides the modal dialog and sets the result code to Accepted.

See also reject() [p. 16] and done() [p. 15].

## void QDialog::done (int r) [virtual protected slot]

Hides the modal dialog and sets its result code to r. This uses the local event loop to finish, and exec() to return r.

If the dialog has the WDestructiveClose flag set, done() also deletes the dialog. If the dialog is the applications's main widget, the application terminates.

See also accept() [p. 15], reject() [p. 16], QApplication::mainWidget() [Additional Functionality with Qt] and QApplication::quit() [Additional Functionality with Qt].

Example: movies/main.cpp.

#### int QDialog::exec() [slot]

Executes a modal dialog. Control passes to the dialog until the user closes it, at which point the local event loop finishes and the function returns with the DialogCode result. Users will not be able to interact with any other window in the same application until they close this dialog. For a modeless or semi-modal dialog use show().

See also show() [p. 17] and result() [p. 16].

Examples: i18n/main.cpp, network/networkprotocol/view.cpp, qdir/qdir.cpp, showimg/showimg.cpp and wizard/main.cpp.

### QWidget \* QDialog::extension() const

Returns the dialog's extension or 0 if no extension has been defined.

See also setExtension() [p. 16].

#### bool QDialog::isSizeGripEnabled() const

Returns TRUE if the size grip is enabled; otherwise returns FALSE. See the "sizeGripEnabled" [p. 17] property for details.

### Orientation QDialog::orientation () const

Returns the dialog's extension orientation.

See also setOrientation() [p. 16].

#### void QDialog::reject() [virtual protected slot]

Hides the modal dialog and sets the result code to Rejected.

See also accept() [p. 15] and done() [p. 15].

#### int QDialog::result() const

Returns the modal dialog's result code, Accepted or Rejected.

#### void QDialog::setExtension ( QWidget \* extension )

Sets the widget, *extension*, to be the dialog's extension, deleting any previous extension. The dialog takes ownership of the extension. Note that if 0 is passed any existing extension will be deleted.

This function must only be called while the dialog is hidden.

See also showExtension() [p. 17], setOrientation() [p. 16] and extension() [p. 16].

### void QDialog::setOrientation ( Orientation orientation )

If *orientation* is Horizontal, the extension will be displayed to the right of the dialog's main area. If *orientation* is Vertical, the extension will be displayed below the dialog's main area.

See also orientation() [p. 16] and setExtension() [p. 16].

#### void QDialog::setResult(int i) [protected]

Sets the modal dialog's result code to i.

### void QDialog::setSizeGripEnabled ( bool )

Sets whether the size grip is enabled. See the "sizeGripEnabled" [p. 17] property for details.

#### void QDialog::show() [virtual]

Shows a modeless or semi-modal dialog. Control returns immediately to the calling code.

The dialog does not have a local event loop so you must call QApplication::processEvents() periodically to give the dialog the opportunity to process its events.

The dialog will be semi-modal if the modal flag was set to TRUE in the constructor.

#### Warning:

In Qt 2.x, calling show() on a modal dialog enters a local event loop, and works like exec(), but doesn't return the result code exec() returns. Trolltech has always warned that doing this is unwise.

See also exec() [p. 15].

Examples: movies/main.cpp, showimg/showimg.cpp, sql/overview/form1/main.cpp and tabdialog/main.cpp.

Reimplemented from QWidget [Widgets with Qt].

#### void QDialog::showExtension (bool showIt) [protected slot]

If showIt is TRUE, the dialog's extension is shown; otherwise the extension is hidden.

This slot is usually connected to the QButton::toggled() signal of a QPushButton.

If the dialog is not visible, or has no extension, nothing happens.

See also show() [p. 17], setExtension() [p. 16] and setOrientation() [p. 16].

# **Property Documentation**

## bool sizeGripEnabled

This property holds whether the size grip is enabled.

A QSizeGrip is placed in the bottom right corner of the dialog when this property is enabled. By default, the size grip is disabled.

Set this property's value with setSizeGripEnabled() and get this property's value with isSizeGripEnabled().

# **QDockArea Class Reference**

The QDockArea class manages and lays out QDockWindows.

#include <qdockarea.h>

Inherits QWidget [Widgets with Qt].

#### **Public Members**

- enum **HandlePosition** { Normal, Reverse }
- QDockArea (Orientation o, HandlePosition h = Normal, QWidget \* parent = 0, const char \* name = 0)
- ~QDockArea ()
- void moveDockWindow ( QDockWindow \* w, const QPoint & p, const QRect & r, bool swap )
- void removeDockWindow (QDockWindow \* w, bool makeFloating, bool swap, bool fixNewLines = TRUE)
- void moveDockWindow (QDockWindow \* w, int index = -1)
- bool hasDockWindow (QDockWindow \* w, int \* index = 0)
- Orientation orientation () const
- HandlePosition handlePosition () const
- bool isEmpty () const
- int count () const
- QPtrList < QDockWindow > dockWindowList () const
- bool isDockWindowAccepted ( QDockWindow \* dw )
- void setAcceptDockWindow (QDockWindow \* dw, bool accept)

### **Public Slots**

■ void **lineUp** (bool keepNewLines)

# **Properties**

- int **count** the number of dock windows in the dock area *(read only)*
- bool **empty** whether the dock area is empty (read only)
- HandlePosition handlePosition where the dock window splitter handle is placed in the dock area (read only)
- Orientation **orientation** the dock area's orientation (read only)

#### **Related Functions**

- QTextStream & **operator**<< (QTextStream & ts, const QDockArea & dockArea)
- QTextStream & operator>> (QTextStream & ts, QDockArea & dockArea)

## **Detailed Description**

The QDockArea class manages and lays out QDockWindows.

A QDockArea is a container which manages a list of QDockWindows which it lays out within its area. In cooperation with the QDockWindows it is responsible for the docking and undocking of QDockWindows and moving them inside the dock area. QDockAreas also handle the wrapping of QDockWindows to fill the available space as compactly as possible. QDockAreas can contain QToolBars since QToolBar is a QDockWindow subclass.

QMainWindow contains four QDockAreas which you can use for your QToolBars and QDockWindows, so in most situations you do not need to use the QDockArea class directly. Although QMainWindow contains support for its own dock areas but isn't convenient for adding new QDockAreas. If you need to create your own dock areas we suggest that you create a subclass of QWidget and add your QDockAreas to your subclass.

Lines. QDockArea uses the concept of lines. A line is a horizontal region which may contain dock windows side-by-side. A dock area may have room for more than one line. When dock windows are docked into a dock area they are usually added at the right hand side of the top-most line that has room (unless manually placed by the user). When users move dock windows they may leave empty lines or gaps in non-empty lines. Dock windows can be lined up to minimize wasted space using the lineUp() function.

The QDockArea class maintains a position list of all its child dock windows. Dock windows are added to a dock area from position 0 onwards. Dock windows are laid out sequentially in position order from left to right, and in the case of multiple lines of dock windows, from top to bottom. If a dock window is floated it still retains its position since this is where the window will return if the user double clicks its caption. A dock window's position can be determined with hasDockWindow(). The position can be changed with moveDockWindow().

To dock or undock a dock window use QDockWindow::dock() and QDockWindow::undock() respectively. If you want to control which dock windows can dock in a dock area use setAcceptDockWindow(). To see if a dock area contains a particular dock window use hasDockWindow(); to see how many dock windows a dock area contains use count().

The streaming operators can write the positions of the dock windows in the dock area to a QTextStream. The positions can be read back later to restore the saved positions.

Save the positions to a QTextStream:

ts <> \*myDockArea;

See also Main Window and Related Classes.

# **Member Type Documentation**

#### QDockArea::HandlePosition

A dock window has two kinds of handles, the dock window handle used for dragging the dock window, and the splitter handle used to resize the dock window in relation to other dock windows using a splitter. (The splitter handle is only visible for docked windows.)

This enum specifies where the dock window splitter handle is placed in the dock area.

- QDockArea::Normal The splitter handles of dock windows are placed at the right or bottom.
- QDockArea::Reverse The splitter handles of dock windows are placed at the left or top.

#### **Member Function Documentation**

# QDockArea::QDockArea (Orientation o, HandlePosition h = Normal, QWidget \* parent = 0, const char \* name = 0)

Constructs a QDockArea with orientation o, HandlePosition h, parent parent and name name.

## QDockArea::~QDockArea()

Destroys the dock area and all the dock windows docked in the dock area.

Does not affect any floating dock windows or dock windows in other dock areas, even if they first appeared in this dock area. Floating dock windows are effectively top level windows and are not child windows of the dock area. When a floating dock window is docked (dragged into a dock area) its parent becomes the dock area.

### int QDockArea::count() const

Returns the number of dock windows in the dock area. See the "count" [p. 22] property for details.

#### QPtrList<QDockWindow> QDockArea::dockWindowList () const

Returns a list of the dock windows in the dock area.

#### HandlePosition QDockArea::handlePosition() const

Returns where the dock window splitter handle is placed in the dock area. See the "handlePosition" [p. 22] property for details.

#### bool QDockArea::hasDockWindow ( QDockWindow \* w, int \* index = 0 )

Returns TRUE if the dock area contains the dock window w, otherwise returns FALSE. If a non-null pointer is passed as *index* it will be set as follows: if the dock area contains the dock window *index* is set to w's position; otherwise *index* is set to -1.

#### bool QDockArea::isDockWindowAccepted (QDockWindow \* dw)

Returns TRUE if dock window *dw* could be docked into the dock area; otherwise returns FALSE. See also setAcceptDockWindow() [p. 21].

QDockArea Class Reference 21

### bool QDockArea::isEmpty() const

Returns TRUE if the dock area is empty; otherwise returns FALSE. See the "empty" [p. 22] property for details.

#### void QDockArea::lineUp ( bool keepNewLines ) [slot]

Lines up the dock windows in this dock area to minimize wasted space. If *keepNewLines* is TRUE, only space within lines is cleaned up. If *keepNewLines* is FALSE the number of lines might be changed.

## void QDockArea::moveDockWindow ( QDockWindow \* w, int index = -1 )

Moves the QDockWindow w within the dock area. If w is not already docked in this area, w is docked first. If index is -1 or larger than the number of docked widgets, w is appended at the end, otherwise it is inserted at the position index.

# void QDockArea::moveDockWindow ( QDockWindow \* w, const QPoint & p, const QRect & r, bool swap )

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Moves the dock window w inside the dock area where p is the new position (in global screen coordinates), r is the suggested rectangle of the dock window and swap specifies whether or not the orientation of the docked widget needs to be changed.

This function is used internally by QDockWindow. You shouldn't need to call it yourself.

#### Orientation QDockArea::orientation () const

Returns the dock area's orientation. See the "orientation" [p. 22] property for details.

## void QDockArea::removeDockWindow ( QDockWindow \* w, bool makeFloating, bool swap, bool fixNewLines = TRUE )

Removes the dock window w from the dock area. If makeFloating is TRUE, w gets floated, and if swap is TRUE, the orientation of w gets swapped. If fixNewLines is TRUE (the default) newlines in the area will be fixed.

You should never need to call this function yourself. Use QDockWindow::dock() and QDockWindow::undock() instead.

#### void QDockArea::setAcceptDockWindow ( QDockWindow \* dw, bool accept )

If accept is TRUE dock window dw can be docked in the dock area. If accept is FALSE dock window dw cannot be docked in the dock area.

See also isDockWindowAccepted() [p. 20].

22

# **Property Documentation**

#### int count

This property holds the number of dock windows in the dock area.

Get this property's value with count().

### bool empty

This property holds whether the dock area is empty.

Get this property's value with isEmpty().

#### HandlePosition handlePosition

This property holds where the dock window splitter handle is placed in the dock area.

The default position is Normal.

Get this property's value with handlePosition().

#### Orientation orientation

This property holds the dock area's orientation.

There is no default value; the orientation is specified in the constructor.

Get this property's value with orientation().

### **Related Functions**

#### QTextStream & operator << (QTextStream & ts, const QDockArea & dockArea)

Writes the layout of the dock windows in dock area dockArea to the text stream ts.

See also operator>>() [p. 22].

#### QTextStream & operator>> (QTextStream & ts, QDockArea & dockArea)

Reads the layout description of the dock windows in dock area *dockArea* from the text stream *ts* and restores it. The layout description must have been previously written by the operator <<() function.

See also operator << () [p. 22].

# **QDockWindow Class Reference**

The QDockWindow class provides a widget which can be docked inside a QDockArea or floated as a top level window on the desktop.

#include <qdockwindow.h>
Inherits QFrame [Widgets with Qt].
Inherited by QToolBar [p. 149].

#### **Public Members**

- enum Place { InDock, OutsideDock }
- enum **CloseMode** { Never = 0, Docked = 1, Undocked = 2, Always = Docked | Undocked }
- **QDockWindow** (Place p = InDock, QWidget \* parent = 0, const char \* name = 0, WFlags f = 0)
- virtual void **setWidget** (QWidget \* w)
- QWidget \* widget () const
- Place place () const
- QDockArea \* **area** () const
- virtual void **setCloseMode** (int m)
- bool isCloseEnabled() const
- int closeMode() const
- virtual void **setResizeEnabled** (bool b)
- virtual void **setMovingEnabled** (bool b)
- bool isResizeEnabled () const
- bool isMovingEnabled () const
- virtual void **setHorizontallyStretchable** (bool b)
- virtual void **setVerticallyStretchable** (bool b)
- bool isHorizontallyStretchable() const
- bool isVerticallyStretchable() const
- void setHorizontalStretchable (bool b) (obsolete)
- void setVerticalStretchable (bool b) (obsolete)
- bool isHorizontalStretchable () const (obsolete)
- bool isVerticalStretchable () const (obsolete)
- bool isStretchable() const
- virtual void **setOffset** (int o)
- int offset () const
- virtual void **setFixedExtentWidth** (int w)

- virtual void **setFixedExtentHeight** (int h)
- QSize **fixedExtent** () const
- virtual void **setNewLine** (bool b)
- bool newLine () const
- Qt::Orientation orientation () const
- QBoxLayout \* **boxLayout**()
- virtual void **setOpaqueMoving** (bool b)
- bool opaqueMoving () const

#### **Public Slots**

- virtual void **undock** ( OWidget \* w )
- virtual void dock()
- virtual void **setOrientation** (Orientation o)

# **Signals**

- void **orientationChanged** (Orientation o)
- void **placeChanged** (QDockWindow::Place p)
- void visibilityChanged (bool visible)

# **Properties**

- int closeMode the close mode of a dock window
- bool **horizontallyStretchable** whether the dock window is horizontally stretchable
- bool movingEnabled whether the user can move the dock window within the dock area, move the dock window to another dock area, or float the dock window
- bool **newLine** whether the dock window prefers to start a new line in the dock area
- int offset the dock window's preferred offset from the dock area's left edge (top edge for vertical dock areas)
- bool opaqueMoving whether the dock window will be shown normally whilst it is being moved
- Place place whether the dock window is in a dock area (read only)
- bool **resizeEnabled** whether the dock window is resizeable
- bool **stretchable** whether the dock window is stretchable in the current orientation() (read only)
- bool **verticallyStretchable** whether the dock window is vertically stretchable

# **Detailed Description**

The QDockWindow class provides a widget which can be docked inside a QDockArea or floated as a top level window on the desktop.

This class handles moving, resizing, docking and undocking dock windows. QToolBar is a subclass of QDockWindow so the functionality provided for dock windows is available with the same API for toolbars.

If the user drags the dock window into the dock area the dock window will be docked. If the user drags the dock area outside any dock areas the dock window will be undocked (floated) and will become a top level window. Double

clicking a floating dock window's titlebar will dock the dock window to the last dock area it was docked in. Double clicking a docked dock window's handle will undock (float) the dock window. Single clicking a docked dock window's handle will minimize the dock window (only its handle will appear, below the menu bar). Single clicking the minimized handle will restore the dock window to the last dock area that it was docked in. If the user clicks the close button (which appears on floating dock windows by default) the dock window will disappear. You can control whether or not a dock window has a close button with setCloseMode().

QMainWindow provides four dock areas (top, left, right and bottom) which can be used by dock windows. For many applications using the dock areas provided by QMainWindow will be sufficient. (See the QDockArea documentation if you want to create your own dock areas.) In QMainWindow a right-click popup menu (the dock window menu) is available which lists dock windows and can be used to show or hide them.

When you construct a dock window you *must* pass it a QDockArea or a QMainWindow as its parent if you want it docked. Pass 0 for the parent if you want it floated.

```
QToolBar *fileTools = new QToolBar( this, "File Actions" );
moveDockWindow( fileTools, Left );
```

In the example above we create a new QToolBar in the constructor of a QMainWindow subclass (so that the *this* pointer points to the QMainWindow). By default the toolbar will be added to the Top dock area, but we've moved it to the Left dock area.

A dock window is often used to contain a single widget. In these cases the widget can be set by calling setWidget(). If you're constructing a dock window that contains multiple widgets, e.g. a toolbar, arrange the widgets within a box layout inside the dock window. To do this use the boxLayout() function to get a pointer to the dock window's box layout, then add widgets to the layout using the box layout's QBoxLayout::addWidget() function. The dock window will dynamically set the orientation of the layout to be vertical or horizontal as necessary, although you can control this yourself with setOrientation().

Although a common use of dock windows is for toolbars, they can be used with any widgets. (See the *Qt Designer* and *Qt Linguist* applications, for example.) When using larger widgets it may make sense for the dock window to be resizable by calling setResizeEnabled(). Resizable dock windows are given splitter-like handles to allow the user to resize them within their dock area. When resizable dock windows are undocked they become top level windows and can be resized like any other top level windows, e.g. by dragging a corner or edge.

Dock windows can be docked and undocked using dock() and undock(). A dock window's orientation can be set with setOrientation(). You can also use QDockArea::moveDockWindow(). If you're using a QMainWindow, QMainWindow::moveDockWindow() and QMainWindow::removeDockWindow() are available.

A dock window can have some preferred settings, for example, you can set a preferred offset from the left edge (or top edge for vertical dock areas) of the dock area using setOffset(). If you'd prefer a dock window to start on a new line when it is docked use setNewLine(). The setFixedExtentWidth() and setFixedExtentHeight() functions can be used to define the dock window's preferred size, and the setHorizontallyStretchable() and setVerticallyStretchable() functions set whether the dock window can be stretched or not. Dock windows can be moved by default, but this can be changed with setMovingEnabled(). When a dock window is moved it is shown as a rectangular outline, but it can be shown normally using setOpaqueMoving().

When a dock window's visibility changes, i.e. it is shown or hidden, the visibilityChanged() signal is emitted. When a dock window is docked or undocked the placeChanged() signal is emitted.

See also Main Window and Related Classes.

## **Member Type Documentation**

#### QDockWindow::CloseMode

This enum type specifies when (if ever) a dock window has a close button.

- QDockWindow:: Never The dock window never has a close button and cannot be closed by the user.
- QDockWindow::Docked The dock window has a close button only when docked.
- QDockWindow: :Undocked The dock window has a close button only when floating.
- QDockWindow::Always The dock window always has a close button.

Note that dock windows can always be minimized if the user clicks their dock window handle when they are docked.

#### QDockWindow::Place

This enum specifies the possible locations for a QDockWindow:

- QDockWindow::InDock Inside a QDockArea.
- QDockWindow::OutsideDock Floating as a top level window on the desktop.

#### **Member Function Documentation**

# QDockWindow::QDockWindow (Place p = InDock, QWidget \* parent = 0, const char \* name = 0, WFlags f = 0)

Constructs a QDockWindow with parent parent, name name and widget flags f.

If *p* is InDock, the dock window is docked into a dock area and *parent must* be a QDockArea or a QMainWindow. If the *parent* is a QMainWindow the dock window will be docked in the main window's Top dock area.

If p is OutsideDock, the parent must be 0 and the dock window is created as a floating window.

We recommend creating the dock area InDock with a QMainWindow as parent then calling QMainWindow::moveDockWindow() to move the dock window where you want it.

#### QDockArea \* QDockWindow::area() const

Returns the dock area in which this dock window is docked, or 0 if the dock window is floating.

#### QBoxLayout \* QDockWindow::boxLayout ()

Returns the layout which is used for adding widgets to the dock window. The layout's orientation is set automatically to match the orientation of the dock window. You can add widgets to the layout using the box layout's QBoxLayout::addWidget() function.

If the dock window only needs to contain a single widget use setWidget() instead.

See also setWidget() [p. 30] and setOrientation() [p. 30].

#### int QDockWindow::closeMode () const

Returns the close mode of a dock window. See the "closeMode" [p. 31] property for details.

#### void QDockWindow::dock() [virtual slot]

Docks the dock window into the last dock area in which it was docked.

If the dock window has no last dock area (e.g. it was created as a floating window and has never been docked), or if the last dock area it was docked in does not exist (e.g. the dock area has been deleted), nothing happens.

See also undock() [p. 30].

#### QSize QDockWindow::fixedExtent() const

Returns the dock window's preferred size (fixed extent).

See also setFixedExtentWidth() [p. 29] and setFixedExtentHeight() [p. 29].

#### bool QDockWindow::isCloseEnabled() const

Returns TRUE if the dock window has a close button; otherwise returns FALSE. The result depends on the dock window's Place and its CloseMode.

See also closeMode [p. 31].

#### bool QDockWindow::isHorizontalStretchable () const

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

#### bool QDockWindow::isHorizontallyStretchable () const

Returns TRUE if the dock window is horizontally stretchable; otherwise returns FALSE. See the "horizontallyStretchable" [p. 31] property for details.

#### bool QDockWindow::isMovingEnabled () const

Returns TRUE if the user can move the dock window within the dock area, move the dock window to another dock area, or float the dock window; otherwise returns FALSE. See the "movingEnabled" [p. 31] property for details.

## bool QDockWindow::isResizeEnabled () const

Returns TRUE if the dock window is resizeable; otherwise returns FALSE. See the "resizeEnabled" [p. 32] property for details.

### bool QDockWindow::isStretchable() const

Returns TRUE if the dock window is stretchable in the current orientation(); otherwise returns FALSE. See the "stretchable" [p. 32] property for details.

#### bool QDockWindow::isVerticalStretchable () const

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

#### bool QDockWindow::isVerticallyStretchable () const

Returns TRUE if the dock window is vertically stretchable; otherwise returns FALSE. See the "verticallyStretchable" [p. 32] property for details.

#### bool QDockWindow::newLine () const

Returns TRUE if the dock window prefers to start a new line in the dock area; otherwise returns FALSE. See the "newLine" [p. 31] property for details.

#### int QDockWindow::offset() const

Returns the dock window's preferred offset from the dock area's left edge (top edge for vertical dock areas). See the "offset" [p. 31] property for details.

#### bool QDockWindow::opaqueMoving () const

Returns TRUE if the dock window will be shown normally whilst it is being moved; otherwise returns FALSE. See the "opaqueMoving" [p. 32] property for details.

#### Qt::Orientation QDockWindow::orientation () const

Returns the orientation of the dock window.

See also orientationChanged() [p. 28].

## void QDockWindow::orientationChanged (Orientation o) [signal]

This signal is emitted when the orientation of the dock window is changed. The new orientation is o.

#### Place QDockWindow::place () const

Returns TRUE if the dock window is in a dock area; otherwise returns FALSE. See the "place" [p. 32] property for details.

### void QDockWindow::placeChanged (QDockWindow::Place p) [signal]

This signal is emitted when the dock window is docked (p is InDock) or undocked (p is OutsideDock).

See also QDockArea::moveDockWindow() [p. 21], QDockArea::removeDockWindow() [p. 21], QMainWindow::moveDockWindow() [p. 69] and QMainWindow::removeDockWindow() [p. 70].

## void QDockWindow::setCloseMode ( int m ) [virtual]

Sets the close mode of a dock window to m. See the "closeMode" [p. 31] property for details.

#### void QDockWindow::setFixedExtentHeight(int h) [virtual]

Sets the dock window's preferred height for its fixed extent (size) to h.

See also setFixedExtentWidth() [p. 29].

## void QDockWindow::setFixedExtentWidth (int w) [virtual]

Sets the dock window's preferred width for its fixed extent (size) to w.

See also setFixedExtentHeight() [p. 29].

## void QDockWindow::setHorizontalStretchable ( bool b )

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

#### void QDockWindow::setHorizontallyStretchable (bool b) [virtual]

Sets whether the dock window is horizontally stretchable to *b*. See the "horizontallyStretchable" [p. 31] property for details.

#### void QDockWindow::setMovingEnabled ( bool b ) [virtual]

Sets whether the user can move the dock window within the dock area, move the dock window to another dock area, or float the dock window to b. See the "movingEnabled" [p. 31] property for details.

#### void QDockWindow::setNewLine (bool b) [virtual]

Sets whether the dock window prefers to start a new line in the dock area to b. See the "newLine" [p. 31] property for details.

#### void QDockWindow::setOffset(int o) [virtual]

Sets the dock window's preferred offset from the dock area's left edge (top edge for vertical dock areas) to o. See the "offset" [p. 31] property for details.

### void QDockWindow::setOpaqueMoving(bool b) [virtual]

Sets whether the dock window will be shown normally whilst it is being moved to *b*. See the "opaqueMoving" [p. 32] property for details.

#### void QDockWindow::setOrientation ( Orientation o ) [virtual slot]

Sets the orientation of the dock window to o. The orientation is propagated to the layout boxLayout().

#### void QDockWindow::setResizeEnabled ( bool b ) [virtual]

Sets whether the dock window is resizeable to b. See the "resizeEnabled" [p. 32] property for details.

#### void QDockWindow::setVerticalStretchable ( bool b )

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

#### void QDockWindow::setVerticallyStretchable ( bool b ) [virtual]

Sets whether the dock window is vertically stretchable to b. See the "vertically Stretchable" [p. 32] property for details.

#### void QDockWindow::setWidget ( QWidget \* w ) [virtual]

Sets the dock window's main widget to w.

See also boxLayout() [p. 26].

#### void QDockWindow::undock ( QWidget \* w ) [virtual slot]

Undocks the QDockWindow from its current dock area, if it is docked; otherwise does nothing.

Do not pass any w paramenter, it is for internal use only.

See also dock() [p. 27], QDockArea::moveDockWindow() [p. 21], QDockArea::removeDockWindow() [p. 21], QMainWindow::moveDockWindow() [p. 69] and QMainWindow::removeDockWindow() [p. 70].

#### void QDockWindow::visibilityChanged (bool visible) [signal]

This signal is emitted if the visibility of the dock window is changed. If *visible* is TRUE, the QDockWindow is now visible, otherwise it has been hidden.

A dock window can be hidden if it has a close button which the user has clicked. In the case of a QMainWindow a dock window can have its visibility changed (hidden or shown) by clicking its name in the dock window menu that lists the QMainWindow's dock windows.

### QWidget \* QDockWindow::widget () const

Returns the dock window's main widget.

See also setWidget() [p. 30].

## **Property Documentation**

#### int closeMode

This property holds the close mode of a dock window.

Defines when (if ever) the dock window has a close button. The choices are Never, Docked (i.e. only when docked), Undocked (only when undocked, i.e. floated) or Always.

The default is Never.

Set this property's value with setCloseMode() and get this property's value with closeMode().

## bool horizontallyStretchable

This property holds whether the dock window is horizontally stretchable.

A dock window is horizontally stretchable if you call setHorizontallyStretchable(TRUE) or setResizeEnabled(TRUE).

See also resizeEnabled [p. 32].

Set this property's value with setHorizontallyStretchable() and get this property's value with isHorizontallyStretchable().

#### bool movingEnabled

This property holds whether the user can move the dock window within the dock area, move the dock window to another dock area, or float the dock window.

This property is TRUE by default.

Set this property's value with setMovingEnabled() and get this property's value with isMovingEnabled().

#### bool newLine

This property holds whether the dock window prefers to start a new line in the dock area.

The default is FALSE, i.e. the dock window doesn't require a new line in the dock area.

Set this property's value with setNewLine() and get this property's value with newLine().

#### int offset

This property holds the dock window's preferred offset from the dock area's left edge (top edge for vertical dock areas). The default is 0.

Set this property's value with setOffset() and get this property's value with offset().

#### bool opaqueMoving

This property holds whether the dock window will be shown normally whilst it is being moved.

If this property is FALSE, (the default), the dock window will be represented by an outline rectangle whilst it is being moved.

Set this property's value with setOpaqueMoving() and get this property's value with opaqueMoving().

### Place place

This property holds whether the dock window is in a dock area.

The place() function returns the current place of the dock window. This is either InDock or OutsideDock.

See also QDockArea::moveDockWindow() [p. 21], QDockArea::removeDockWindow() [p. 21], QMainWindow::moveDockWindow() [p. 69] and QMainWindow::removeDockWindow() [p. 70].

Get this property's value with place().

#### bool resizeEnabled

This property holds whether the dock window is resizeable.

A resizeable dock window can be resized using splitter-like handles inside a dock area and like every other top level window when floating.

A dock window is both horizontally and vertically stretchable if you call or setResizeEnabled(TRUE).

This property is FALSE by default.

See also verticallyStretchable [p. 32] and horizontallyStretchable [p. 31].

Set this property's value with setResizeEnabled() and get this property's value with isResizeEnabled().

#### bool stretchable

This property holds whether the dock window is stretchable in the current orientation().

This property can be set using setHorizontallyStretchable() and setVerticallyStretchable(), or with setResizeEnabled(). See also resizeEnabled [p. 32].

Get this property's value with isStretchable().

#### bool verticallyStretchable

This property holds whether the dock window is vertically stretchable.

 $A \ dock \ window \ is \ horizontally \ stretchable \ if \ you \ call \ set Vertically Stretchable (TRUE) \ or \ set Resize Enabled (TRUE).$ 

See also resizeEnabled [p. 32].

 $Set\ this\ property's\ value\ with\ set Vertically Stretchable ()\ and\ get\ this\ property's\ value\ with\ is Vertically Stretchable ().$ 

The QFileDialog class provides dialogs that allow users to select files or directories.

```
#include <qfiledialog.h>
```

Inherits QDialog [p. 12].

#### **Public Members**

- **QFileDialog** (const QString & dirName, const QString & filter = QString::null, QWidget \* parent = 0, const char \* name = 0, bool modal = FALSE)
- **QFileDialog** (QWidget \* parent = 0, const char \* name = 0, bool modal = FALSE)
- ~QFileDialog ()
- QString **selectedFile** () const
- QString **selectedFilter** () const
- virtual void **setSelectedFilter** (const QString & mask)
- virtual void **setSelectedFilter** (int n)
- void **setSelection** (const QString & filename)
- void **selectAll** (bool b)
- QStringList **selectedFiles** () const
- QString dirPath () const
- void **setDir** (const QDir & dir)
- const QDir \* dir() const
- void setShowHiddenFiles (bool s)
- bool showHiddenFiles () const
- void rereadDir()
- void resortDir()
- enum Mode { AnyFile, ExistingFile, Directory, ExistingFiles, DirectoryOnly }
- void **setMode** (Mode)
- Mode **mode** () const
- enum ViewMode { Detail, List }
- enum **PreviewMode** { NoPreview, Contents, Info }
- void **setViewMode** (ViewMode m)
- ViewMode viewMode () const
- void **setPreviewMode** ( PreviewMode m )
- PreviewMode previewMode () const
- bool isInfoPreviewEnabled () const

- bool isContentsPreviewEnabled () const
- void setInfoPreviewEnabled (bool)
- void setContentsPreviewEnabled (bool)
- void **setInfoPreview** ( OWidget \* w, OFilePreview \* preview )
- void **setContentsPreview** ( QWidget \* w, QFilePreview \* preview )
- OUrl url () const
- void addFilter (const QString & filter)

### **Public Slots**

- void **setDir** (const QString & pathstr)
- void **setUrl** (const QUrlOperator & url)
- void **setFilter** (const QString & newFilter)
- void **setFilters** (const QString & filters)
- void **setFilters** (const char \*\* types)
- void **setFilters** (const QStringList &)

# **Signals**

- void **fileHighlighted** (const QString &)
- void **fileSelected** (const QString &)
- void **filesSelected** (const QStringList &)
- void **dirEntered** (const QString &)
- void **filterSelected** (const QString &)

#### **Static Public Members**

- QString **getOpenFileName** (const QString & startWith = QString::null, const QString & filter = QString::null, QWidget \* parent = 0, const char \* name = 0, const QString & caption = QString::null, QString \* selectedFilter = 0, bool resolveSymlinks = TRUE)
- QString **getSaveFileName** (const QString & startWith = QString::null, const QString & filter = QString::null, QWidget \* parent = 0, const char \* name = 0, const QString & caption = QString::null, QString \* selectedFilter = 0, bool resolveSymlinks = TRUE)
- QString **getExistingDirectory** (const QString & dir = QString::null, QWidget \* parent = 0, const char \* name = 0, const QString & caption = QString::null, bool dirOnly = TRUE, bool resolveSymlinks = TRUE)
- QStringList **getOpenFileNames** (const QString & filter = QString::null, const QString & dir = QString::null, QWidget \* parent = 0, const char \* name = 0, const QString & caption = QString::null, QString \* selectedFilter = 0, bool resolveSymlinks = TRUE)
- void **setIconProvider** (QFileIconProvider \* provider)
- QFileIconProvider \* iconProvider ()

## **Properties**

- bool contentsPreview whether the file dialog offers the possibility of previewing the contents of the currently selected file
- QString **dirPath** the file dialog's working directory (read only)
- bool **infoPreview** whether the file dialog offers the possibility to preview information about the currently selected file
- Mode **mode** the file dialog's mode
- PreviewMode **previewMode** the preview mode for the file dialog
- QString **selectedFile** the name of the selected file *(read only)*
- QStringList **selectedFiles** a list of selected files *(read only)*
- QString **selectedFilter** the filter which the user has selected in the file dialog (read only)
- bool **showHiddenFiles** whether hidden files are shown in the file dialog
- ViewMode viewMode the file dialog's view mode

### **Protected Members**

- void addWidgets (QLabel \* l, QWidget \* w, QPushButton \* b)
- void **addToolButton** (QButton \* b, bool separator = FALSE)
- void **addLeftWidget** ( OWidget \* w )
- void addRightWidget ( QWidget \* w)

# **Detailed Description**

The OFileDialog class provides dialogs that allow users to select files or directories.

The QFileDialog class enables a user to traverse their file system in order to select one or many files or a directory.

The easiest way to create a QFileDialog is to use the static functions. On Windows, these static functions will call the native Windows file dialog and on Mac OS X, these static function will call the native Mac OS X file dialog.

In the above example, a modal QFileDialog is created using a static function. The startup directory is set to "/home". The file filter is set to "Images (\*.png \*.xpm \*.jpg)". The parent of the file dialog is set to this and it is given the identification name - "open file dialog". The caption at the top of file dialog is set to "Choose a file".

You can create your own QFileDialog without using the static functions. By calling setMode(), you can set what can be returned by the QFileDialog.

```
QFileDialog* fd = new QFileDialog( this, "file dialog", TRUE );
fd->setMode( QFileDialog::AnyFile );
```

In the above example, the mode of the file dialog is set to AnyFile, meaning that the user can select any file, or even specify a file that doesn't exist. This mode is useful for creating a "File Save As" file dialog. Use ExistingFile if the user must select an existing file or Directory if only a directory must be selected. (See the QFileDialog::Mode enum for the complete list of modes.)

You can retrieve the dialog's mode with mode(). Use setFilter() to set the dialog's file filter, e.g.

```
fd->setFilter( "Images (*.png *.xpm *.jpg)" );
```

In the above example, the filter is set to "Images (\*.png \*.xpm \*.jpg)", this means that only files with the extension png, xpm or jpg files will be visible in the QFileDialog. You can apply several filters by using setFilters() and add additional filters with addFilter(). Use setSelectedFilter() to select one of the filters you've given as the file dialog's default filter. Whenever the user changes the filter the filterSelected() signal is emitted.

The file dialog has two view modes, QFileDialog::List which simply lists file and directory names and QFileDialog::Detail which displays additional information beside each name, e.g. file size, modification date, etc. Set the move with setViewMode().

```
fd->setViewMode( OFileDialog::Detail );
```

The last important function you will need to use when creating your own file dialog is selectedFile().

```
QString fileName;
if ( fd->exec() == QDialog::Accepted )
    fileName = fd->selectedFile();
```

In the above example, a modal file dialog is created and shown. If the user clicked OK, then the file they selected is put in fileName.

If you are using the ExistingFiles mode then you will need to use selectedFiles() which will return the selected files in a QStringList.

The dialog's working directory can be set with setDir(). The display of hidden files is controlled with setShowHidden-Files(). The dialog can be forced to re-read the directory with rereadDir() and re-sort the directory with resortDir(). All the files in the current directory can be selected with selectAll().

# Creating and using preview widgets

There are two kinds of preview widgets that can be used with QFileDialogs: *content* preview widgets and *information* preview widgets. They are created and used in the same way except that the function names differ, e.g. setContentsPreview() and setInfoPreview().

A preview widget is a widget that is placed inside a QFileDialog so that the user can see either the contents of the file, or information about the file.

```
class Preview : public QLabel, public QFilePreview
{
public:
    Preview( QWidget *parent=0 ) : QLabel( parent ) {}

    void previewUrl( const QUrl &u )
    {
```

```
QString path = u.path();
    QPixmap pix( path );
    if ( pix.isNull() )
        setText( "This is not a pixmap" );
    else
        setPixmap( pix );
    }
};
```

In the above snippet, we create a preview widget which inherits from QLabel and QFilePreview. File preview widgets *must* inherit from QFilePreview.

Inside the class we reimplement QFilePreview::previewUrl(), this is where we determine what happens when a file is selected. In the case above we only show a preview of the file if it is a valid pixmap. Now we tell a file dialog that we have a preview widget that we want it to use.


```
Preview* p = new Preview;

QFileDialog* fd = new QFileDialog( this );
fd->setContentsPreviewEnabled( TRUE );
fd->setContentsPreview( p, p );
fd->setPreviewMode( QFileDialog::Contents );
fd->show();
```

The first line creates an instance of our preview widget. We then create our file dialog and call setContentsPreviewEnabled( TRUE ), this tell the file dialog to preview the contents of the currently selected file. We then call setContentsPreview() — note that we pass the same preview widget twice. Finally, before showing the file dialog, we call setPreviewMode() setting the mode to *Contents* which will show the contents the file that the user has selected.

If you create another preview widget that is used for displaying information about a file, create it in the same way as we have the contents preview widget and call setInfoPreviewEnabled(), and setInfoPreview(). Then the user will be able to switch between the two preview modes.

For more information about creating a QFilePreview widget see QFilePreview.



See also Dialog Classes.

# **Member Type Documentation**

# QFileDialog::Mode

This enum is used to indicate what the user may select in the file dialog, i.e. what the dialog will return if the user clicks OK.

- QFileDialog::AnyFile The name of a file, whether it exists or not.
- QFileDialog::ExistingFile The name of a single existing file.
- QFileDialog::Directory The name of a directory. Both files and directories are displayed.
- QFileDialog::DirectoryOnly The name of a directory. The file dialog will only display directories.
- QFileDialog::ExistingFiles The names of zero or more existing files.

See setMode().

#### QFileDialog::PreviewMode

This enum describes the preview mode of the file dialog.

- QFileDialog::NoPreview No preview is shown at all.
- QFileDialog::Contents Show a preview of the contents of the current file using the contents preview widget.
- QFileDialog::Info Show information about the current file using the info preview widget.

See setPreviewMode(), setContentsPreview() and setInfoPreview().

#### QFileDialog::ViewMode

This enum describes the view mode of the file dialog, i.e. what information about each file it will display.

- QFileDialog::List Display file and directory names with icons.
- QFileDialog::Detail Display file and directory names with icons plus additional information, e.g. file size, modification date.

See setViewMode().

#### **Member Function Documentation**

QFileDialog::QFileDialog (const QString & dirName, const QString & filter = QString::null, QWidget \* parent = 0, const char \* name = 0, bool modal = FALSE)

Constructs a file dialog with the parent *parent*, the name *name* If *modal* is TRUE then the file dialog is modal; otherwise it is non-modal.

If *dirName* is specified then it will be used as the dialog's working directory, i.e. it will be the directory that is shown when the dialog appears. If *filter* is specified it will be used as the dialog's file filter.

# QFileDialog::QFileDialog (QWidget \* parent = 0, const char \* name = 0, bool modal = FALSE)

Constructs a file dialog with the parent, parent, and the name, name. If modal is TRUE then the file dialog is modal; otherwise it is non-modal.

# QFileDialog::~QFileDialog()

Destroys the file dialog.

# void QFileDialog::addFilter ( const QString & filter )

Adds the filter to the list of filters and makes it the current one.

```
QFileDialog* fd = new QFileDialog( this );
fd->addFilter( "Images (*.png *.jpg *.xpm)" );
fd->show();
```

In the above example, a file dialog is created, and the file filter - "Images (\*.png \*.jpg \*.xpm)" is added and is set as the current filter. The original filter - "All Files (\*)" is still available.

See also setFilter() [p. 46] and setFilters() [p. 47].

# void QFileDialog::addLeftWidget ( QWidget \* w ) [protected]

Adds the widget w to the left-hand side of the file dialog.

See also addRightWidget() [p. 40], addWidgets() [p. 40] and addToolButton() [p. 40].

# void QFileDialog::addRightWidget ( QWidget \* w ) [protected]

Adds the widget w to the right-hand side of the file dialog.

See also addLeftWidget() [p. 40], addWidgets() [p. 40] and addToolButton() [p. 40].

# void QFileDialog::addToolButton ( QButton \* b, bool separator = FALSE ) [protected]

Adds the tool button b to the row of tool buttons at the top of the file dialog. The button is appended to the right of this row. If *separator* is TRUE, a small space is inserted between the last button of the row and the new button b.

See also addWidgets() [p. 40], addLeftWidget() [p. 40] and addRightWidget() [p. 40].

# void QFileDialog::addWidgets ( QLabel \* 1, QWidget \* w, QPushButton \* b ) [protected]

```
MyFileDialog::MyFileDialog( QWidget* parent, const char* name ) :
    QFileDialog( parent, name )
{
```

```
QLabel* label = new QLabel( "Added widgets", this );
QLineEdit* lineedit = new QLineEdit( this );
QToolButton* toolbutton = new QToolButton( this );
addWidgets( label, lineedit, toolbutton );
}
```

Adds the specified widgets to the bottom of the file dialog. The label l is placed underneath the "file name" and the "file types" labels. The widget w is placed underneath the file types combobox. The button b is placed underneath the cancel pushbutton.

If you don't want to have one of the widgets to be added then just pass 0 instead of a label, widget or pushbutton.

Every time you call this function, a new row of widgets will be added to the bottom of the file dialog.

See also addToolButton() [p. 40], addLeftWidget() [p. 40] and addRightWidget() [p. 40].

# const QDir \* QFileDialog::dir() const

Returns the current directory shown in the file dialog.

See also setDir() [p. 46].

#### void QFileDialog::dirEntered ( const QString & ) [signal]

This signal is emitted when the user enters a directory.

See also dir() [p. 41].

#### **QString QFileDialog::dirPath () const**

Returns the file dialog's working directory. See the "dirPath" [p. 50] property for details.

#### void QFileDialog::fileHighlighted (const QString &) [signal]

This signal is emitted when the user highlights a file.

See also fileSelected() [p. 41] and filesSelected() [p. 41].

#### void QFileDialog::fileSelected ( const QString & ) [signal]

This signal is emitted when the user selects a file.

See also filesSelected() [p. 41], fileHighlighted() [p. 41] and selectedFile [p. 51].

#### void QFileDialog::filesSelected (const QStringList &) [signal]

This signal is emitted when the user selects one or more files in ExistingFiles mode.

See also fileSelected() [p. 41], fileHighlighted() [p. 41] and selectedFiles [p. 51].

# void QFileDialog::filterSelected ( const QString & ) [signal]

This signal is emitted when the user selects a filter.

See also selectedFilter [p. 51].

```
QString QFileDialog::getExistingDirectory (const QString & dir = QString::null, QWidget * parent = 0, const char * name = 0, const QString & caption = QString::null, bool dirOnly = TRUE, bool resolveSymlinks = TRUE) [static]
```

This is a convenience static function that will return an existing directory selected by the user.

This function creates a modal file dialog with parent *parent*, and name *name*. If a parent is specified the dialog will be shown centered over the parent.

The dialog's working directory is set to *dir*, and the caption is set to *caption*. Either of these may be QString::null in which case the current directory and a default caption will be used respectively.

If dirOnly is TRUE, then only directories will be shown in the file dialog; otherwise both directories and files will be shown.

Under Unix/X11, the normal behavior of the file dialog is to resolve and follow symlinks. For example, if /usr/tmp is a symlink to /var/tmp, the file dialog will change to /var/tmp after entering /usr/tmp. If resolveSymlinks is FALSE, the file dialog will treat symlinks as regular directories.

See also getOpenFileName() [p. 42], getOpenFileNames() [p. 43] and getSaveFileName() [p. 43].

```
QString QFileDialog::getOpenFileName (const QString & startWith = QString::null, const QString & filter = QString::null, QWidget * parent = 0, const char * name = 0, const QString & caption = QString::null, QString * selectedFilter = 0, bool resolveSymlinks = TRUE) [static]
```

This is a convenience static function that returns an existing file selected by the user. If the user pressed cancel, it returns a null string.

The function creates a modal file dialog with parent *parent*, and name *name*. If a parent is specified, then the dialog will be shown centered over the parent.

The file dialog's working directory will be set to *startWith*. If *startWith* includes a file name, the file will be selected. The filter is set to *filter* so that only those files which match the filter are shown. The filter selected is set to *selectedFilter*. The parameters *startWith*, *selectedFilter* and *filter* may be QString::null.

The dialog's caption is set to caption. If caption is not specified then a default caption will be used.

Under Windows and Mac OS X, this static function will use the native file dialog and not a QFileDialog, unless the style of the application is set to something other than the native style.

Under Unix/X11, the normal behavior of the file dialog is to resolve and follow symlinks. For example, if /usr/tmp is a symlink to /var/tmp, the file dialog will change to /var/tmp after entering /usr/tmp. If resolveSymlinks is FALSE, the file dialog will treat symlinks as regular directories.

See also getOpenFileNames() [p. 43], getSaveFileName() [p. 43] and getExistingDirectory() [p. 42].

Examples: action/application.cpp, addressbook/mainwindow.cpp, application/application.cpp, helpviewer/helpwindow.cpp, mdi/application.cpp, qwerty/qwerty.cpp and showimg/showimg.cpp.

```
QStringList QFileDialog::getOpenFileNames (const QString & filter = QString::null, const QString & dir = QString::null, QWidget * parent = 0, const char * name = 0, const QString & caption = QString::null, QString * selectedFilter = 0, bool resolveSymlinks = TRUE) [static]
```

This is a convenience static function that will return one or more existing files as selected by the user.

The function creates a modal file dialog with parent *parent*, and name *name*. If a parent is specified, then the dialog will be shown centered over the parent.

The file dialog's working directory will be set to *dir*. If *dir* includes a file name, the file will be selected. The filter is set to *filter* so that only those files which match the filter are shown. The filter selected is set to *selectedFilter*. The parameters *dir*, *selectedFilter* and *filter* may be QString::null.

The dialog's caption is set to caption. If caption is not specified then a default caption will be used.

Under Windows and Mac OS X, this static function will use the native file dialog and not a QFileDialog, unless the style of the application is set to something other than the native style.

Under Unix/X11, the normal behavior of the file dialog is to resolve and follow symlinks. For example, if /usr/tmp is a symlink to /var/tmp, the file dialog will change to /var/tmp after entering /usr/tmp. If resolveSymlinks is FALSE, the file dialog will treat symlinks as regular directories.

See also getOpenFileName() [p. 42], getSaveFileName() [p. 43] and getExistingDirectory() [p. 42].

```
QString QFileDialog::getSaveFileName (const QString & startWith = QString::null, const QString & filter = QString::null, QWidget * parent = 0, const char * name = 0, const QString & caption = QString::null, QString * selectedFilter = 0, bool resolveSymlinks = TRUE) [static]
```

This is a convenience static function that will return a file name selected by the user. The file does not have to exist.

It creates a modal file dialog with parent *parent*, and name *name*. If a parent is specified, then the dialog will be shown centered over the parent.

The file dialog's working directory will be set to *startWith*. If *startWith* includes a file name, the file will be selected. The filter is set to *filter* so that only those files which match the filter are shown. The filter selected is set to *selectedFilter*. The parameters *startWith*, *selectedFilter* and *filter* may be QString::null.

The dialog's caption is set to caption. If caption is not specified then a default caption will be used.

Under Windows and Mac OS X, this static function will use the native file dialog and not a QFileDialog, unless the style of the application is set to something other than the native style.

Under Unix/X11, the normal behavior of the file dialog is to resolve and follow symlinks. For example, if /usr/tmp is a symlink to /var/tmp, the file dialog will change to /var/tmp after entering /usr/tmp. If resolveSymlinks is FALSE, the file dialog will treat symlinks as regular directories.

See also getOpenFileName() [p. 42], getOpenFileNames() [p. 43] and getExistingDirectory() [p. 42].

Examples: action/application.cpp, addressbook/mainwindow.cpp, application/application.cpp, mdi/application.cpp, qmag/qmag.cpp, qwerty/qwerty.cpp and showimg/showimg.cpp.

### QFileIconProvider \* QFileDialog::iconProvider () [static]

Returns a pointer to the icon provider currently set on the file dialog. By default there is no icon provider, and this function returns 0.

See also setIconProvider() [p. 47] and QFileIconProvider [p. 52].

#### bool QFileDialog::isContentsPreviewEnabled () const

Returns TRUE if the file dialog offers the possibility of previewing the contents of the currently selected file; otherwise returns FALSE. See the "contentsPreview" [p. 50] property for details.

# bool QFileDialog::isInfoPreviewEnabled () const

Returns TRUE if the file dialog offers the possibility to preview information about the currently selected file; otherwise returns FALSE. See the "infoPreview" [p. 50] property for details.

#### Mode QFileDialog::mode() const

Returns the file dialog's mode. See the "mode" [p. 50] property for details.

#### PreviewMode QFileDialog::previewMode () const

Returns the preview mode for the file dialog. See the "previewMode" [p. 50] property for details.

# void QFileDialog::rereadDir()

Rereads the current directory shown in the file dialog.

The only time you will need to call this function is if the contents of the directory change and you wish to refresh the file dialog to reflect the change.

See also resortDir() [p. 45].

#### void QFileDialog::resortDir()

Re-sorts the displayed directory.

See also rereadDir() [p. 45].

# void QFileDialog::selectAll ( bool b )

If b is TRUE then all the files in the current directory are selected; otherwise, they are deselected.

#### QString QFileDialog::selectedFile() const

Returns the name of the selected file. See the "selectedFile" [p. 51] property for details.

# QStringList QFileDialog::selectedFiles() const

Returns a list of selected files. See the "selectedFiles" [p. 51] property for details.

# QString QFileDialog::selectedFilter() const

Returns the filter which the user has selected in the file dialog. See the "selectedFilter" [p. 51] property for details.

# void QFileDialog::setContentsPreview ( QWidget \* w, QFilePreview \* preview )

Sets the widget to be used for displaying the contents of the file to the widget w and a preview of those contents to the QFilePreview preview.

Normally you would create a preview widget that derives from both QWidget and QFilePreview, so you should pass the same widget twice.

```
class Preview : public QLabel, public QFilePreview
{
  public:
    Preview( QWidget *parent=0 ) : QLabel( parent ) {}

    void previewUrl( const QUrl &u )
    {
        QString path = u.path();
        QPixmap pix( path );
}
```

See also contentsPreview [p. 50], setInfoPreview() [p. 47] and previewMode [p. 50].

Example: qdir/qdir.cpp.

#### void QFileDialog::setContentsPreviewEnabled (bool)

Sets whether the file dialog offers the possibility of previewing the contents of the currently selected file. See the "contentsPreview" [p. 50] property for details.

# void QFileDialog::setDir (const QDir & dir)

Sets the file dialog's working directory to dir.

See also dir() [p. 41].

### void QFileDialog::setDir ( const QString & pathstr ) [slot]

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Sets the file dialog's working directory to pathstr.

See also dir() [p. 41].

#### void QFileDialog::setFilter ( const QString & newFilter ) [slot]

Sets the filter used in the file dialog to newFilter.

If newFilter contains a pair of parentheses containing one or more of anything\*something separated by spaces or by semi-colons then only the text contained in the parentheses is used as the filter. This means that these calls are all equivalent:

```
fd->setFilter( "All C++ files (*.cpp *.cc *.C *.cxx *.c++)" );
fd->setFilter( "*.cpp *.cc *.C *.cxx *.c++" );
fd->setFilter( "All C++ files (*.cpp;*.cc;*.C;*.cxx;*.c++)" );
fd->setFilter( "*.cpp;*.cc;*.C;*.cxx;*.c++" );
```

See also setFilters() [p. 47].

# void QFileDialog::setFilters ( const QString & filters ) [slot]

Sets the filters used in the file dialog to filters. Each group of filters must be separated by ;;.

```
QString types("*.png;;*.xpm;;*.jpg");
QFileDialog fd = new QFileDialog( this );
fd->setFilters( types );
fd->show();
```

# void QFileDialog::setFilters ( const char \*\* types ) [slot]

This is an overloaded member function, provided for convenience. It behaves essentially like the above function. *types* must be a null-terminated list of strings.

#### void QFileDialog::setFilters ( const QStringList & ) [slot]

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

# void QFileDialog::setIconProvider ( QFileIconProvider \* provider ) [static]

Sets the OFileIconProvider used on the file dialog to the OFileIconProvider specified by provider.

The default is that there is no QFileIconProvider and QFileDialog just draws a folder icon next to each directory and nothing next to the files.

See also QFileIconProvider [p. 52] and iconProvider() [p. 44].

Example: showing/main.cpp.

#### void QFileDialog::setInfoPreview ( QWidget \* w, QFilePreview \* preview )

Sets the widget to be used for displaying information about the file to the widget w and a preview of that information to the QFilePreview preview.

Normally you would create a preview widget that derives from both QWidget and QFilePreview, so you should pass the same widget twice.

```
class Preview : public QLabel, public QFilePreview
{
public:
    Preview( QWidget *parent=0 ) : QLabel( parent ) {}
```

```
void previewUrl( const QUrl &u )
          QString path = u.path();
          QPixmap pix( path );
          if ( pix.isNull() )
              setText( "This is not a pixmap" );
          else
              setText( "This is a pixmap" );
  };
//...
int main( int argc, char** argv )
 Preview* p = new Preview;
 QFileDialog* fd = new QFileDialog( this );
 fd->setInfoPreviewEnabled( TRUE );
 fd->setInfoPreview( p, p );
 fd->setPreviewMode( QFileDialog::Info );
 fd->show();
```

See also setContentsPreview() [p. 45], infoPreview [p. 50] and previewMode [p. 50].

#### void QFileDialog::setInfoPreviewEnabled ( bool )

Sets whether the file dialog offers the possibility to preview information about the currently selected file. See the "infoPreview" [p. 50] property for details.

#### void QFileDialog::setMode ( Mode )

Sets the file dialog's mode. See the "mode" [p. 50] property for details.

#### void QFileDialog::setPreviewMode ( PreviewMode m )

Sets the preview mode for the file dialog to m. See the "previewMode" [p. 50] property for details.

#### void QFileDialog::setSelectedFilter (const QString & mask) [virtual]

Sets the current filter selected in the file dialog to the first one that contains the text mask.

#### void QFileDialog::setSelectedFilter(int n) [virtual]

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Sets the current filter selected in the file dialog to the *n* filter in the filter list.

See also filterSelected() [p. 42], selectedFilter [p. 51], selectedFiles [p. 51] and selectedFile [p. 51].

# void QFileDialog::setSelection ( const QString & filename )

Sets the default selection to *filename*. If *filename* is absolute, setDir() is also called to set the file dialog's working directory to the filename's directory.

Example: qdir/qdir.cpp.

## void QFileDialog::setShowHiddenFiles ( bool s )

Sets whether hidden files are shown in the file dialog to s. See the "showHiddenFiles" [p. 51] property for details.

# void QFileDialog::setUrl (const QUrlOperator & url) [slot]

Sets the file dialog's working directory to the directory specified at url.

See also url() [p. 49].

# void QFileDialog::setViewMode (ViewMode m)

Sets the file dialog's view mode to m. See the "viewMode" [p. 51] property for details.

# bool QFileDialog::showHiddenFiles () const

Returns TRUE if hidden files are shown in the file dialog; otherwise returns FALSE. See the "showHiddenFiles" [p. 51] property for details.

#### QUrl QFileDialog::url() const

Returns the URL of the current working directory in the file dialog.

See also setUrl() [p. 49].

Example: network/networkprotocol/view.cpp.

#### ViewMode QFileDialog::viewMode () const

Returns the file dialog's view mode. See the "viewMode" [p. 51] property for details.

# **Property Documentation**

#### bool contentsPreview

This property holds whether the file dialog offers the possibility of previewing the contents of the currently selected file.

The default is FALSE.

See also setContentsPreview() [p. 45] and infoPreview [p. 50].

Set this property's value with setContentsPreviewEnabled() and get this property's value with isContentsPreviewEnabled().

# **QString dirPath**

This property holds the file dialog's working directory.

Get this property's value with dirPath().

See also dir() [p. 41] and setDir() [p. 46].

#### bool infoPreview

This property holds whether the file dialog offers the possibility to preview information about the currently selected file.

The default is FALSE.

Set this property's value with setInfoPreviewEnabled() and get this property's value with isInfoPreviewEnabled().

#### Mode mode

This property holds the file dialog's mode.

The default mode is ExistingFile.

Set this property's value with setMode() and get this property's value with mode().

#### PreviewMode previewMode

This property holds the preview mode for the file dialog.

If you set the mode to be a mode other than *NoPreview*, then use setInfoPreview() or setContentsPreview() to set the dialog's preview widget to your preview widget and enable the preview widget(s) with setInfoPreviewEnabled() or setContentsPreviewEnabled().

See also infoPreview [p. 50], contentsPreview [p. 50] and viewMode [p. 51].

Set this property's value with setPreviewMode() and get this property's value with previewMode().

# **QString** selectedFile

This property holds the name of the selected file.

If a file was selected selected File contains the file's name including its absolute path; otherwise selected File is empty.

See also QString::isEmpty() [Datastructures and String Handling with Qt], selectedFiles [p. 51] and selectedFilter [p. 51].

Get this property's value with selectedFile().

## **QStringList selectedFiles**

This property holds a list of selected files.

If one or more files were selected selectedFiles contains the names of the selected files including their absolute paths. If no files were selected or the mode wasn't ExistingFiles selectedFiles is an empty list.

It is more convenient to use selectedFile() if the mode is ExistingFile, Directory or DirectoryOnly.

See also selectedFile [p. 51], selectedFilter [p. 51] and QValueList::empty() [Datastructures and String Handling with Qt].

Get this property's value with selectedFiles().

#### **QString** selectedFilter

This property holds the filter which the user has selected in the file dialog.

Get this property's value with selectedFilter().

See also filterSelected() [p. 42], selectedFiles [p. 51] and selectedFile [p. 51].

### bool showHiddenFiles

This property holds whether hidden files are shown in the file dialog.

The default is FALSE, i.e. don't show hidden files.

Set this property's value with setShowHiddenFiles() and get this property's value with showHiddenFiles().

#### ViewMode viewMode

This property holds the file dialog's view mode.

If you set the view mode to be *Detail* (the default), then you will see the file's details, such as the size of the file and the date the file was last modified alongside the file.

If you set the view mode to be *List*, then you will just see a list of the files and folders.

See QFileDialog::ViewMode

Set this property's value with setViewMode() and get this property's value with viewMode().

# **QFileIconProvider Class Reference**

The QFileIconProvider class provides icons for QFileDialog to use.

#include <qfiledialog.h>

Inherits QObject [Additional Functionality with Qt].

### **Public Members**

- **QFileIconProvider** ( QObject \* parent = 0, const char \* name = 0 )
- virtual const QPixmap \* pixmap (const QFileInfo & info)

# **Detailed Description**

The QFileIconProvider class provides icons for QFileDialog to use.

By default QFileIconProvider is not used, but any application or library can subclass it, reimplement pixmap() to return a suitable icon, and make all QFileDialog objects use it by calling the static function QFileDialog::setIconProvider().

It is advisable to make all the icons that QFileIconProvider returns be the same size or at least the same width. This makes the list view look much better.

See also QFileDialog [p. 34] and Miscellaneous Classes.

### **Member Function Documentation**

QFileIconProvider::QFileIconProvider (QObject \* parent = 0, const char \* name = 0)

Constructs an empty file icon provider with the parent parent and name name.

#### const QPixmap \* QFileIconProvider::pixmap (const QFileInfo & info) [virtual]

Returns a pointer to a pixmap that should be used for visualizing the file with the information info.

If pixmap() returns 0, OFileDialog draws the default pixmap.

The default implementation returns particular icons for files, directories, link-files and link-directories. It returns a blank "icon" for other types.

If you return a pixmap here, it should measure 16x16.

# **QInputDialog Class Reference**

The QInputDialog class provides a simple convenience dialog to get a single value from the user.

```
#include <qinputdialog.h>
Inherits QDialog [p. 12].
```

### **Static Public Members**

- QString **getText** (const QString & caption, const QString & label, QLineEdit::EchoMode mode = QLineEdit::Normal, const QString & text = QString::null, bool \* ok = 0, QWidget \* parent = 0, const char \* name = 0)
- int **getInteger** (const QString & caption, const QString & label, int num = 0, int from = -2147483647, int to = 2147483647, int step = 1, bool \* ok = 0, QWidget \* parent = 0, const char \* name = 0)
- double **getDouble** (const QString & caption, const QString & label, double num = 0, double from = -2147483647, double to = 2147483647, int decimals = 1, bool \* ok = 0, QWidget \* parent = 0, const char \* name = 0)
- QString **getItem** (const QString & caption, const QString & label, const QStringList & list, int current = 0, bool editable = TRUE, bool \* ok = 0, QWidget \* parent = 0, const char \* name = 0)

# **Detailed Description**

The QInputDialog class provides a simple convenience dialog to get a single value from the user.

The QInputDialog is a simple dialog which can be used if you need to get a single input value from the user. The input value can be a string, a number or an item from a list. A label has to be set to tell the user what they should input.

Four static convenience functions are provided: getText(), getInteger(), getDouble() and getItem(). All the functions can be used in a similar way, for example:

See also Dialog Classes.

#### **Member Function Documentation**

```
double QInputDialog::getDouble (const QString & caption, const QString & label, double num = 0, double from = -2147483647, double to = 2147483647, int decimals = 1, bool * ok = 0, QWidget * parent = 0, const char * name = 0) [static]
```

Static convenience function to get a floating point number from the user. *caption* is the text which is displayed in the title bar of the dialog. *label* is the text which is shown to the user (it should mention what they should input), *num* is the default floating point number that the line edit will be set to. *from* and *to* are the minimum and maximum values the user may choose, and *decimals* is the maximum number of decimal places the number may have.

If *ok* is not-null it will be set to TRUE if the user pressed OK and FALSE if the user pressed Cancel. The dialog's parent is *parent*; the dialog is called *name*. The dialog will be modal.

This method returns the floating point number which has been entered by the user.

Use this static method like this:

```
int QInputDialog::getInteger (const QString & caption, const QString & label, int num = 0, int from = -2147483647, int to = 2147483647, int step = 1, bool * ok = 0, QWidget * parent = 0, const char * name = 0) [static]
```

Static convenience function to get an integer input from the user. *caption* is the text which is displayed in the title bar of the dialog. *label* is the text which is shown to the user (it should mention what they should input), *num* is the default number which the spinbox will be set to. *from* and *to* are the minimum and maximum values the user may choose, and *step* is the amount by which the values change as the user presses the arrow buttons to increment or decrement the value.

If *ok* is not-null it will be set to TRUE if the user pressed OK and FALSE if the user pressed Cancel. The dialog's parent is *parent*; the dialog is called *name*. The dialog will be modal.

This method returns the number which has been entered by the user.

Use this static method like this:

```
;// user entered something and pressed OK
else
;// user pressed Cancel
```

```
QString QInputDialog::getItem (const QString & caption, const QString & label, const QStringList & list, int current = 0, bool editable = TRUE, bool * ok = 0, QWidget * parent = 0, const char * name = 0) [static]
```

Static convenience function to let the user select an item from a string list. *caption* is the text which is displayed in the title bar of the dialog. *label* is the text which is shown to the user (it should mention what they should input). *list* is the string list which is inserted into the combobox, and *current* is the number of the item which should be the current item. If *editable* is TRUE the user can enter their own text; if *editable* is FALSE the user may only select one of the existing items.

If *ok* is not-null it will be set to TRUE if the user pressed OK and FALSE if the user pressed Cancel. The dialog's parent is *parent*; the dialog is called *name*. The dialog will be modal.

This method returns the text of the current item, or if *editable* is TRUE, the current text of the combobox.

Use this static method like this:

QString QInputDialog::getText (const QString & caption, const QString & label, QLineEdit::EchoMode mode = QLineEdit::Normal, const QString & text = QString::null, bool \* ok = 0, OWidget \* parent = 0, const char \* name = 0) [static]

Static convenience function to get a string from the user. *caption* is the text which is displayed in the title bar of the dialog. *label* is the text which is shown to the user (it should mention what they should input), *text* the default text which is placed in the line edit. The *mode* is the echo mode the line edit will use. If *ok* is not-null it will be set to TRUE if the user pressed OK and FALSE if the user pressed Cancel. The dialog's parent is *parent*; the dialog is called *name*. The dialog will be modal.

This method returns the text which has been entered in the line edit.

Use this static method like this:

```
;// user entered something and pressed OK
else
;// user entered nothing or pressed Cancel
```

Example: network/ftpclient/ftpmainwindow.cpp.

# **QMainWindow Class Reference**

The QMainWindow class provides a main application window, with a menu bar, dock windows (e.g. for toolbars), and a status bar.

#include <qmainwindow.h>

Inherits QWidget [Widgets with Qt].

#### **Public Members**

- QMainWindow (QWidget \* parent = 0, const char \* name = 0, WFlags f = WType TopLevel)
- ~QMainWindow ()
- QMenuBar \* menuBar () const
- QStatusBar \* statusBar () const
- QToolTipGroup \* toolTipGroup () const
- virtual void **setCentralWidget** (QWidget \* w)
- QWidget \* centralWidget () const
- virtual void **setDockEnabled** (Dock dock, bool enable)
- bool isDockEnabled (Dock dock) const
- bool isDockEnabled (QDockArea \* area) const
- virtual void **setDockEnabled** (QDockWindow \* dw, Dock dock, bool enable)
- bool isDockEnabled (QDockWindow \* tb, Dock dock) const
- bool isDockEnabled (QDockWindow \* dw, QDockArea \* area) const
- virtual void **addDockWindow** (QDockWindow \* dockWindow, Dock edge = DockTop, bool newLine = FALSE)
- virtual void **addDockWindow** (QDockWindow \* dockWindow, const QString & label, Dock edge = DockTop, bool newLine = FALSE)
- virtual void **moveDockWindow** (QDockWindow \* dockWindow, Dock edge = DockTop)
- virtual void **moveDockWindow** (QDockWindow \* dockWindow, Dock edge, bool nl, int index, int extraOffset = -1)
- virtual void **removeDockWindow** ( QDockWindow \* dockWindow )
- bool rightJustification() const
- bool usesBigPixmaps() const
- bool usesTextLabel() const
- bool dockWindowsMovable () const
- bool opaqueMoving () const
- bool getLocation (QDockWindow \* dw, Dock & dock, int & index, bool & nl, int & extraOffset) const
- QPtrList < QDockWindow > dockWindows (Dock dock) const
- QPtrList < QDockWindow > dockWindows () const

- void **lineUpDockWindows** (bool keepNewLines = FALSE)
- bool isDockMenuEnabled () const
- bool hasDockWindow (QDockWindow \* dw)
- void addToolBar (QDockWindow \*, Dock = DockTop, bool newLine = FALSE) (obsolete)
- void addToolBar (QDockWindow \*, const QString & label, Dock = DockTop, bool newLine = FALSE) (obsolete)
- void moveToolBar (QDockWindow \*, Dock = DockTop) (obsolete)
- void moveToolBar (QDockWindow \*, Dock, bool nl, int index, int extraOffset = -1) (obsolete)
- void removeToolBar (QDockWindow \*) (obsolete)
- bool toolBarsMovable () const (obsolete)
- QPtrList < QToolBar > toolBars (Dock dock) const
- void lineUpToolBars (bool keepNewLines = FALSE) (obsolete)
- QDockArea \* leftDock () const
- QDockArea \* rightDock () const
- QDockArea \* **topDock** () const
- QDockArea \* **bottomDock** () const
- virtual bool isCustomizable () const
- bool appropriate (QDockWindow \* dw) const
- enum **DockWindows** { OnlyToolBars, NoToolBars, AllDockWindows }
- QPopupMenu \* createDockWindowMenu (DockWindows dockWindows = AllDockWindows) const

# **Public Slots**

- virtual void **setRightJustification** (bool)
- virtual void **setUsesBigPixmaps** (bool)
- virtual void **setUsesTextLabel** (bool)
- virtual void **setDockWindowsMovable** (bool)
- virtual void **setOpaqueMoving** (bool)
- virtual void **setDockMenuEnabled** (bool b)
- virtual void whatsThis()
- virtual void **setAppropriate** (QDockWindow \* dw, bool a)
- virtual void **customize**()
- void setToolBarsMovable (bool) (obsolete)

# Signals

- void **pixmapSizeChanged** (bool)
- void usesTextLabelChanged (bool)
- void **dockWindowPositionChanged** ( QDockWindow \* dockWindow )
- void toolBarPositionChanged (QToolBar \*) (obsolete)

# **Properties**

- bool dockWindowsMovable whether the dock windows are movable
- bool **opaqueMoving** whether dock windows are moved opaquely
- bool **rightJustification** whether the main window right-justifies its dock windows
- bool usesBigPixmaps whether big pixmaps are enabled
- bool usesTextLabel whether text labels for toolbar buttons are enabled

#### **Protected Members**

■ virtual void **childEvent** (QChildEvent \* e)

# **Protected Slots**

- virtual void setUpLayout()
- virtual bool **showDockMenu** (const QPoint & globalPos)
- void menuAboutToShow()

# **Related Functions**

- QTextStream & operator << (QTextStream & ts, const QMainWindow & mainWindow)
- QTextStream & operator>> (QTextStream & ts, QMainWindow & mainWindow)

# **Detailed Description**

The QMainWindow class provides a main application window, with a menu bar, dock windows (e.g. for toolbars), and a status bar.

Main windows are most often used to provide menus, toolbars and a status bar around a large central widget, such as a text edit or drawing canvas. QMainWindow is usually subclassed since this makes it easier to encapsulate the central widget, menus and toolbars as well as the window's state. Subclassing makes it possible to create the slots that are called when the user clicks menu items or toolbar buttons. You can also create main windows using *Qt Designer*. We'll briefly review adding menu items and toolbar buttons then describe the facilities of QMainWindow itself.

```
QMainWindow *mw = new QMainWindow;
QTextEdit *edit = new QTextEdit( mw, "editor" );
edit->setFocus();
mw->setCaption( "Main Window" );
mw->setCentralWidget( edit );
mw->show();
```

QMainWindows may be created in their own right as shown above. The central widget is set with setCentralWidget(). Popup menus can be added to the default menu bar, widgets can be added to the status bar, toolbars and dock windows can be added to any of the dock areas.

```
ApplicationWindow * mw = new ApplicationWindow();
mw->setCaption( "Qt Example - Application" );
mw->show();
```

In the extract above ApplicationWindow is a subclass of QMainWindow that we must write for ourselves; this is the usual approach to using QMainWindow. (The source for the extracts in this description are taken from application/main.cpp, application/application.cpp, action/main.cpp, and action/application.cpp)

When subclassing we add the menu items and toolbars in the subclass's constructor. If we've created a QMainWindow instance directly we can add menu items and toolbars just as easily by passing the QMainWindow instance as the parent instead of the *this* pointer.

```
QPopupMenu * help = new QPopupMenu( this );
menuBar()->insertItem( "&Help", help );
help->insertItem( "&About", this, SLOT(about()), Key_F1 );
```

Here we've added a new menu with one menu item. The menu has been inserted into the menu bar that QMainWindow provides by default and which is accessible through the menuBar() function. The slot will be called when the menu item is clicked.

This extract shows the creation of a toolbar with one toolbar button. QMainWindow supplies four dock areas for toolbars. When a toolbar is created as a child of a QMainWindow (or derived class) instance it will be placed in a dock area (the Top dock area by default). The slot will be called when the toolbar button is clicked. Any dock window can be added to a dock area either using addDockWindow(), or by creating a dock window with the QMainWindow as the parent.

```
e = new QTextEdit( this, "editor" );
e->setFocus();
setCentralWidget( e );
statusBar()->message( "Ready", 2000 );
```

Having created the menus and toolbar we create an instance of the large central widget, give it the focus and set it as the main window's central widget. In the example we've also set the status bar, accessed via the statusBar() function, to an initial message which will be displayed for two seconds. Note that you can add additional widgets to the status bar, for example labels, to show further status information. See the QStatusBar documentation for details, particularly the addWidget() function.

Often we want to synchronize a toolbar button with a menu item. For example, if the user clicks a 'bold' toolbar button we want the 'bold' menu item to be checked. This synchronization can be achieved automatically by creating actions and adding the actions to the toolbar and menu.

```
QAction * fileOpenAction;
```

Here we create an action with an icon which will be used in any menu and toolbar that the action is added to. We've also given the action a menu name, '&Open', and a keyboard shortcut. The connection that we have made will be used when the user clicks either the menu item *or* the toolbar button.

```
QPopupMenu * file = new QPopupMenu( this );
menuBar()->insertItem( "&File", file );
fileOpenAction->addTo( file );
```

The extract above shows the creation of a popup menu. We add the menu to the QMainWindow's menu bar and add our action.

```
QToolBar * fileTools = new QToolBar( this, "file operations" );
fileTools->setLabel( "File Operations" );
fileOpenAction->addTo( fileTools );
```

Here we create a new toolbar as a child of the QMainWindow and add our action to the toolbar.

We'll now explore the functionality offered by QMainWindow.

The main window will take care of the dock areas, and the geometry of the central widget, but all other aspects of the central widget are left to you. QMainWindow automatically detects the creation of a menu bar or status bar if you specify the QMainWindow as parent, or you can use the provided menuBar() and statusBar() functions. The functions menuBar() and statusBar() create a suitable widget if one doesn't exist, and update the window's layout to make space.

QMainWindow provides a QToolTipGroup connected to the status bar. The function toolTipGroup() provides access to the default QToolTipGroup. It isn't possible to set a different tool tip group.

New dock windows and toolbars can be added to a QMainWindow using addDockWindow(). Dock windows can be moved using moveDockWindow() and removed with removeDockWindow(). QMainWindow allows default dock window (toolbar) docking in all its dock areas (top, left, right, bottom). You can use setDockEnabled() to enable and disable docking areas for dock windows. When adding or moving dock windows you can specify their 'edge' (dock area). The currently available edges are: Top, Left, Right, Bottom, Minimized (effectively a 'hidden' dock area) and TornOff (floating). See Qt::Dock for an explanation of these areas. Note that the \*ToolBar functions are included for backward compatibility, all new code should use the \*DockWindow functions. QToolbar is a subclass of QDockWindow so all functions that work with dock windows work on toolbars in the same way. If the user minimizes a dock window by clicking the dock window's window handle then the dock window is moved to the Minimized dock area. If the user clicks the close button, then the dock window is hidden and can only be shown again by using the dock window menu.

Some functions change the appearance of a QMainWindow globally:

- QDockWindow::setHorizontalStretchable() and QDockWindow::setVerticalStretchable() are used to make specific dock windows or toolbars stretchable.
- setUsesBigPixmaps() is used to set whether tool buttons should draw small or large pixmaps (see QIconSet for more information).
- setUsesTextLabel() is used to set whether tool buttons should display a textual label in addition to pixmaps (see QToolButton for more information).

The user can drag dock windows into any enabled docking area. Dock windows can also be dragged within a docking area, for example to rearrange the order of some toolbars. Dock windows can also be dragged outside any docking

area (undocked or 'floated'). Being able to drag dock windows can be enabled (the default) and disabled using setDockWindowsMovable(). If the user clicks the close button on a floating dock window then the dock window will disappear. To get the dock window back the user must right click a dock area, to pop up the dock window menu, then click the name of the dock window they want to restore. Visible dock windows have a tick by their name in the dock window menu. The dock window menu is created automatically as required by createDockWindowMenu(). Since it may not always be appropriate for a dock window to appear on this menu the setAppropriate() function is used to inform the main window whether or not the dock window menu should include a particular dock window. Double clicking a dock window handle (usually on the left-hand side of the dock window) undocks (floats) the dock window. Double clicking a floating dock window's titlebar will dock the floating dock window.

The Minimized edge is a hidden dock area. If this dock area is enabled the user can hide (minimize) a dock window or show (restore) a minimized dock window by clicking the dock window handle. If the user hovers the mouse cursor over one of the handles, the caption of the dock window is displayed in a tool tip (see QDockWindow::caption() or QToolBar::label()), so if you enable the Minimized dock area, it is best to specify a meaningful caption or label for each dock window. To minimize a dock window programmatically use moveDockWindow() with an edge of Minimized.

Dock windows are moved transparently by default, i.e. during the drag an outline rectangle is drawn on the screen representing the position of the dock window as it moves. If you want the dock window to be shown normally whilst it is moved use setOpaqueMoving().

The location of a dock window, i.e. its dock area and position within the dock area, can be determined by calling getLocation(). Movable dock windows can be lined up to minimize wasted space with lineUpDockWindows(). Pointers to the dock areas are available from topDock(), leftDock(), rightDock() and bottomDock(). A customize menu item is added to the pop up dock window menu if isCustomizable() returns TRUE; it returns FALSE by default. Reimplement isCustomizable() and customize() if you want to offer this extra menu item, for example, to allow the user to change settings relating to the main window and its toolbars and dock windows.

The main window's menu bar is fixed (at the top) by default. If you want a movable menu bar, create a QMenuBar as a stretchable widget inside its own movable dock window and restrict this dock window to only live within the Top or Bottom dock:

```
QToolBar *tb = new QToolBar( this );
addDockWindow( tb, tr( "Menubar" ), Top, FALSE );
QMenuBar *mb = new QMenuBar( tb );
mb->setFrameStyle( QFrame::NoFrame );
tb->setStretchableWidget( mb );
setDockEnabled( tb, Left, FALSE );
setDockEnabled( tb, Right, FALSE );
```

An application with multiple dock windows can choose to save the current dock window layout in order to restore it later, e.g. in the next session. You can do this by using the streaming operators for QMainWindow.

To save the layout and positions of all the dock windows do this:

```
QFile f( filename );
if ( f.open( IO_WriteOnly ) ) {
    QTextStream ts( &f );
    ts << *mainWindow;
    f.close();
}</pre>
```

To restore the dock window positions and sizes (normally when the application is next started), do following:

```
QFile f(filename);
```


```
if ( f.open( IO_ReadOnly ) ) {
   QTextStream ts( &f );
   ts >> *mainWindow;
   f.close();
}
```

The QSettings class can be used in conjunction with the streaming operators to store the application's settings.

QMainWindow's management of dock windows and toolbars is done transparently behind-the-scenes by QDockArea.

For multi-document interfaces (MDI), use a QWorkspace as the central widget.

Adding dock windows, e.g. toolbars, to QMainWindow's dock areas is straightforward. If the supplied dock areas are not sufficient for your application we suggest that you create a QWidget subclass and add your own dock areas (see QDockArea) to the subclass since QMainWindow provides functionality specific to the standard dock areas it provides.



See also QToolBar [p. 149], QDockWindow [p. 23], QStatusBar [Widgets with Qt], QAction [Events, Actions, Layouts and Styles with Qt], QMenuBar [p. 76], QPopupMenu [p. 115], QToolTipGroup [p. 168], QDialog [p. 12] and Main Window and Related Classes.

# **Member Type Documentation**

#### QMainWindow::DockWindows

Right-clicking a dock area will pop-up the dock window menu (createDockWindowMenu() is called automatically). When called in code you can specify what items should appear on the menu with this enum.

- QMainWindow::OnlyToolBars The menu will list all the toolbars, but not any other dock windows.
- QMainWindow::NoToolBars The menu will list dock windows but not toolbars.
- QMainWindow:: AllDockWindows The menu will list all toolbars and other dock windows. (This is the default.)

#### **Member Function Documentation**

QMainWindow::QMainWindow (QWidget \* parent = 0, const char \* name = 0, WFlags f = WType TopLevel)

Constructs an empty main window. The parent, name and widget flags f, are passed to the QWidget constructor.

By default, the widget flags are set to WType\_TopLevel rather than 0 as it is with QWidget. If you don't want your QMainWindow to be a top level widget then you will need to set *f* to 0.

# QMainWindow::~QMainWindow()

Destroys the object and frees any allocated resources.

# 

Adds dockWindow to the edge dock area.

If newLine is FALSE (the default) then the dockWindow is added at the end of the edge. For vertical edges the end is at the bottom, for horizontal edges (including Minimized) the end is at the right. If newLine is TRUE a new line of dock windows is started with dockWindow as the first (left-most and top-most) dock window.

If dockWindow is managed by another main window, it is first removed from that window.

# 

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Adds dockWindow to the dock area with label label.

If *newLine* is FALSE (the default) the *dockWindow* is added at the end of the *edge*. For vertical edges the end is at the bottom, for horizontal edges (including Minimized) the end is at the right. If *newLine* is TRUE a new line of dock windows is started with *dockWindow* as the first (left-most and top-most) dock window.

If dockWindow is managed by another main window, it is first removed from that window.

# void QMainWindow::addToolBar ( QDockWindow \*, Dock = DockTop, bool newLine = FALSE )

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

# void QMainWindow::addToolBar ( QDockWindow \*, const QString & label, Dock = DockTop, bool newLine = FALSE )

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code. This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

# bool QMainWindow::appropriate (QDockWindow \* dw) const

Returns TRUE if it is appropriate to include a menu item listing the *dw* dock window on the dock window menu. Otherwise returns FALSE.

The user is able to change the state (show or hide) a dock window that has a menu item by clicking the item.

Call setAppropriate() to indicate whether or not a particular dock window should appear on the popup menu.

See also setAppropriate() [p. 71].

# QDockArea \* QMainWindow::bottomDock () const

Returns a pointer the Bottom dock area

See also topDock() [p. 73], leftDock() [p. 69] and rightDock() [p. 70].

# QWidget \* QMainWindow::centralWidget () const

Returns a pointer to the main window's central widget.

The central widget is surrounded by the left, top, right and bottom dock areas. The menu bar is above the top dock area.

See also setCentralWidget() [p. 71].

Example: qfd/qfd.cpp.

#### void QMainWindow::childEvent ( QChildEvent \* e ) [virtual protected]

Monitors events, recieved in e, to ensure the layout is updated.

Reimplemented from QObject [Additional Functionality with Qt].

# QPopupMenu \* QMainWindow::createDockWindowMenu ( DockWindows dockWindows = AllDockWindows ) const

Creates the dock window menu which contains all toolbars (if *dockWindows* is OnlyToolBars ), all dock windows (if *dockWindows* is NoToolBars) or all toolbars and dock windows (if *dockWindows* is AllDockWindows - the default).

This function is called internally when necessary, e.g. when the user right clicks a dock area (providing isDockMenu-Enabled() returns TRUE). You may reimplement this function if you wish to customize the behaviour.

The menu items representing the toolbars and dock windows are checkable. The visible dock windows are checked and the hidden dock windows are unchecked. The user can click a menu item to change its state (show or hide the dock window).

The list and the state are always kept up-to-date.

Toolbars and dock windows which are not appropriate in the current context (see setAppropriate()) are not listed in the menu.

The menu also has a menu item for lining up the dock windows.

If isCustomizable() returns TRUE, a Customize menu item is added to the menu, which if clicked will call customize(). The isCustomizable() function we provide returns FALSE and customize() does nothing, so they must be reimplemented in a subclass to be useful.

#### void QMainWindow::customize() [virtual slot]

This function is called when the user clicks the Customize menu item on the dock window menu.

The customize menu item will only appear if isCustomizable() returns TRUE (it returns FALSE by default).

The function is intended, for example, to provide the user a means of telling the application that they wish to customize the main window, dock windows or dock areas.

The default implementation does nothing, but this may change in later Qt versions. In view of this the Customize menu item is not shown on the right-click menu by default. If you want the item to appear then reimplement is Customizable() to return TRUE.

See also isCustomizable() [p. 68].

#### void QMainWindow::dockWindowPositionChanged (QDockWindow \* dockWindow) [signal]

This signal is emitted when the *dockWindow* has changed its position. A change in position occurs when a dock window is moved within its dock area or moved to another dock area (including the Minimized and TearOff dock areas).

See also getLocation() [p. 67].

## QPtrList<QDockWindow> QMainWindow::dockWindows (Dock dock) const

Returns a list of all the dock windows which are in the dock dock area, regardless of their state.

For example, the TornOff dock area may contain closed dock windows but these are returned along with the visible dock windows.

#### QPtrList < QDockWindow > QMainWindow::dockWindows () const

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Returns the list of dock windows which belong to this main window, regardless of which dock area they are in or what their state is, (e.g. irrespective of whether they are visible or not).

#### bool QMainWindow::dockWindowsMovable () const

Returns TRUE if the dock windows are movable; otherwise returns FALSE. See the "dockWindowsMovable" [p. 74] property for details.

# bool QMainWindow::getLocation (QDockWindow \* dw, Dock & dock, int & index, bool & nl, int & extraOffset) const

Finds the location of the dock window dw.

If the *dw* dock window is found in the main window the function returns TRUE and populates the *dock* variable with the dw's dock area and the *index* with the dw's position within the dock area. It also sets *nl* to TRUE if the *dw* begins a new line (otherwise FALSE), and *extraOffset* with the dw's offset.

If the dw dock window is not found then the function returns FALSE and the state of dock, index, nl and extraOffset is undefined.

If you want to save and restore dock window positions then use operator>>() and operator<<().

See also operator>>() [p. 75] and operator<<() [p. 75].

# bool QMainWindow::hasDockWindow ( QDockWindow \* dw )

Returns TRUE if dw is a dock window known to the main window, otherwise returns FALSE.

#### bool QMainWindow::isCustomizable () const [virtual]

Returns TRUE if the dock area dock window menu includes the Customize menu item (which calls customize when clicked). Returns FALSE by default, i.e. the popup menu will not contain a Customize menu item. You will need to reimplement this function and set it to return TRUE if you wish the user to be able to see the dock window menu. See also customize() [p. 66].

#### bool QMainWindow::isDockEnabled (Dock dock) const

Returns TRUE if the *dock* dock area is enabled, i.e. it can accept user dragged dock windows; otherwise returns FALSE. See also setDockEnabled() [p. 71].

#### bool QMainWindow::isDockEnabled (QDockArea \* area) const

This is an overloaded member function, provided for convenience. It behaves essentially like the above function. Returns TRUE if *area* is enabled, i.e. it can accept user dragged dock windows; otherwise returns FALSE. See also setDockEnabled() [p. 71].

#### bool QMainWindow::isDockEnabled (QDockWindow \* tb, Dock dock) const

This is an overloaded member function, provided for convenience. It behaves essentially like the above function. Returns TRUE if dock is enabled for the dock window tb, otherwise returns FALSE. See also setDockEnabled() [p. 71].

# bool QMainWindow::isDockEnabled (QDockWindow \* dw, QDockArea \* area) const

This is an overloaded member function, provided for convenience. It behaves essentially like the above function. Returns TRUE if *area* is enabled for the dock window *dw*, otherwise returns FALSE.

See also setDockEnabled() [p. 71].

#### bool QMainWindow::isDockMenuEnabled () const

Returns TRUE, if the dock window menu is enabled; otherwise returns FALSE.

The menu lists the (appropriate()) dock windows (which may be shown or hidden), and has a "Line Up Dock Windows" menu item. It will also have a "Customize" menu item if isCustomizable() returns TRUE.

See also setDockEnabled() [p. 71], lineUpDockWindows() [p. 69], appropriate() [p. 65] and setAppropriate() [p. 71].

# QDockArea \* QMainWindow::leftDock () const

Returns the Left dock area

See also rightDock() [p. 70], topDock() [p. 73] and bottomDock() [p. 66].

#### void QMainWindow::lineUpDockWindows ( bool keepNewLines = FALSE )

This function will line up dock windows within the visible dock areas (Top, Left, Right and Bottom) as compactly as possible.

If *keepNewLines* is TRUE, all dock windows stay on their original lines. If *keepNewLines* is FALSE then newlines may be removed to achieve the most compact layout possible.

The method only works if dockWindowsMovable() returns TRUE.

#### void QMainWindow::lineUpToolBars ( bool keepNewLines = FALSE )

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

#### void QMainWindow::menuAboutToShow () [protected slot]

This slot is called from the aboutToShow() signal of the default dock menu of the mainwindow. The default implementation initializes the menu with all dock windows and toolbars in this slot.

If you want to do small adjustments to the menu, you can do it in this slot. Else reimplement createDockWindow-Menu().

#### QMenuBar \* QMainWindow::menuBar () const

Returns the menu bar for this window.

If there isn't one, then menuBar() creates an empty menu bar.

See also statusBar() [p. 72].

# void QMainWindow::moveDockWindow ( QDockWindow \* dockWindow, Dock edge = DockTop ) [virtual]

Moves dockWindow to the end of the edge.

For vertical edges the end is at the bottom, for horizontal edges (including Minimized) the end is at the right.

If dockWindow is managed by another main window, it is first removed from that window.

# void QMainWindow::moveDockWindow (QDockWindow \* dockWindow, Dock edge, bool nl, int index, int extraOffset = -1) [virtual]

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Moves dockWindow to position index of edge.

Any dock windows with positions *index* or higher have their position number incremented and any of these on the same line are moved right (down for vertical dock areas) to make room.

If *nl* is TRUE, a new dock window line is created below the line in which the moved dock window appears and the moved dock window, with any others with higher positions on the same line, is moved to this new line.

The *extraOffset* is the space to put between the left side of the dock area (top side for vertical dock areas) and the dock window. (This is mostly used for restoring dock windows to the positions the user has dragged them to.)

If dockWindow is managed by another main window, it is first removed from that window.

# void QMainWindow::moveToolBar ( QDockWindow \*, Dock = DockTop )

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

# void QMainWindow::moveToolBar ( QDockWindow \*, Dock, bool nl, int index, int extraOffset = -1)

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

# bool QMainWindow::opaqueMoving() const

Returns TRUE if dock windows are moved opaquely; otherwise returns FALSE. See the "opaqueMoving" [p. 74] property for details.

# void QMainWindow::pixmapSizeChanged(bool) [signal]

This signal is called whenever the setUsesBigPixmaps() is called with a value different to the current setting. All widgets that should respond to such changes, e.g. toolbar buttons, must connect to this signal.

# void QMainWindow::removeDockWindow ( QDockWindow \* dockWindow ) [virtual]

Removes dockWindow from the main window's docking area, provided dockWindow is non-null and managed by this main window.

# void QMainWindow::removeToolBar ( QDockWindow \*)

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

#### QDockArea \* QMainWindow::rightDock () const

Returns the Right dock area

See also leftDock() [p. 69], topDock() [p. 73] and bottomDock() [p. 66].

# bool QMainWindow::rightJustification() const

Returns TRUE if the main window right-justifies its dock windows; otherwise returns FALSE. See the "rightJustification" [p. 74] property for details.

#### void QMainWindow::setAppropriate ( QDockWindow \* dw, bool a ) [virtual slot]

Use this function to control whether or not the dw dock window's caption should appear as a menu item on the dock window menu that lists the dock windows.

If a is TRUE then the dw will appear as a menu item on the dock window menu. The user is able to change the state (show or hide) a dock window that has a menu item by clicking the item; depending on the state of your application, this may or may not be appropriate. If a is FALSE the dw will not appear on the popup menu.

See also showDockMenu() [p. 72], isCustomizable() [p. 68] and customize() [p. 66].

# void QMainWindow::setCentralWidget ( QWidget \* w ) [virtual]

Sets the central widget for this window to w.

The central widget is surrounded by the left, top, right and bottom dock areas. The menu bar is above the top dock area.

See also centralWidget() [p. 66].

# void QMainWindow::setDockEnabled (Dock dock, bool enable) [virtual]

If enable is TRUE then users can dock windows in the dock area. If enable is FALSE users cannot dock windows in the dock area.

Users can dock (drag) dock windows into any enabled dock area.

# void QMainWindow::setDockEnabled ( QDockWindow \* dw, Dock dock, bool enable ) [virtual]

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

If enable is TRUE then users can dock the dw dock window in the dock area. If enable is FALSE users cannot dock the dw dock window in the dock area.

In general users can dock (drag) dock windows into any enabled dock area. Using this function particular dock areas can be enabled (or disabled) as docking points for particular dock windows.

#### void QMainWindow::setDockMenuEnabled ( bool b ) [virtual slot]

If *b* is TRUE then right clicking on a dock window or dock area will pop up the dock window menu. If *b* is FALSE right clicking a dock window or dock area will not pop up the menu.

The menu lists the (appropriate()) dock windows (which may be shown or hidden), and has a line up dock window item. It will also have a Customize menu item if isCustomizable() returns TRUE.

See also lineUpDockWindows() [p. 69] and isDockMenuEnabled() [p. 68].

# void QMainWindow::setDockWindowsMovable ( bool ) [virtual slot]

Sets whether the dock windows are movable. See the "dockWindowsMovable" [p. 74] property for details.

#### void QMainWindow::setOpaqueMoving(bool)[virtual slot]

Sets whether dock windows are moved opaquely. See the "opaqueMoving" [p. 74] property for details.

#### void QMainWindow::setRightJustification(bool) [virtual slot]

Sets whether the main window right-justifies its dock windows. See the "rightJustification" [p. 74] property for details.

#### void QMainWindow::setToolBarsMovable ( bool ) [slot]

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

# void QMainWindow::setUpLayout() [virtual protected slot]

Sets up the geometry management of the window. It is called automatically when needed, so you shouldn't need to call it.

# void QMainWindow::setUsesBigPixmaps(bool) [virtual slot]

Sets whether big pixmaps are enabled. See the "usesBigPixmaps" [p. 74] property for details.

#### void QMainWindow::setUsesTextLabel(bool) [virtual slot]

Sets whether text labels for toolbar buttons are enabled. See the "usesTextLabel" [p. 75] property for details.

#### bool QMainWindow::showDockMenu (const QPoint & globalPos) [virtual protected slot]

Shows the dock menu at the position *globalPos*. The menu lists the dock windows so that they can be shown (or hidden), lined up, and possibly customized.

The default implementation uses the dock window menu which gets created by createDockWindowMenu(). You can reimplement createDockWindowMenu() if you want to use your own specialized popup menu.

#### QStatusBar \* QMainWindow::statusBar() const

Returns the status bar for this window. If there isn't one, statusBar() creates an empty status bar, and if necessary a tool tip group too.

See also menuBar() [p. 69] and toolTipGroup() [p. 73].

Example: qfd/qfd.cpp.

#### void QMainWindow::toolBarPositionChanged (QToolBar \*) [signal]

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

#### QPtrList < QToolBar > QMainWindow::toolBars (Dock dock) const

Returns a list of all the toolbars which are in the dock dock area, regardless of their state.

For example, the TornOff dock area may contain closed toolbars but these are returned along with the visible toolbars. See also dockWindows() [p. 67].

#### bool QMainWindow::toolBarsMovable () const

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

#### QToolTipGroup \* QMainWindow::toolTipGroup () const

Returns the tool tip group for this window. If there isn't one, toolTipGroup() creates an empty tool tip groups. See also menuBar() [p. 69] and statusBar() [p. 72].

#### QDockArea \* QMainWindow::topDock() const

Returns the Top dock area

See also bottomDock() [p. 66], leftDock() [p. 69] and rightDock() [p. 70].

#### bool QMainWindow::usesBigPixmaps() const

Returns TRUE if big pixmaps are enabled; otherwise returns FALSE. See the "usesBigPixmaps" [p. 74] property for details.

#### bool QMainWindow::usesTextLabel() const

Returns TRUE if text labels for toolbar buttons are enabled; otherwise returns FALSE. See the "usesTextLabel" [p. 75] property for details.

#### void QMainWindow::usesTextLabelChanged(bool)[signal]

This signal is called whenever the setUsesTextLabel() is called with a value different to the current setting. All widgets that should respond to such changes, e.g. toolbar buttons, must connect to this signal.

#### void QMainWindow::whatsThis() [virtual slot]

Enters 'What's This?' question mode and returns immediately.

This is the same as QWhatsThis::enterWhatsThisMode(), but implemented as a main window object's slot. This way it can easily be used for popup menus, for example:

```
QPopupMenu * help = new QPopupMenu( this );
help->insertItem( "What's &This", this , SLOT(whatsThis()), SHIFT+Key_F1);
```

See also QWhatsThis::enterWhatsThisMode() [Widgets with Qt].

### **Property Documentation**

#### bool dockWindowsMovable

This property holds whether the dock windows are movable.

If TRUE (the default), the user will be able to move Movable dock windows from one QMainWindow dock area to another, including the TearOff area (i.e. where the dock window floats freely as a window in its own right), and the Minimized area (where only the dock window's handle is shown below the menu bar). Moveable dock windows can also be moved within QMainWindow dock areas, i.e. to rearrange them within a dock area.

If FALSE the user will not be able to move any dock windows.

By default dock windows are moved transparently (i.e. only an outline rectangle is shown during the drag), but this setting can be changed with setOpaqueMoving().

See also setDockEnabled() [p. 71] and opaqueMoving [p. 74].

Set this property's value with setDockWindowsMovable() and get this property's value with dockWindowsMovable().

#### bool opaqueMoving

This property holds whether dock windows are moved opaquely.

If TRUE the dock windows of the main window are shown opaquely (i.e. it shows the toolbar as it looks when docked) when moved. If FALSE (the default) they are shown transparently, (i.e. as an outline rectangle).

Set this property's value with setOpaqueMoving() and get this property's value with opaqueMoving().

### bool rightJustification

This property holds whether the main window right-justifies its dock windows.

If disabled (the default), stretchable dock windows are expanded, and non-stretchable dock windows are given the minimum space they need. Since most dock windows are not stretchable, this usually results in a unjustified right edge (or unjustified bottom edge for a vertical dock area). If enabled, the main window will right-justify its dock windows.

See also QDockWindow::setVerticalStretchable() [p. 30] and QDockWindow::setHorizontalStretchable() [p. 29].

Set this property's value with setRightJustification() and get this property's value with rightJustification().

#### bool usesBigPixmaps

This property holds whether big pixmaps are enabled.

If FALSE (the default), the tool buttons will use small pixmaps; otherwise big pixmaps will be used.

Tool buttons and other widgets that wish to respond to this setting are responsible for reading the correct state on startup, and for connecting to the main window's widget's pixmapSizeChanged() signal.

Set this property's value with setUsesBigPixmaps() and get this property's value with usesBigPixmaps().

#### bool usesTextLabel

This property holds whether text labels for toolbar buttons are enabled.

If disabled (the default), the tool buttons will not use text labels. If enabled, text labels will be used.

Tool buttons and other widgets that wish to respond to this setting are responsible for reading the correct state on startup, and for connecting to the main window's widget's usesTextLabelChanged() signal.

See also QToolButton::usesTextLabel [p. 160].

Set this property's value with setUsesTextLabel() and get this property's value with usesTextLabel().

#### **Related Functions**

#### QTextStream & operator << ( QTextStream & ts, const QMainWindow & mainWindow )

Writes the layout (sizes and positions) of the dock windows in the dock areas of the QMainWindow mainWindow, including Minimized and TornOff dock windows, to the text stream ts.

This can be used, for example, in conjunction with QSettings to save the user's layout.

See also operator>>() [p. 75].

#### QTextStream & operator>> (QTextStream & ts, QMainWindow & mainWindow)

Reads the layout (sizes and positions) of the dock windows in the dock areas of the QMainWindow mainWindow from the text stream, ts, including Minimized and TornOff dock windows. Restores the dock windows and dock areas to these sizes and positions. The layout information must be in the format produced by operator < < ().

This can be used, for example, in conjunction with QSettings to restore the user's layout.

See also operator << () [p. 75].

The QMenuBar class provides a horizontal menu bar.

```
#include <qmenubar.h>
```

Inherits QFrame [Widgets with Qt] and QMenuData [p. 87].

#### **Public Members**

- QMenuBar (QWidget \* parent = 0, const char \* name = 0)
- ~QMenuBar()
- virtual void **show** ()
- virtual void hide()
- virtual int **heightForWidth** (int max\_width) const
- enum **Separator** { Never = 0, InWindowsStyle = 1 }
- Separator separator () const (obsolete)
- virtual void setSeparator (Separator when) (obsolete)
- void **setDefaultUp** (bool)
- bool isDefaultUp() const

### Signals

- void activated (int id)
- void **highlighted** (int id)

## **Important Inherited Members**

- int **insertItem** (const QString & text, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, const QString & text, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)
- int **insertItem** (const QPixmap & pixmap, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, const QPixmap & pixmap, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)
- int insertItem (const QString & text, int id = -1, int index = -1)

- int insertItem (const QIconSet & icon, const QString & text, int id = -1, int index = -1)
- int insertItem (const QString & text, QPopupMenu \* popup, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, const QString & text, QPopupMenu \* popup, int id = -1, int index = -1)
- int insertItem (const QPixmap & pixmap, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, const QPixmap & pixmap, int id = -1, int index = -1)
- int insertItem (const QPixmap & pixmap, QPopupMenu \* popup, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, const QPixmap & pixmap, QPopupMenu \* popup, int id = -1, int index = -1)
- int **insertItem** (QWidget \* widget, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, QCustomMenuItem \* custom, int id = -1, int index = -1)
- int insertItem (QCustomMenuItem \* custom, int id = -1, int index = -1)
- int insertSeparator (int index = -1)
- void **removeItem** (int id)
- void clear()
- bool isItemEnabled (int id) const
- void setItemEnabled (int id, bool enable)

### **Properties**

- bool **defaultUp** the popup orientation
- Separator separator in which cases a menubar sparator is drawn (obsolete)

#### **Protected Members**

- virtual void **drawContents** ( QPainter \* p )
- virtual void menuContentsChanged()
- virtual void menuStateChanged ()

## **Detailed Description**

The QMenuBar class provides a horizontal menu bar.

A menu bar consists of a list of pull-down menu items. You add menu items with insertItem(). For example, asuming that menubar is a pointer to a QMenuBar and filemenu is a pointer to a QPopupMenu, the following statement inserts the menu into the menu bar:

```
menubar->insertItem( "&File", filemenu );
```

The ampersand in the menu item's text sets Alt+F as a shortcut for this menu. (You can use "&&" to get a real ampersand in the menu bar.)

Items are either enabled or disabled. You toggle their state with setItemEnabled().

There is no need to lay out a menu bar. It automatically sets its own geometry to the top of the parent widget and changes it appropriately whenever the parent is resized.

Example of creating a menu bar with menu items (from menu/menu.cpp):

```
QPopupMenu *file = new QPopupMenu( this );
file->insertItem( p1, "&Open", this, SLOT(open()), CTRL+Key_O );
file->insertItem( p2, "&New", this, SLOT(news()), CTRL+Key_N );
menu = new QMenuBar( this );
menu->insertItem( "&File", file );
```

In most main window style applications you would use the menuBar() provided in QMainWindow, adding QPopup-Menus to the menu bar and adding QActions to the popup menus.

Example (from action/application.cpp):

```
QPopupMenu * file = new QPopupMenu( this );
menuBar()->insertItem( "&File", file );
fileNewAction->addTo( file );
```

Menu items can have text and pixmaps (or iconsets), see the various insertItem() overloads, as well as separators, see insertSeparator(). You can also add custom menu items that are derived from QCustomMenuItem.

Menu items may be removed with removeItem() and enabled or disabled with setItemEnabled().

QMenuBar on Qt/Mac is a wrapper for using the system-wide menubar. However if you have multiple menubars in one dialog the outermost menubar (normally inside a widget with WType TopLevel) will be used for the global menubar.



See also QPopupMenu [p. 115], QAccel [Events, Actions, Layouts and Styles with Qt], QAction [Events, Actions, Layouts and Styles with Qt], GUI Design Handbook: Menu Bar and Main Window and Related Classes.

# **Member Type Documentation**

### QMenuBar::Separator

This enum type is used to decide whether QMenuBar should draw a separator line at its bottom. The possible values are:

- QMenuBar:: Never In many applications there is already a separator, and having two looks wrong.
- QMenuBar::InWindowsStyle In some other applications a separator looks good in Windows style, but nowhere else.

#### **Member Function Documentation**

```
QMenuBar::QMenuBar (QWidget * parent = 0, const char * name = 0)
```

Constructs a menu bar with a parent and a name.

#### QMenuBar::~QMenuBar()

Destroys the menu bar.

#### void QMenuBar::activated(int id) [signal]

This signal is emitted when a menu item is selected; id is the id of the selected item.

Normally you will connect each menu item to a single slot using QMenuData::insertItem(), but sometimes you will want to connect several items to a single slot (most often if the user selects from an array). This signal is useful in such cases.

See also highlighted() [p. 79] and QMenuData::insertItem() [p. 92].

Example: progress/progress.cpp.

#### void QMenuData::clear ()

Removes all menu items.

See also removeItem() [p. 98] and removeItemAt() [p. 98].

Examples: mdi/application.cpp and qwerty/qwerty.cpp.

#### void QMenuBar::drawContents ( QPainter \* p ) [virtual protected]

Called from QFrame::paintEvent(). Draws the menu bar contents using painter p.

Reimplemented from QFrame [Widgets with Qt].

#### int QMenuBar::heightForWidth (int max width) const [virtual]

Returns the height that the menu would resize itself to if its parent (and hence itself) resized to the given *max\_width*. This can be useful for simple layout tasks in which the height of the menu bar is needed after items have been inserted. See showing/showing.cpp for an example of the usage.

Example: showing/showing.cpp.

Reimplemented from QWidget [Widgets with Qt].

#### void QMenuBar::hide() [virtual]

Reimplements QWidget::hide() in order to deselect any selected item, and calls setUpLayout() for the main window.

Example: grapher/grapher.cpp.

Reimplemented from QWidget [Widgets with Qt].

#### void QMenuBar::highlighted(int id) [signal]

This signal is emitted when a menu item is highlighted; id is the id of the highlighted item.

Normally, you will connect each menu item to a single slot using QMenuData::insertItem(), but sometimes you will want to connect several items to a single slot (most often if the user selects from an array). This signal is useful in such cases.

See also activated() [p. 79] and QMenuData::insertItem() [p. 92].

```
int QMenuData::insertItem (const QString & text, const QObject * receiver, const char * member, const QKeySequence & accel = 0, int id = -1, int index = -1)
```

The family of insertItem() functions inserts menu items into a popup menu or a menu bar.

A menu item is usually either a text string or a pixmap, both with an optional icon or keyboard accelerator. For special cases it is also possible to insert custom items (see QCustomMenuItem) or even widgets into popup menus.

Some insertItem() members take a popup menu as an additional argument. Use this to insert submenus to existing menus or pulldown menus to a menu bar.

The number of insert functions may look confusing, but they are actually quite simple to use.

This default version inserts a menu item with the text text, the accelerator key accel, an id and an optional index and connects it to the slot member in the object receiver.

#### Example:

```
QMenuBar *mainMenu = new QMenuBar;
QPopupMenu *fileMenu = new QPopupMenu;
fileMenu->insertItem( "New", myView, SLOT(newFile()), CTRL+Key_N );
fileMenu->insertItem( "Open", myView, SLOT(open()), CTRL+Key_O );
mainMenu->insertItem( "File", fileMenu );
```

Not all insert functions take an object/slot parameter or an accelerator key. Use connectItem() and setAccel() on these items.

If you need to translate accelerators, use tr() with a string description that use pass to the QKeySequence constructor:

In the example above, pressing Ctrl+N or selecting "Open" from the menu activates the myView->open() function.

Some insert functions take a QIconSet parameter to specify the little menu item icon. Note that you can always pass a QPixmap object instead.

The *index* specifies the position in the menu. The menu item is appended at the end of the list if *index* is negative.

Note that keyboard accelerators in Qt are not application-global, instead they are bound to a certain top-level window. For example, accelerators in QPopupMenu items only work for menus that are associated with a certain window. This is true for popup menus that live in a menu bar since their accelerators will then be installed in the menu bar itself. This also applies to stand-alone popup menus that have a top-level widget in their parentWidget() chain. The menu will then install its accelerator object on that top-level widget. For all other cases use an independent QAccel object.

**Warning:** Be careful when passing a literal 0 to insertItem() because some C++ compilers choose the wrong overloaded function. Cast the 0 to what you mean, e.g. (QObject\*)0.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98], connectItem() [p. 90], QAccel [Events, Actions, Layouts and Styles with Qt] and qnamespace.h.

Examples: addressbook/mainwindow.cpp, mdi/application.cpp, menu/menu.cpp, qwerty/qwerty.cpp, scrollview/scrollview.cpp and showimg/showimg.cpp.

### 

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, text *text*, accelerator *accel*, optional id id, and optional *index*. The menu item is connected it to the *receiver*'s *member* slot. The icon will be displayed to the left of the text in the item.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98], connectItem() [p. 90], QAccel [Events, Actions, Layouts and Styles with Qt] and gnamespace.h.

# int QMenuData::insertItem (const QPixmap & pixmap, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with pixmap *pixmap*, accelerator *accel*, optional id *id*, and optional *index*. The menu item is connected it to the *receiver*'s *member* slot. The icon will be displayed to the left of the text in the item.

To look best when being highlighted as a menu item, the pixmap should provide a mask (see QPixmap::mask()).

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QIconSet & icon, const QPixmap & pixmap, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1. int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, pixmap *pixmap*, accelerator *accel*, optional id *id*, and optional *index*. The icon will be displayed to the left of the pixmap in the item. The item is connected to the *member* slot in the *receiver* object.

To look best when being highlighted as a menu item, the pixmap should provide a mask (see QPixmap::mask()).

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98], connectItem() [p. 90], QAccel [Events, Actions, Layouts and Styles with Qt] and qnamespace.h.

#### int QMenuData::insertItem (const QString & text, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with text text, optional id id, and optional index.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QIconSet & icon, const QString & text, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, text *text*, optional id *id*, and optional *index*. The icon will be displayed to the left of the text in the item.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem ( const QString & text, QPopupMenu \* popup, int id = -1, int index = -1 )

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with text text, submenu popup, optional id id, and optional index.

The *popup* must be deleted by the programmer or by its parent widget. It is not deleted when this menu item is removed or when the menu is deleted.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QIconSet & icon, const QString & text, QPopupMenu \* popup, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, text *text*, submenu *popup*, optional id *id*, and optional *index*. The icon will be displayed to the left of the text in the item.

The *popup* must be deleted by the programmer or by its parent widget. It is not deleted when this menu item is removed or when the menu is deleted.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

### int QMenuData::insertItem (const QPixmap & pixmap, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with pixmap pixmap, optional id id, and optional index.

To look best when being highlighted as a menu item, the pixmap should provide a mask (see OPixmap::mask()).

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QIconSet & icon, const QPixmap & pixmap, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, pixmap *pixmap*, optional id *id*, and optional *index*. The icon will be displayed to the left of the pixmap in the item.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QPixmap & pixmap, QPopupMenu \* popup, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with pixmap pixmap, submenu popup, optional id id, and optional index.

The *popup* must be deleted by the programmer or by its parent widget. It is not deleted when this menu item is removed or when the menu is deleted.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QIconSet & icon, const QPixmap & pixmap, QPopupMenu \* popup, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, pixmap *pixmap* submenu *popup*, optional id *id*, and optional *index*. The icon will be displayed to the left of the pixmap in the item.

The *popup* must be deleted by the programmer or by its parent widget. It is not deleted when this menu item is removed or when the menu is deleted.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

### int QMenuData::insertItem (QWidget \* widget, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item that consists of the widget widget with optional id id, and optional index.

Ownership of *widget* is transferred to the popup menu or to the menu bar.

Theoretically, any widget can be inserted into a popup menu. In practice, this only makes sense with certain widgets.

If a widget is not focus-enabled (see QWidget::isFocusEnabled()), the menu treats it as a separator; this means that the item is not selectable and will never get focus. In this way you can, for example, simply insert a QLabel if you need a popup menu with a title.

If the widget is focus-enabled it will get focus when the user traverses the popup menu with the arrow keys. If the widget does not accept ArrowUp and ArrowDown in its key event handler, the focus will move back to the menu

when the respective arrow key is hit one more time. This works with a QLineEdit, for example. If the widget accepts the arrow key itself, it must also provide the possibility to put the focus back on the menu again by calling QWidget::focusNextPrevChild(). Futhermore, if the embedded widget closes the menu when the user made a selection, this can be done safely by calling

```
if ( isVisible() &&
    parentWidget() &&
    parentWidget()->inherits("QPopupMenu") )
    parentWidget()->close();
```

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98].

# int QMenuData::insertItem ( const QIconSet & icon, QCustomMenuItem \* custom, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a custom menu item custom with an icon and with optional id id, and optional index.

This only works with popup menus. It is not supported for menu bars. Ownership of *custom* is transferred to the popup menu.

If you want to connect a custom item to a certain slot, use connectItem().

Returns the allocated menu identifier number (id if id >= 0).

See also connectItem() [p. 90], removeItem() [p. 98] and QCustomMenuItem [p. 6].

### int QMenuData::insertItem (QCustomMenuItem \* custom, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a custom menu item *custom* with optional id id, and optional index.

This only works with popup menus. It is not supported for menu bars. Ownership of *custom* is transferred to the popup menu.

If you want to connect a custom item to a certain slot, use connectItem().

Returns the allocated menu identifier number (id if id >= 0).

See also connectItem() [p. 90], removeItem() [p. 98] and QCustomMenuItem [p. 6].

#### int QMenuData::insertSeparator (int index = -1)

Inserts a separator at position index. The separator becomes the last menu item if index is negative.

In a popup menu a separator is rendered as a horizontal line. In a Motif menu bar a separator is spacing, so the rest of the items (normally just "Help") are drawn right-justified. In a Windows menu bar separators are ignored (to comply with the Windows style guidelines).

Examples: addressbook/mainwindow.cpp, mdi/application.cpp, menu/menu.cpp, progress/progress.cpp, qwerty/qwerty.cpp, scrollview/scrollview.cpp and showimg/showimg.cpp.

#### bool QMenuBar::isDefaultUp () const

Returns the popup orientation. See the "defaultUp" [p. 86] property for details.

#### bool QMenuData::isItemEnabled (int id) const

Returns TRUE if the item with identifier *id* is enabled; otherwise returns FALSE See also setItemEnabled() [p. 99].

#### void QMenuBar::menuContentsChanged() [virtual protected]

Recomputes the menu bar's display data according to the new contents.

You should never need to call this; it is called automatically by QMenuData whenever it needs to be called. Reimplemented from QMenuData [p. 97].

#### void QMenuBar::menuStateChanged() [virtual protected]

Recomputes the menu bar's display data according to the new state.

You should never need to call this; it is called automatically by QMenuData whenever it needs to be called. Reimplemented from QMenuData [p. 97].

#### void QMenuData::removeItem ( int id )

Removes the menu item that has the identifier *id*. See also removeItemAt() [p. 98] and clear() [p. 90].

#### Separator QMenuBar::separator () const

Returns in which cases a menubar sparator is drawn. See the "separator" [p. 86] property for details.

#### void QMenuBar::setDefaultUp (bool)

Sets the popup orientation. See the "defaultUp" [p. 86] property for details.

#### void QMenuData::setItemEnabled ( int id, bool enable )

If enable is TRUE, enables the menu item with identifier id; otherwise disables the menu item with identifier id. See also isItemEnabled() [p. 97].

Examples: mdi/application.cpp, menu/menu.cpp, progress/progress.cpp and showimg/showimg.cpp.

#### void QMenuBar::setSeparator (Separator when) [virtual]

Sets in which cases a menubar sparator is drawn to when. See the "separator" [p. 86] property for details.

#### void QMenuBar::show() [virtual]

Reimplements QWidget::show() in order to set up the correct keyboard accelerators and to raise itself to the top of the widget stack.

Example: grapher/grapher.cpp.

Reimplemented from QWidget [Widgets with Qt].

## **Property Documentation**

#### bool defaultUp

This property holds the popup orientation.

The default popup orientation. By default, menus pop "down" the screen. By setting the property to TRUE, the menu will pop "up". You might call this for menus that are *below* the document to which they refer.

If the menu would not fit on the screen, the other direction is used rather than the default.

Set this property's value with setDefaultUp() and get this property's value with isDefaultUp().

#### Separator separator

This property holds in which cases a menubar sparator is drawn.

**This property is obsolete.** It is provided to keep old source working. We strongly advise against using it in new code. Set this property's value with setSeparator() and get this property's value with separator().

The QMenuData class is a base class for QMenuBar and QPopupMenu.

```
#include <qmenudata.h>
```

Inherited by QMenuBar [p. 76] and QPopupMenu [p. 115].

#### **Public Members**

- QMenuData ()
- virtual ~QMenuData ()
- uint count () const
- int **insertItem** (const QString & text, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, const QString & text, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)
- int **insertItem** (const QPixmap & pixmap, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, const QPixmap & pixmap, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)
- int insertItem (const QString & text, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, const QString & text, int id = -1, int index = -1)
- int insertItem (const OString & text, OPopupMenu \* popup, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, const QString & text, QPopupMenu \* popup, int id = -1, int index = -1)
- int insertItem (const QPixmap & pixmap, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, const QPixmap & pixmap, int id = -1, int index = -1)
- int insertItem (const QPixmap & pixmap, QPopupMenu \* popup, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, const QPixmap & pixmap, QPopupMenu \* popup, int id = -1, int index = -1)
- int insertItem (QWidget \* widget, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, QCustomMenuItem \* custom, int id = -1, int index = -1)
- int insertItem (QCustomMenuItem \* custom, int id = -1, int index = -1)
- int insertSeparator (int index = -1)
- void removeItem (int id)
- void **removeItemAt** (int index)
- void clear()
- QKeySequence **accel** (int id) const
- void **setAccel** (const QKeySequence & key, int id)

- QIconSet \* iconSet (int id) const
- QString text (int id) const
- QPixmap \* pixmap (int id) const
- void **setWhatsThis** (int id, const QString & text)
- QString whatsThis (int id) const
- void changeItem (int id, const OString & text)
- void **changeItem** (int id, const QPixmap & pixmap)
- void **changeItem** (int id, const QIconSet & icon, const QString & text)
- void **changeItem** (int id, const QIconSet & icon, const QPixmap & pixmap)
- void changeItem (const QString & text, int id) (obsolete)
- void changeItem (const QPixmap & pixmap, int id) (obsolete)
- void changeItem (const QIconSet & icon, const QString & text, int id) (obsolete)
- bool isItemActive (int id) const
- bool isItemEnabled (int id) const
- void **setItemEnabled** (int id, bool enable)
- bool isItemChecked (int id) const
- void **setItemChecked** (int id, bool check)
- virtual void **updateItem** (int id)
- int indexOf (int id) const
- int idAt (int index) const
- virtual void **setId** (int index, int id)
- bool **connectItem** (int id, const QObject \* receiver, const char \* member)
- bool disconnectItem (int id, const QObject \* receiver, const char \* member)
- bool **setItemParameter** (int id, int param)
- int itemParameter (int id) const
- QMenuItem \* findItem (int id) const
- QMenuItem \* findItem (int id, QMenuData \*\* parent) const
- virtual void activateItemAt (int index)

#### **Protected Members**

- virtual void menuContentsChanged ()
- virtual void menuStateChanged ()
- virtual void **menuInsPopup** (QPopupMenu \*)
- virtual void **menuDelPopup** ( QPopupMenu \* )

### **Detailed Description**

The QMenuData class is a base class for QMenuBar and QPopupMenu.

QMenuData has an internal list of menu items. A menu item is a text, pixmap or separator, and may also have a popup menu (separators have no popup menus).

The menu item sends out an activated() signal when it is selected and a highlighted() signal when it receives the user input focus.

Menu items are assigned the menu identifier id that is passed in insertItem() or an automatically generated identifier if id is < 0 (the default). The generated identifiers (negative integers) are guaranteed to be unique within the entire application. The identifier is used to access the menu item in other functions.

Menu items can be removed with removeItem() or changed with changeItem(). Accelerators can be changed or set with setAccel(). Checkable items can be checked or unchecked with setItemChecked(). Items can be enabled or disabled using setItemEnabled() and connected and disconnected with connectItem() and disconnectItem() respectively.

Menu items are stored in a list. Use findItem() to find an item by its list position or by its menu identifier.

See also QAccel [Events, Actions, Layouts and Styles with Qt], QPopupMenu [p. 115], QAction [Events, Actions, Layouts and Styles with Qt] and Miscellaneous Classes.

#### **Member Function Documentation**

#### QMenuData::QMenuData()

Constructs an empty menu data list.

#### QMenuData::~QMenuData() [virtual]

Removes all menu items and disconnects any signals that have been connected.

#### QKeySequence QMenuData::accel (int id) const

Returns the accelerator key that has been defined for the menu item *id*, or 0 if it has no accelerator key. See also setAccel() [p. 98], QAccel [Events, Actions, Layouts and Styles with Qt] and qnamespace.h.

#### void QMenuData::activateItemAt(int index) [virtual]

Activates the menu item at position index.

If the index is invalid (for example, -1), the object itself is deactivated.

#### void QMenuData::changeItem (int id, const QString & text)

Changes the text of the menu item id to text. If the item has an icon, the icon remains unchanged. See also text() [p. 99].

#### void QMenuData::changeItem ( int id, const QPixmap & pixmap )

This is an overloaded member function, provided for convenience. It behaves essentially like the above function. Changes the pixmap of the menu item *id* to the pixmap *pixmap*. If the item has an icon, the icon is unchanged. See also pixmap() [p. 98].

#### void QMenuData::changeItem (int id, const QIconSet & icon, const QString & text)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function. Changes the iconset and text of the menu item *id* to the *icon* and *text* respectively.

See also pixmap() [p. 98].

#### void QMenuData::changeItem (int id, const QIconSet & icon, const QPixmap & pixmap)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function. Changes the iconset and pixmap of the menu item *id* to *icon* and *pixmap* respectively.

See also pixmap() [p. 98].

#### void QMenuData::changeItem ( const QString & text, int id )

**This function is obsolete.** It is provided to keep old source working. We strongly advise against using it in new code. Changes the text of the menu item *id*. If the item has an icon, the icon remains unchanged. See also text() [p. 99].

#### void QMenuData::changeItem (const QPixmap & pixmap, int id)

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code. Changes the pixmap of the menu item *id*. If the item has an icon, the icon remains unchanged. See also pixmap() [p. 98].

#### void QMenuData::changeItem (const QIconSet & icon, const QString & text, int id)

**This function is obsolete.** It is provided to keep old source working. We strongly advise against using it in new code. Changes the icon and text of the menu item id. See also pixmap() [p. 98].

#### void QMenuData::clear()

Removes all menu items.

See also removeItem() [p. 98] and removeItemAt() [p. 98].

Examples: mdi/application.cpp and qwerty/qwerty.cpp.

### bool QMenuData::connectItem (int id, const QObject \* receiver, const char \* member)

Connects the menu item with identifier id to receiver's member slot or signal.

The receiver's slot/signal is activated when the menu item is activated.

See also disconnectItem() [p. 91] and setItemParameter() [p. 99].

Example: menu/menu.cpp.

#### uint QMenuData::count() const

Returns the number of items in the menu.

### bool QMenuData::disconnectItem (int id, const QObject \* receiver, const char \* member)

Disconnects the receiver's member from the menu item with identifier id.

All connections are removed when the menu data object is destroyed.

See also connectItem() [p. 90] and setItemParameter() [p. 99].

#### QMenuItem \* QMenuData::findItem (int id) const

Returns a pointer to the menu item with identifier *id*, or 0 if there is no item with this identifier. See also indexOf() [p. 91].

### QMenuItem \* QMenuData::findItem (int id, QMenuData \*\* parent) const

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Returns a pointer to the menu item with identifier *id*, or 0 if there is no item with this identifier. Changes \*parent to point to the parent of the return value.

See also indexOf() [p. 91].

#### QIconSet \* QMenuData::iconSet (int id) const

Returns the icon set that has been set for menu item id, or 0 if no icon set has been set.

See also changeItem() [p. 89], text() [p. 99] and pixmap() [p. 98].

#### int QMenuData::idAt (int index) const

Returns the identifier of the menu item at position *index* in the internal list, or -1 if *index* is out of range. See also setId() [p. 99] and indexOf() [p. 91].

#### int QMenuData::indexOf (int id) const

Returns the index of the menu item with identifier *id*, or -1 if there is no item with this identifier. See also idAt() [p. 91] and findItem() [p. 91].

Example: scrollview/scrollview.cpp.

```
int QMenuData::insertItem (const QString & text, const QObject * receiver,
const char * member, const QKeySequence & accel = 0, int id = -1, int index = -1)
```

The family of insertItem() functions inserts menu items into a popup menu or a menu bar.

A menu item is usually either a text string or a pixmap, both with an optional icon or keyboard accelerator. For special cases it is also possible to insert custom items (see QCustomMenuItem) or even widgets into popup menus.

Some insertItem() members take a popup menu as an additional argument. Use this to insert submenus to existing menus or pulldown menus to a menu bar.

The number of insert functions may look confusing, but they are actually quite simple to use.

This default version inserts a menu item with the text *text*, the accelerator key *accel*, an id and an optional index and connects it to the slot *member* in the object *receiver*.

Example:

```
QMenuBar *mainMenu = new QMenuBar;
QPopupMenu *fileMenu = new QPopupMenu;
fileMenu->insertItem( "New", myView, SLOT(newFile()), CTRL+Key_N );
fileMenu->insertItem( "Open", myView, SLOT(open()), CTRL+Key_O );
mainMenu->insertItem( "File", fileMenu );
```

Not all insert functions take an object/slot parameter or an accelerator key. Use connectItem() and setAccel() on these items.

If you need to translate accelerators, use tr() with a string description that use pass to the QKeySequence constructor:

In the example above, pressing Ctrl+N or selecting "Open" from the menu activates the myView->open() function.

Some insert functions take a QIconSet parameter to specify the little menu item icon. Note that you can always pass a QPixmap object instead.

The *index* specifies the position in the menu. The menu item is appended at the end of the list if *index* is negative.

Note that keyboard accelerators in Qt are not application-global, instead they are bound to a certain top-level window. For example, accelerators in QPopupMenu items only work for menus that are associated with a certain window. This is true for popup menus that live in a menu bar since their accelerators will then be installed in the menu bar itself. This also applies to stand-alone popup menus that have a top-level widget in their parentWidget() chain. The menu will then install its accelerator object on that top-level widget. For all other cases use an independent QAccel object.

**Warning:** Be careful when passing a literal 0 to insertItem() because some C++ compilers choose the wrong overloaded function. Cast the 0 to what you mean, e.g. (QObject\*)0.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98], connectItem() [p. 90], QAccel [Events, Actions, Layouts and Styles with Qt] and qnamespace.h.

Examples: addressbook/mainwindow.cpp, mdi/application.cpp, menu/menu.cpp, qwerty/qwerty.cpp, scrollview/scrollview.cpp and showimg/showimg.cpp.

# int QMenuData::insertItem (const QIconSet & icon, const QString & text, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, text *text*, accelerator *accel*, optional id id, and optional *index*. The menu item is connected it to the *receiver*'s *member* slot. The icon will be displayed to the left of the text in the item.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98], connectItem() [p. 90], QAccel [Events, Actions, Layouts and Styles with Qt] and qnamespace.h.

# int QMenuData::insertItem (const QPixmap & pixmap, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with pixmap *pixmap*, accelerator *accel*, optional id *id*, and optional *index*. The menu item is connected it to the *receiver's member* slot. The icon will be displayed to the left of the text in the item.

To look best when being highlighted as a menu item, the pixmap should provide a mask (see QPixmap::mask()).

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QIconSet & icon, const QPixmap & pixmap, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, pixmap *pixmap*, accelerator *accel*, optional id *id*, and optional *index*. The icon will be displayed to the left of the pixmap in the item. The item is connected to the *member* slot in the *receiver* object.

To look best when being highlighted as a menu item, the pixmap should provide a mask (see QPixmap::mask()).

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98], connectItem() [p. 90], QAccel [Events, Actions, Layouts and Styles with Qt] and gnamespace.h.

#### int QMenuData::insertItem (const QString & text, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with text text, optional id id, and optional index.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem ( const QIconSet & icon, const QString & text, int id = -1, int index = -1 )

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, text *text*, optional id *id*, and optional *index*. The icon will be displayed to the left of the text in the item.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem ( const QString & text, QPopupMenu \* popup, int id = -1, int index = -1 )

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with text text, submenu popup, optional id id, and optional index.

The *popup* must be deleted by the programmer or by its parent widget. It is not deleted when this menu item is removed or when the menu is deleted.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QIconSet & icon, const QString & text, QPopupMenu \* popup, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, text *text*, submenu *popup*, optional id *id*, and optional *index*. The icon will be displayed to the left of the text in the item.

The *popup* must be deleted by the programmer or by its parent widget. It is not deleted when this menu item is removed or when the menu is deleted.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

#### int QMenuData::insertItem (const QPixmap & pixmap, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with pixmap pixmap, optional id id, and optional index.

To look best when being highlighted as a menu item, the pixmap should provide a mask (see QPixmap::mask()).

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QIconSet & icon, const QPixmap & pixmap, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, pixmap *pixmap*, optional id *id*, and optional *index*. The icon will be displayed to the left of the pixmap in the item.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QPixmap & pixmap, QPopupMenu \* popup, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with pixmap pixmap, submenu popup, optional id id, and optional index.

The *popup* must be deleted by the programmer or by its parent widget. It is not deleted when this menu item is removed or when the menu is deleted.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QIconSet & icon, const QPixmap & pixmap, QPopupMenu \* popup, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, pixmap *pixmap* submenu *popup*, optional id *id*, and optional *index*. The icon will be displayed to the left of the pixmap in the item.

The *popup* must be deleted by the programmer or by its parent widget. It is not deleted when this menu item is removed or when the menu is deleted.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

### int QMenuData::insertItem (QWidget \* widget, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item that consists of the widget widget with optional id id, and optional index.

Ownership of *widget* is transferred to the popup menu or to the menu bar.

Theoretically, any widget can be inserted into a popup menu. In practice, this only makes sense with certain widgets.

If a widget is not focus-enabled (see QWidget::isFocusEnabled()), the menu treats it as a separator; this means that the item is not selectable and will never get focus. In this way you can, for example, simply insert a QLabel if you need a popup menu with a title.

If the widget is focus-enabled it will get focus when the user traverses the popup menu with the arrow keys. If the widget does not accept ArrowUp and ArrowDown in its key event handler, the focus will move back to the menu

when the respective arrow key is hit one more time. This works with a QLineEdit, for example. If the widget accepts the arrow key itself, it must also provide the possibility to put the focus back on the menu again by calling QWidget::focusNextPrevChild(). Futhermore, if the embedded widget closes the menu when the user made a selection, this can be done safely by calling

```
if ( isVisible() &&
    parentWidget() &&
    parentWidget()->inherits("QPopupMenu") )
    parentWidget()->close();
```

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98].

# int QMenuData::insertItem (const QIconSet & icon, QCustomMenuItem \* custom, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a custom menu item custom with an icon and with optional id id, and optional index.

This only works with popup menus. It is not supported for menu bars. Ownership of *custom* is transferred to the popup menu.

If you want to connect a custom item to a certain slot, use connectItem().

Returns the allocated menu identifier number (id if id >= 0).

See also connectItem() [p. 90], removeItem() [p. 98] and OCustomMenuItem [p. 6].

### int QMenuData::insertItem (QCustomMenuItem \* custom, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a custom menu item *custom* with optional id id, and optional index.

This only works with popup menus. It is not supported for menu bars. Ownership of *custom* is transferred to the popup menu.

If you want to connect a custom item to a certain slot, use connectItem().

Returns the allocated menu identifier number (id if id >= 0).

See also connectItem() [p. 90], removeItem() [p. 98] and QCustomMenuItem [p. 6].

#### int QMenuData::insertSeparator (int index = -1)

Inserts a separator at position index. The separator becomes the last menu item if index is negative.

In a popup menu a separator is rendered as a horizontal line. In a Motif menu bar a separator is spacing, so the rest of the items (normally just "Help") are drawn right-justified. In a Windows menu bar separators are ignored (to comply with the Windows style guidelines).

Examples: addressbook/mainwindow.cpp, mdi/application.cpp, menu/menu.cpp, progress/progress.cpp, qwerty/qwerty.cpp, scrollview/scrollview.cpp and showimg/showimg.cpp.

#### bool QMenuData::isItemActive (int id) const

Returns TRUE if the menu item with the id id is currently active; otherwise returns FALSE.

#### bool QMenuData::isItemChecked (int id) const

Returns TRUE if the menu item with the id id has been checked; otherwise returns FALSE.

See also setItemChecked() [p. 99].

Examples: progress/progress.cpp and showimg/showimg.cpp.

#### bool QMenuData::isItemEnabled(int id) const

Returns TRUE if the item with identifier *id* is enabled; otherwise returns FALSE See also setItemEnabled() [p. 99].

#### int QMenuData::itemParameter (int id) const

Returns the parameter of the activation signal of item id.

If no parameter has been specified for this item with setItemParameter(), the value defaults to id.

See also connectItem() [p. 90], disconnectItem() [p. 91] and setItemParameter() [p. 99].

#### void QMenuData::menuContentsChanged() [virtual protected]

Virtual function; notifies subclasses that one or more items have been inserted or removed. Reimplemented in QMenuBar.

#### void QMenuData::menuDelPopup ( QPopupMenu \* ) [virtual protected]

Virtual function; notifies subclasses that a popup menu item has been removed.

#### void QMenuData::menuInsPopup ( QPopupMenu \* ) [virtual protected]

Virtual function; notifies subclasses that a popup menu item has been inserted.

#### void QMenuData::menuStateChanged() [virtual protected]

Virtual function; notifies subclasses that one or more items have changed state (enabled/disabled or checked/unchecked).

Reimplemented in QMenuBar.

#### QPixmap \* QMenuData::pixmap (int id) const

Returns the pixmap that has been set for menu item id, or 0 if no pixmap has been set.

See also changeItem() [p. 89], text() [p. 99] and iconSet() [p. 91].

#### void QMenuData::removeItem ( int id )

Removes the menu item that has the identifier id.

See also removeItemAt() [p. 98] and clear() [p. 90].

#### void QMenuData::removeItemAt ( int index )

Removes the menu item at position index.

See also removeItem() [p. 98] and clear() [p. 90].

#### void QMenuData::setAccel ( const QKeySequence & key, int id )

Sets the accelerator key for the menu item id to key.

An accelerator key consists of a key code and a combination of the modifiers SHIFT, CTRL, ALT or UNICODE\_ACCEL (OR'ed or added). The header file qnamespace.h contains a list of key codes.

Defining an accelerator key produces a text that is added to the menu item; for instance, CTRL + Key\_O produces "Ctrl+O". The text is formatted differently for different platforms.

Note that keyboard accelerators in Qt are not application-global, instead they are bound to a certain top-level window. For example, accelerators in QPopupMenu items only work for menus that are associated with a certain window. This is true for popup menus that live in a menu bar since their accelerators will then be installed in the menu bar itself. This also applies to stand-alone popup menus that have a top-level widget in their parentWidget() chain. The menu will then install its accelerator object on that top-level widget. For all other cases use an independent QAccel object.

#### Example:

If you need to translate accelerators, use QAccel::stringToKey():

```
fileMenu->setAccel( QAccel::stringToKey(tr("Ctrl+0")), 67 );
```

You can also specify the accelerator in the insertItem() function. You may prefer to use QAction to associate accelerators with menu items.

See also accel() [p. 89], insertItem() [p. 92], QAccel [Events, Actions, Layouts and Styles with Qt], qnamespace.h and QAction [Events, Actions, Layouts and Styles with Qt].

Example: menu/menu.cpp.

#### void QMenuData::setId(int index, int id) [virtual]

Sets the menu identifier of the item at index to id.

If index is out of range, the operation is ignored.

See also idAt() [p. 91].

#### void QMenuData::setItemChecked ( int id, bool check )

If *check* is TRUE, checks the menu item with id *id*; otherwise unchecks the menu item with id *id*. Calls QPopup-Menu::setCheckable(TRUE) if necessary.

See also isItemChecked() [p. 97].

Examples: grapher/grapher.cpp, mdi/application.cpp, menu/menu.cpp, progress/progress.cpp, scrollview/scrollview.cpp and showimg/showimg.cpp.

#### void QMenuData::setItemEnabled (int id, bool enable)

If enable is TRUE, enables the menu item with identifier id; otherwise disables the menu item with identifier id.

See also isItemEnabled() [p. 97].

Examples: mdi/application.cpp, menu/menu.cpp, progress/progress.cpp and showimg/showimg.cpp.

#### bool QMenuData::setItemParameter (int id, int param)

Sets the parameter of the activation signal of item *id* to *param*.

If any receiver takes an integer parameter, this value is passed.

See also connectItem() [p. 90], disconnectItem() [p. 91] and itemParameter() [p. 97].

Example: mdi/application.cpp.

#### void QMenuData::setWhatsThis (int id, const QString & text)

Sets text as What's This help for the menu item with identifier id.

See also whatsThis() [p. 100].

Examples: application/application.cpp and mdi/application.cpp.

#### QString QMenuData::text(int id) const

Returns the text that has been set for menu item id, or a null string if no text has been set.

See also changeItem() [p. 89], pixmap() [p. 98] and iconSet() [p. 91].

Examples: qdir/qdir.cpp and showimg/showimg.cpp.

### void QMenuData::updateItem(int id) [virtual]

Virtual function; notifies subclasses about an item with id that has been changed. Reimplemented in QPopupMenu.

### QString QMenuData::whatsThis (int id) const

Returns the What's This help text for the item with identifier *id* or QString::null if no text has yet been defined. See also setWhatsThis() [p. 99].

# **QMessageBox Class Reference**

The QMessageBox class provides a modal dialog with a short message, an icon, and some buttons.

#include <qmessagebox.h>

Inherits QDialog [p. 12].

#### **Public Members**

- enum Icon { NoIcon = 0, Information = 1, Warning = 2, Critical = 3 }
- QMessageBox (QWidget \* parent = 0, const char \* name = 0)
- QMessageBox (const QString & caption, const QString & text, Icon icon, int button0, int button1, int button2, QWidget \* parent = 0, const char \* name = 0, bool modal = TRUE, WFlags f = WStyle\_DialogBorder)
- ~QMessageBox ()
- QString text () const
- void **setText** (const QString &)
- Icon icon () const
- void **setIcon** (Icon)
- const QPixmap \* iconPixmap () const
- void **setIconPixmap** (const QPixmap &)
- OString **buttonText** (int button) const
- void **setButtonText** (int button, const OString & text)
- virtual void **adjustSize**()
- TextFormat textFormat () const
- void **setTextFormat** ( TextFormat )

#### **Static Public Members**

- int **information** (QWidget \* parent, const QString & caption, const QString & text, int button0, int button1 = 0, int button2 = 0)
- int information (QWidget \* parent, const QString & caption, const QString & text, const QString & button0Text = QString::null, const QString & button1Text = QString::null, const QString & button2Text = QString::null, int defaultButtonNumber = 0, int escapeButtonNumber = -1)
- int warning (QWidget \* parent, const QString & caption, const QString & text, int button0, int button1, int button2 = 0)
- int warning (QWidget \* parent, const QString & caption, const QString & text, const QString & button0Text = QString::null, const QString & button1Text = QString::null, const QString & button2Text = QString::null, int defaultButtonNumber = 0, int escapeButtonNumber = -1)

- int **critical** (QWidget \* parent, const QString & caption, const QString & text, int button0, int button1, int button2 = 0)
- int critical (QWidget \* parent, const QString & caption, const QString & text, const QString & button0Text = QString::null, const QString & button1Text = QString::null, const QString & button2Text = QString::null, int defaultButtonNumber = 0, int escapeButtonNumber = -1)
- void **about** (QWidget \* parent, const QString & caption, const QString & text)
- void **aboutQt** ( QWidget \* parent, const QString & caption = QString::null )
- int message (const QString & caption, const QString & text, const QString & buttonText = QString::null, QWidget \* parent = 0, const char \* = 0) (obsolete)
- bool query (const QString & caption, const QString & text, const QString & yesButtonText = QString::null, const QString & noButtonText = QString::null, QWidget \* parent = 0, const char \* = 0) (obsolete)
- QPixmap standardIcon (Icon icon, GUIStyle style) (obsolete)
- QPixmap **standardIcon** (Icon icon )

### **Properties**

- Icon icon the messagebox icon
- QPixmap iconPixmap the current icon
- QString text the message box text to be displayed
- TextFormat **textFormat** the format of the text displayed by the message box

### **Detailed Description**

The QMessageBox class provides a modal dialog with a short message, an icon, and some buttons.

A message box is a modal dialog that displays an icon, some text and up to three push buttons. It's used for simple messages and questions.

QMessageBox provides a range of different messages, arranged roughly along two axes: severity and complexity.

Severity is

- Information for message boxes that are part of normal operation
- Warning for message boxes that tell the user about unusual errors
- Critical as Warning, but for critical errors

The message box has a different icon for each of the severity levels.

Complexity is one button (OK) for a simple messages, or two or even three buttons for questions.

There are static functions for common cases. For example:

If a program is unable to find a supporting file, but can do perfectly well without it:

```
QMessageBox::information( this, "Application name",
    "Unable to find the user preferences file.\n"
    "The factory default will be used instead." );
```

warning() can be used to tell the user about unusual errors, or errors which can't be easily fixed:

The text part of all message box messages can be either rich text or plain text. If you specify a rich text formatted string, it will be rendered using the default stylesheet. See QStyleSheet::defaultSheet() for details. With certain strings that contain XML meta characters, the auto-rich text detection may fail, interpreting plain text incorrectly as rich text. In these rare cases, use QStyleSheet::convertFromPlainText() to convert your plain text string to a visually equivalent rich text string or set the text format explicitly with setTextFormat().

Below are some examples of how to use the static member functions. After these examples you will find an overview of the non-static member functions.

If a program is unable to find a supporting file, it may do the following:

```
QMessageBox::information( this, "Application name here",
    "Unable to find the file \"index.html\".\n"
    "The factory default will be used instead." );
```

The Microsoft Windows User Interface Guidelines strongly recommend using the application name as the window's caption. The message box has just one button, OK, and its text tells the user both what happened and what the program will do about it. Because the application is able to make do, the message box is just information, not a warning or a critical error.

Exiting a program is part of its normal operation. If there is unsaved data the user probably should be asked if they want to save the data. For example:

The application name is used as the window caption in accordance with the Microsoft recommendation. The Escape button cancels the entire exit operation, and pressing Enter causes the changes to be saved before the exit occurs.

Disk full errors are unusual (in a perfect world, they are) and they certainly can be hard to correct. This example uses predefined buttons instead of hard-coded button texts:

The critical() function should be reserved for critical errors. In this example errorDetails is a QString or const char\*, and QString is used to concatenate several strings:

```
QMessageBox::critical( 0, "Application name here",
    QString("An internal error occurred. Please ") +
    "call technical support at 123456789 and report\n"+
    "these numbers:\n\n" + errorDetails +
    "\n\n will now exit." );
```

In this example an OK button is displayed.

QMessageBox provides a very simple About box, which displays an appropriate icon and the string you provide:

See about() for more information.

Finally, you can create a QMessageBox from scratch and with custom button texts:

```
mb.setButtonText( QMessageBox::No, "Discard" );
switch( mb.exec() ) {
   case QMessageBox::Yes:
        // save and exit
        break;
   case QMessageBox::No:
        // exit without saving
        break;
   case QMessageBox::Cancel:
        // don't save and don't exit
        break;
}
```

QMessageBox defines two enum types: Icon and an unnamed button type. Icon defines the Information, Warning, and Critical icons for each GUI style. It is used by the constructor and by the static member functions information(), warning() and critical(). A function called standardIcon() gives you access to the various icons.

The button types are:

- Ok the default for single-button message boxes
- Cancel note that this is not automatically Escape
- Yes
- No
- Abort
- Retry
- Ignore

Button types can be combined with two modifiers by using OR, '|':

- Default makes pressing Enter equivalent to clicking this button. Normally used with Ok, Yes or similar.
- Escape makes pressing Escape equivalent to clicking this button. Normally used with Abort, Cancel or similar.

The text(), icon() and iconPixmap() functions provide access to the current text and pixmap of the message box. The setText(), setIcon() and setIconPixmap() let you change it. The difference between setIcon() and setIconPixmap() is that the former accepts a QMessageBox::Icon and can be used to set standard icons, whereas the latter accepts a QPixmap and can be used to set custom icons.

setButtonText() and buttonText() provide access to the buttons.

QMessageBox has no signals or slots.



See also ODialog [p. 12], Isys on error messages, GUI Design Handbook: Message Box and Dialog Classes.

### **Member Type Documentation**

#### QMessageBox::Icon

This enum includes provides the following values:

- QMessageBox::NoIcon the message box does not have any icon.
- QMessageBox::Information an icon indicating that the message is nothing out of the ordinary.
- QMessageBox::Warning an icon indicating that the message is a warning, but can be dealt with.
- QMessageBox::Critical an icon indicating that the message represents a critical problem.

#### **Member Function Documentation**

```
QMessageBox::QMessageBox (QWidget * parent = 0, const char * name = 0)
```

Constructs a message box with no text and a button with the label "OK".

If *parent* is 0, the message box becomes an application-global modal dialog box. If *parent* is a widget, the message box becomes modal relative to *parent*.

The parent and name arguments are passed to the QDialog constructor.

```
QMessageBox::QMessageBox (const QString & caption, const QString & text, Icon icon, int button0, int button1, int button2, QWidget * parent = 0, const char * name = 0, bool modal = TRUE, WFlags f = WStyle DialogBorder)
```

Constructs a message box with a caption, a text, an icon, and up to three buttons.

The *icon* must be one of the following:

- QMessageBox::NoIcon
- QMessageBox::Information
- QMessageBox::Warning
- QMessageBox::Critical

Each button, button0, button1 and button2, can have one of the following values:

- QMessageBox::NoButton
- QMessageBox::Ok
- QMessageBox::Cancel
- QMessageBox::Yes
- QMessageBox::No
- QMessageBox::Abort
- QMessageBox::Retry
- QMessageBox::Ignore

Use QMessageBox::NoButton for the later parameters to have fewer than three buttons in your message box.

One of the buttons can be OR-ed with the QMessageBox::Default flag to make it the default button (clicked when Enter is pressed).

One of the buttons can be OR-ed with the QMessageBox::Escape flag to make it the cancel or close button (clicked when Escape is pressed).

#### Example:

If *parent* is 0, the message box becomes an application-global modal dialog box. If *parent* is a widget, the message box becomes modal relative to *parent*.

If modal is TRUE the message becomes modal; otherwise it becomes modeless.

The parent, name, modal, and f arguments are passed to the QDialog constructor.

See also caption [Widgets with Qt], text [p. 113] and icon [p. 113].

### QMessageBox::~QMessageBox()

Destroys the message box.

# void QMessageBox::about ( QWidget \* parent, const QString & caption, const QString & text ) [static]

Displays a simple about box with caption caption and text text. The about box's parent is parent.

about() looks for a suitable icon in four locations:

- 1. It prefers parent->icon() if that exists.
- 2. If not, it tries the top-level widget containing parent.
- 3. If that fails, it tries the main widget.
- 4. As a last resort it uses the Information icon.

The about box has a single button labelled OK.

See also QWidget::icon [Widgets with Qt] and QApplication::mainWidget() [Additional Functionality with Qt].

Examples: action/application.cpp, application/application.cpp, helpviewer/helpwindow.cpp, mdi/application.cpp, menu/menu.cpp and themes/themes.cpp.

# void QMessageBox::aboutQt (QWidget \* parent, const QString & caption = QString::null) [static]

Displays a simple message box about Qt, with caption caption and optionally centered over parent. The message includes the version number of Qt being used by the application.

This is useful for inclusion in the Help menu. See the examples/menu/menu.cpp example.

Examples: action/application.cpp, application/application.cpp, helpviewer/helpwindow.cpp, mdi/application.cpp, menu/menu.cpp, themes/themes.cpp and trivial/trivial.cpp.

### void QMessageBox::adjustSize() [virtual]

Adjusts the size of the message box to fit the contents just before QDialog::exec() or QDialog::show() is called.

This function will not be called if the message box has been explicitly resized before showing it.

Reimplemented from QWidget [Widgets with Qt].

#### QString QMessageBox::buttonText(int button) const

Returns the text of the messagebox button button, or null if the message box does not contain the button.

See also setButtonText() [p. 111].

# int QMessageBox::critical(QWidget \* parent, const QString & caption, const QString & text, int button0, int button1, int button2 = 0) [static]

Opens a critical message box with the caption *caption* and the text *text*. The dialog may have up to three buttons. Each of the button parameters, *button0*, *button1* and *button2* may be set to one of the following values:

• QMessageBox::NoButton

• QMessageBox::Ok

• QMessageBox::Cancel

• QMessageBox::Yes

• QMessageBox::No

• QMessageBox::Abort

• QMessageBox::Retry

• QMessageBox::Ignore

If you don't want all three buttons, set the last button, or last two buttons to QMessageBox::NoButton.

Returns the index of the button that was clicked.

If *parent* is 0, the message box becomes an application-global modal dialog box. If *parent* is a widget, the message box becomes modal relative to *parent*.

See also information() [p. 109] and warning() [p. 112].

Examples: network/ftpclient/ftpmainwindow.cpp, process/process.cpp and xml/outliner/outlinetree.cpp.

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Displays a critical error message box with a caption, a text, and 1..3 buttons. Returns the number of the button that was clicked (0, 1 or 2).

button0Text is the text of the first button and is optional. If button0Text is not supplied, "OK" (translated) will be used. button1Text is the text of the second button and is optional, and button2Text is the text of the third button and is optional. defaultButtonNumber (0..2) is the index of the default button; pressing Return or Enter is the same as clicking the default button. It defaults to 0 (the first button). escapeButtonNumber is the index of the Escape button; pressing Escape is the same as clicking this button. It defaults to -1 (pressing Escape does nothing); supply 0, 1, or 2 to make pressing Escape equivalent to clicking the relevant button.

If *parent* is 0, the message box becomes an application-global modal dialog box. If *parent* is a widget, the message box becomes modal relative to *parent*.

See also information() [p. 109] and warning() [p. 112].

#### Icon QMessageBox::icon() const

Returns the messagebox icon. See the "icon" [p. 113] property for details.

#### const QPixmap \* QMessageBox::iconPixmap() const

Returns the current icon. See the "iconPixmap" [p. 113] property for details.

# int QMessageBox::information (QWidget \* parent, const QString & caption, const QString & text, int button0, int button1 = 0, int button2 = 0) [static]

Opens an information message box with the caption *caption* and the text *text*. The dialog may have up to three buttons. Each of the buttons, *button0*, *button1* and *button2* may be set to one of the following values:

• QMessageBox::NoButton

• QMessageBox::Ok

• QMessageBox::Cancel

• QMessageBox::Yes

• QMessageBox::No

• QMessageBox::Abort

• QMessageBox::Retry

• QMessageBox::Ignore

If you don't want all three buttons, set the last button, or last two buttons to QMessageBox::NoButton.

Returns the index of the button that was clicked.

If *parent* is 0, the message box becomes an application-global modal dialog box. If *parent* is a widget, the message box becomes modal relative to *parent*.

See also warning() [p. 112] and critical() [p. 108].

Examples: action/application.cpp, application/application.cpp, dirview/dirview.cpp, fileiconview/qfileiconview.cpp, picture/picture.cpp, qwerty/qwerty.cpp and sql/sqltable/main.cpp.

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Displays an information message box with caption *caption*, text *text* and one, two or three buttons. Returns the index of the button that was clicked (0, 1 or 2).

button0Text is the text of the first button and is optional. If button0Text is not supplied, "OK" (translated) will be used. button1Text is the text of the second button and is optional. button2Text is the text of the third button and is optional. defaultButtonNumber (0..2) is the index of the default button; pressing Return or Enter is the same as clicking the default button. It defaults to 0 (the first button). escapeButtonNumber is the index of the Escape button; pressing Escape is the same as clicking this button. It defaults to -1 (pressing Escape does nothing); supply 0, 1 or 2 to make pressing Escape equivalent to clicking the relevant button.

If parent is 0, the message box becomes an application-global modal dialog box. If parent is a widget, the message box becomes modal relative to parent.

See also warning() [p. 112] and critical() [p. 108].

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

Opens a modal message box directly using the specified parameters.

Please use information(), warning() or critical() instead.

Example: grapher/grapher.cpp.

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

Queries the user using a modal message box with two buttons. Note that *caption* is not always shown, it depends on the window manager.

Please use information(), warning() or critical() instead.

#### void QMessageBox::setButtonText (int button, const QString & text)

Sets the text of the message box button button to text. Setting the text of a button that is not in the message box is silently ignored.

See also buttonText() [p. 108].

#### void QMessageBox::setIcon(Icon)

Sets the messagebox icon. See the "icon" [p. 113] property for details.

#### void QMessageBox::setIconPixmap ( const QPixmap & )

Sets the current icon. See the "iconPixmap" [p. 113] property for details.

#### void QMessageBox::setText ( const QString & )

Sets the message box text to be displayed. See the "text" [p. 113] property for details.

#### void QMessageBox::setTextFormat ( TextFormat )

Sets the format of the text displayed by the message box. See the "textFormat" [p. 113] property for details.

#### QPixmap QMessageBox::standardIcon (Icon icon) [static]

Returns the pixmap used for a standard icon. This allows the pixmaps to be used in more complex message boxes. *icon* specifies the required icon, e.g. QMessageBox::Information, QMessageBox::Warning or QMessageBox::Critical.

#### QPixmap QMessageBox::standardIcon (Icon icon, GUIStyle style) [static]

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

Returns the pixmap used for a standard icon. This allows the pixmaps to be used in more complex message boxes. *icon* specifies the required icon, e.g. QMessageBox::Information, QMessageBox::Warning or QMessageBox::Critical. *style* is unused.

#### QString QMessageBox::text() const

Returns the message box text to be displayed. See the "text" [p. 113] property for details.

#### TextFormat QMessageBox::textFormat() const

Returns the format of the text displayed by the message box. See the "textFormat" [p. 113] property for details.

# int QMessageBox::warning(QWidget \* parent, const QString & caption, const QString & text, int button0, int button1, int button2 = 0) [static]

Opens a warning message box with the caption *caption* and the text *text*. The dialog may have up to three buttons. Each of the button parameters, *button0*, *button1* and *button2* may be set to one of the following values:

• QMessageBox::NoButton

• QMessageBox::Ok

• QMessageBox::Cancel

• QMessageBox::Yes

• QMessageBox::No

• QMessageBox::Abort

QMessageBox::Retry

• QMessageBox::Ignore

If you don't want all three buttons, set the last button, or last two buttons to QMessageBox::NoButton.

Returns the index of the button that was clicked.

If parent is 0, the message box becomes an application-global modal dialog box. If parent is a widget, the message box becomes modal relative to parent.

See also information() [p. 109] and critical() [p. 108].

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Displays a warning message box with a caption, a text, and 1..3 buttons. Returns the number of the button that was clicked (0, 1, or 2).

button0Text is the text of the first button and is optional. If button0Text is not supplied, "OK" (translated) will be used. button1Text is the text of the second button and is optional, and button2Text is the text of the third button and is optional. defaultButtonNumber (0..2) is the index of the default button; pressing Return or Enter is the same as clicking the default button. It defaults to 0 (the first button). escapeButtonNumber is the index of the Escape button; pressing Escape is the same as clicking this button. It defaults to -1 (pressing Escape does nothing); supply 0, 1, or 2 to make pressing Escape equivalent to clicking the relevant button.

If *parent* is 0, the message box becomes an application-global modal dialog box. If *parent* is a widget, the message box becomes modal relative to *parent*.

See also information() [p. 109] and critical() [p. 108].

### **Property Documentation**

#### Icon icon

This property holds the messagebox icon.

The icon of the message box can be one of the following predefined icons:

• QMessageBox::NoIcon

• QMessageBox::Information

• QMessageBox::Warning

• QMessageBox::Critical

The actual pixmap used for displaying the icon depends on the current GUI style. You can also set a custom pixmap icon using the QMessageBox::iconPixmap property. The default icon is QMessageBox::NoIcon.

See also iconPixmap [p. 113].

Set this property's value with setIcon() and get this property's value with icon().

#### QPixmap iconPixmap

This property holds the current icon.

The icon currently used by the message box. Note that it's often hard to draw one pixmap that looks appropriate in both Motif and Windows GUI styles; you may want to draw two pixmaps.

See also icon [p. 113].

Set this property's value with setIconPixmap() and get this property's value with iconPixmap().

#### **QString** text

This property holds the message box text to be displayed.

The text will be interpreted either as a plain text or as a rich text, depending on the text format setting (QMessage-Box::textFormat). The default setting is AutoText, i.e. the message box will try to auto-detect the format of the text.

The default value of the property is QString::null.

See also textFormat [p. 113].

Set this property's value with setText() and get this property's value with text().

#### TextFormat textFormat

This property holds the format of the text displayed by the message box.

The current text format used by the message box. See the Qt::TextFormat [Additional Functionality with Qt] enum for an explanation of the possible options.

The default format is AutoText.

See also text [p. 113].

Set this property's value with setTextFormat() and get this property's value with textFormat().

# **QPopupMenu Class Reference**

The QPopupMenu class provides a popup menu widget.

```
#include <qpopupmenu.h>
```

Inherits QFrame [Widgets with Qt] and QMenuData [p. 87].

#### **Public Members**

- **QPopupMenu** (QWidget \* parent = 0, const char \* name = 0)
- ~QPopupMenu ()
- void **popup** (const QPoint & pos, int indexAtPoint = 0)
- virtual void **updateItem** (int id)
- virtual void **setCheckable** (bool)
- bool isCheckable() const
- int exec()
- int exec (const QPoint & pos, int indexAtPoint = 0)
- virtual void **setActiveItem** (int i)
- int idAt (int index) const
- int idAt (const QPoint & pos) const
- int insertTearOffHandle (int id = -1, int index = -1)

## **Signals**

- void activated (int id)
- void **highlighted** (int id)
- void aboutToShow()
- void aboutToHide()

# **Important Inherited Members**

- int insertItem (const QString & text, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)
- int **insertItem** (const QIconSet & icon, const QString & text, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)

- int insertItem (const QPixmap & pixmap, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, const QPixmap & pixmap, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)
- int insertItem (const QString & text, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, const QString & text, int id = -1, int index = -1)
- int insertItem (const QString & text, QPopupMenu \* popup, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, const QString & text, QPopupMenu \* popup, int id = -1, int index = -1)
- int insertItem (const QPixmap & pixmap, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, const QPixmap & pixmap, int id = -1, int index = -1)
- int insertItem (const QPixmap & pixmap, QPopupMenu \* popup, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, const QPixmap & pixmap, QPopupMenu \* popup, int id = -1, int index = -1)
- int insertItem (QWidget \* widget, int id = -1, int index = -1)
- int insertItem (const QIconSet & icon, QCustomMenuItem \* custom, int id = -1, int index = -1)
- int insertItem (QCustomMenuItem \* custom, int id = -1, int index = -1)
- $\blacksquare$  int insertSeparator (int index = -1)
- void **removeItem** (int id)
- void removeItemAt (int index)
- void clear()
- QKeySequence accel (int id) const
- void **setAccel** (const QKeySequence & key, int id)
- QIconSet \* iconSet (int id ) const
- QString text (int id) const
- QPixmap \* pixmap (int id) const
- void **setWhatsThis** (int id, const QString & text)
- QString whatsThis (int id) const
- void **changeItem** (int id, const QString & text)
- void **changeItem** (int id, const OPixmap & pixmap)
- void **changeItem** (int id, const QIconSet & icon, const QString & text)
- void **changeItem** (int id, const OIconSet & icon, const OPixmap & pixmap)
- bool isItemEnabled (int id) const
- void **setItemEnabled** (int id, bool enable)
- bool isItemChecked (int id) const
- void **setItemChecked** (int id, bool check)
- bool **connectItem** (int id, const QObject \* receiver, const char \* member)
- bool disconnectItem (int id, const QObject \* receiver, const char \* member)
- bool **setItemParameter** (int id, int param)
- int itemParameter (int id) const

## **Properties**

■ bool **checkable** — whether the display of check marks on menu items is enabled

#### **Protected Members**

- int itemHeight (int row) const
- int itemHeight ( OMenuItem \* mi ) const
- void **drawItem** (QPainter \* p, int tab , QMenuItem \* mi, bool act, int x, int y, int w, int h)
- virtual void **drawContents** ( OPainter \* p )
- int columns() const

### **Detailed Description**

The QPopupMenu class provides a popup menu widget.

A popup menu widget is a selection menu. It can be either a pull-down menu in a menu bar or a standalone context (popup) menu. Pull-down menus are shown by the menu bar when the user clicks on the respective item or hits the specified shortcut key. Use QMenuBar::insertItem() to insert a popup menu into a menu bar. Show a context menu either asynchronously with popup() or synchronously with exec().

Technically, a popup menu consists of a list of menu items. You add items with insertItem(). An item is either a string, a pixmap or a custom item that provides its own drawing function (see QCustomMenuItem). In addition, items can have an optional icon drawn on the very left side and an accelerator key such as "Ctrl+X". The accelerator can also be changed at run-time by holding the left mouse button over an item and pressing the new accelerator.

There are three kinds of menu items: separators, menu items that perform an action and menu items that show a submenu. Separators are inserted with insertSeparator(). For submenus, you pass a pointer to a QPopupMenu in your call to insertItem(). All other items are considered action items.

When inserting action items you usually specify a receiver and a slot. The receiver will be notifed whenever the item is selected. In addition, QPopupMenu provides two signals, activated() and highlighted(), which signal the identifier of the respective menu item. It is sometimes practical to connect several items to one slot. To distinguish between them, specify a slot that takes an integer argument and use setItemParameter() to associate a unique value with each item.

You clear a popup menu with clear() and remove single items with removeItem() or removeItemAt().

A popup menu can display check marks for certain items when enabled with setCheckable(TRUE). You check or uncheck items with setItemChecked().

Items are either enabled or disabled. You toggle their state with setItemEnabled(). Just before a popup menu becomes visible, it emits the aboutToShow() signal. You can use this signal to set the correct enabled/disabled states of all menu items before the user sees it. The corresponding aboutToHide() signal is emitted when the menu hides again.

You can provide What's This? help for single menu items with setWhatsThis(). See QWhatsThis for general information about this kind of lightweight online help.

For ultimate flexibility, you can also add entire widgets as items into a popup menu (for example, a color selector).

A QPopupMenu can also provide a tear-off menu. A tear-off menu is a top-level window that contains a copy of the menu. This makes it possible for the user to "tear off" frequently used menus and position them in a convenient place on the screen. If you want that functionality for a certain menu, insert a tear-off handle with insertTearOffHandle(). When using tear-off menus, bear in mind that the concept isn't typically used on Microsoft Windows so users may not be familiar with it. Consider using a QToolBar instead.

menu/menu.cpp is a typical example of QMenuBar and QPopupMenu use.



See also QMenuBar [p. 76], GUI Design Handbook: Menu, Drop-Down and Pop-Up, Main Window and Related Classes and Basic Widgets.

#### **Member Function Documentation**

### QPopupMenu::QPopupMenu (QWidget \* parent = 0, const char \* name = 0)

Constructs a popup menu with a the parent called name.

Although a popup menu is always a top-level widget, if a parent is passed the popup menu will be deleted when that parent is destroyed (as with any other QObject).

#### QPopupMenu::~QPopupMenu()

Destroys the popup menu.

#### void QPopupMenu::aboutToHide() [signal]

This signal is emitted just before the popup menu is hidden after it has been displayed.

See also aboutToShow() [p. 118], setItemEnabled() [p. 99], setItemChecked() [p. 99], insertItem() [p. 92] and removeItem() [p. 98].

#### void QPopupMenu::aboutToShow() [signal]

This signal is emitted just before the popup menu is displayed. You can connect it to any slot that sets up the menu contents (e.g. to ensure that the right items are enabled).

See also aboutToHide() [p. 118], setItemEnabled() [p. 99], setItemChecked() [p. 99], insertItem() [p. 92] and removeItem() [p. 98].

Example: mdi/application.cpp.

#### QKeySequence QMenuData::accel (int id) const

Returns the accelerator key that has been defined for the menu item id, or 0 if it has no accelerator key.

See also setAccel() [p. 98], QAccel [Events, Actions, Layouts and Styles with Qt] and qnamespace.h.

#### void QPopupMenu::activated(int id) [signal]

This signal is emitted when a menu item is selected; *id* is the id of the selected item.

Normally, you connect each menu item to a single slot using QMenuData::insertItem(), but sometimes you will want to connect several items to a single slot (most often if the user selects from an array). This signal is useful in such cases.

See also highlighted() [p. 121] and QMenuData::insertItem() [p. 92].

Examples: grapher/grapher.cpp, helpviewer/helpwindow.cpp, qdir/qdir.cpp, qwerty/qwerty.cpp, scrollview/scrollview.cpp and showimg/showimg.cpp.

#### void QMenuData::changeItem ( int id, const QString & text )

Changes the text of the menu item *id* to *text*. If the item has an icon, the icon remains unchanged. See also text() [p. 99].

#### void QMenuData::changeItem (int id, const QPixmap & pixmap)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function. Changes the pixmap of the menu item *id* to the pixmap *pixmap*. If the item has an icon, the icon is unchanged. See also pixmap() [p. 98].

#### void QMenuData::changeItem (int id, const QIconSet & icon, const QString & text)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function. Changes the iconset and text of the menu item *id* to the *icon* and *text* respectively.

See also pixmap() [p. 98].

#### void QMenuData::changeItem (int id, const QIconSet & icon, const QPixmap & pixmap)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function. Changes the iconset and pixmap of the menu item *id* to *icon* and *pixmap* respectively.

See also pixmap() [p. 98].

#### void QMenuData::clear()

Removes all menu items.

See also removeItem() [p. 98] and removeItemAt() [p. 98].

Examples: mdi/application.cpp and qwerty/qwerty.cpp.

#### int QPopupMenu::columns() const [protected]

If a popup menu does not fit on the screen it lays itself out in multiple columns until it does fit.

This functions returns the number of columns necessary.

See also sizeHint [Widgets with Qt].

#### bool QMenuData::connectItem (int id, const QObject \* receiver, const char \* member)

Connects the menu item with identifier id to receiver's member slot or signal.

The receiver's slot/signal is activated when the menu item is activated.

See also disconnectItem() [p. 91] and setItemParameter() [p. 99].

Example: menu/menu.cpp.

#### bool QMenuData::disconnectItem (int id, const QObject \* receiver, const char \* member)

Disconnects the receiver's member from the menu item with identifier id.

All connections are removed when the menu data object is destroyed.

See also connectItem() [p. 90] and setItemParameter() [p. 99].

### void QPopupMenu::drawContents(QPainter \* p) [virtual protected]

Draws all menu items using painter p.

Reimplemented from QFrame [Widgets with Qt].

# void QPopupMenu::drawItem ( QPainter \* p, int tab\_, QMenuItem \* mi, bool act, int x, int y, int w, int h) [protected]

Draws menu item mi in the area x, y, w, h, using painter p. The item is drawn active if act is TRUE or drawn inactive if act is FALSE. The rightmost tab pixels are used for accelerator text.

See also QStyle::drawControl() [Events, Actions, Layouts and Styles with Qt].

#### int QPopupMenu::exec()

Executes this popup synchronously.

This is equivalent to exec(mapToGlobal(QPoint(0,0))). In most situations you'll want to specify the position yourself, for example at the current mouse position:

```
exec(QCursor::pos());
```

or aligned to a widget:

```
exec(somewidget.mapToGlobal(QPoint(0,0)));
```

Examples: fileiconview/qfileiconview.cpp and scribble/scribble.cpp.

#### int QPopupMenu::exec ( const QPoint & pos, int indexAtPoint = 0 )

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Executes this popup synchronously.

Opens the popup menu so that the item number *indexAtPoint* will be at the specified *global* position *pos*. To translate a widget's local coordinates into global coordinates, use QWidget::mapToGlobal().

The return code is the id of the selected item in either the popup menu or one of its submenus, or -1 if no item is selected (normally because the user presses Escape).

Note that all signals are emitted as usual. If you connect a menu item to a slot and call the menu's exec(), you get the result both via the signal-slot connection and in the return value of exec().

Common usage is to position the popup at the current mouse position:

```
exec(QCursor::pos());
```

or aligned to a widget:

```
exec(somewidget.mapToGlobal(QPoint(0,0)));
```

When positioning a popup with exec() or popup(), bear in mind that you cannot rely on the popup menu's current size(). For performance reasons, the popup adapts its size only when necessary. So in many cases, the size before and after the show is different. Instead, use sizeHint(). It calculates the proper size depending on the menu's current contents.

See also popup() [p. 128] and sizeHint [Widgets with Qt].

#### void QPopupMenu::highlighted(int id) [signal]

This signal is emitted when a menu item is highlighted; id is the id of the highlighted item.

Normally, you connect each menu item to a single slot using QMenuData::insertItem(), but sometimes you will want to connect several items to a single slot (most often if the user selects from an array). This signal is useful in such cases.

See also activated() [p. 119] and QMenuData::insertItem() [p. 92].

#### QIconSet \* QMenuData::iconSet (int id) const

Returns the icon set that has been set for menu item id, or 0 if no icon set has been set.

See also changeItem() [p. 89], text() [p. 99] and pixmap() [p. 98].

#### int QPopupMenu::idAt(int index) const

Returns the identifier of the menu item at position *index* in the internal list, or -1 if *index* is out of range.

See also QMenuData::setId() [p. 99] and QMenuData::indexOf() [p. 91].

Example: scrollview/scrollview.cpp.

#### int QPopupMenu::idAt (const QPoint & pos) const

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Returns the id of the item at pos, or -1 if there is no item there or if it is a separator item.

```
int QMenuData::insertItem (const QString & text, const QObject * receiver, const char * member, const QKeySequence & accel = 0, int id = -1, int index = -1)
```

The family of insertItem() functions inserts menu items into a popup menu or a menu bar.

A menu item is usually either a text string or a pixmap, both with an optional icon or keyboard accelerator. For special cases it is also possible to insert custom items (see QCustomMenuItem) or even widgets into popup menus.

Some insertItem() members take a popup menu as an additional argument. Use this to insert submenus to existing menus or pulldown menus to a menu bar.

The number of insert functions may look confusing, but they are actually quite simple to use.

This default version inserts a menu item with the text text, the accelerator key accel, an id and an optional index and connects it to the slot member in the object receiver.

#### Example:

```
QMenuBar *mainMenu = new QMenuBar;
QPopupMenu *fileMenu = new QPopupMenu;
fileMenu->insertItem( "New", myView, SLOT(newFile()), CTRL+Key_N );
fileMenu->insertItem( "Open", myView, SLOT(open()), CTRL+Key_O );
mainMenu->insertItem( "File", fileMenu );
```

Not all insert functions take an object/slot parameter or an accelerator key. Use connectItem() and setAccel() on these items.

If you need to translate accelerators, use tr() with a string description that use pass to the QKeySequence constructor:

In the example above, pressing Ctrl+N or selecting "Open" from the menu activates the myView->open() function.

Some insert functions take a QIconSet parameter to specify the little menu item icon. Note that you can always pass a QPixmap object instead.

The *index* specifies the position in the menu. The menu item is appended at the end of the list if *index* is negative.

Note that keyboard accelerators in Qt are not application-global, instead they are bound to a certain top-level window. For example, accelerators in QPopupMenu items only work for menus that are associated with a certain window. This is true for popup menus that live in a menu bar since their accelerators will then be installed in the menu bar itself. This also applies to stand-alone popup menus that have a top-level widget in their parentWidget() chain. The menu will then install its accelerator object on that top-level widget. For all other cases use an independent QAccel object.

**Warning:** Be careful when passing a literal 0 to insertItem() because some C++ compilers choose the wrong overloaded function. Cast the 0 to what you mean, e.g. (QObject\*)0.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98], connectItem() [p. 90], QAccel [Events, Actions, Layouts and Styles with Qt] and gnamespace.h.

Examples: addressbook/mainwindow.cpp, mdi/application.cpp, menu/menu.cpp, qwerty/qwerty.cpp, scrollview/scrollview.cpp and showimg/showimg.cpp.

### 

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, text *text*, accelerator *accel*, optional id *id*, and optional *index*. The menu item is connected it to the *receiver*'s *member* slot. The icon will be displayed to the left of the text in the item.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98], connectItem() [p. 90], QAccel [Events, Actions, Layouts and Styles with Qt] and qnamespace.h.

# int QMenuData::insertItem (const QPixmap & pixmap, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with pixmap *pixmap*, accelerator *accel*, optional id *id*, and optional *index*. The menu item is connected it to the *receiver*'s *member* slot. The icon will be displayed to the left of the text in the item.

To look best when being highlighted as a menu item, the pixmap should provide a mask (see QPixmap::mask()).

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QIconSet & icon, const QPixmap & pixmap, const QObject \* receiver, const char \* member, const QKeySequence & accel = 0, int id = -1. int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, pixmap *pixmap*, accelerator *accel*, optional id *id*, and optional *index*. The icon will be displayed to the left of the pixmap in the item. The item is connected to the *member* slot in the *receiver* object.

To look best when being highlighted as a menu item, the pixmap should provide a mask (see QPixmap::mask()).

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98], connectItem() [p. 90], QAccel [Events, Actions, Layouts and Styles with Qt] and qnamespace.h.

#### int QMenuData::insertItem (const QString & text, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with text text, optional id id, and optional index.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QIconSet & icon, const QString & text, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, text *text*, optional id *id*, and optional *index*. The icon will be displayed to the left of the text in the item.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QString & text, QPopupMenu \* popup, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with text text, submenu popup, optional id id, and optional index.

The *popup* must be deleted by the programmer or by its parent widget. It is not deleted when this menu item is removed or when the menu is deleted.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QIconSet & icon, const QString & text, QPopupMenu \* popup, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, text *text*, submenu *popup*, optional id *id*, and optional *index*. The icon will be displayed to the left of the text in the item.

The *popup* must be deleted by the programmer or by its parent widget. It is not deleted when this menu item is removed or when the menu is deleted.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

#### int QMenuData::insertItem (const QPixmap & pixmap, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with pixmap pixmap, optional id id, and optional index.

To look best when being highlighted as a menu item, the pixmap should provide a mask (see OPixmap::mask()).

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QIconSet & icon, const QPixmap & pixmap, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, pixmap *pixmap*, optional id *id*, and optional *index*. The icon will be displayed to the left of the pixmap in the item.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QPixmap & pixmap, QPopupMenu \* popup, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with pixmap pixmap, submenu popup, optional id id, and optional index.

The *popup* must be deleted by the programmer or by its parent widget. It is not deleted when this menu item is removed or when the menu is deleted.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

# int QMenuData::insertItem (const QIconSet & icon, const QPixmap & pixmap, QPopupMenu \* popup, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item with icon *icon*, pixmap *pixmap* submenu *popup*, optional id *id*, and optional *index*. The icon will be displayed to the left of the pixmap in the item.

The *popup* must be deleted by the programmer or by its parent widget. It is not deleted when this menu item is removed or when the menu is deleted.

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98], changeItem() [p. 89], setAccel() [p. 98] and connectItem() [p. 90].

### int QMenuData::insertItem (QWidget \* widget, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a menu item that consists of the widget widget with optional id id, and optional index.

Ownership of *widget* is transferred to the popup menu or to the menu bar.

Theoretically, any widget can be inserted into a popup menu. In practice, this only makes sense with certain widgets.

If a widget is not focus-enabled (see QWidget::isFocusEnabled()), the menu treats it as a separator; this means that the item is not selectable and will never get focus. In this way you can, for example, simply insert a QLabel if you need a popup menu with a title.

If the widget is focus-enabled it will get focus when the user traverses the popup menu with the arrow keys. If the widget does not accept ArrowUp and ArrowDown in its key event handler, the focus will move back to the menu

when the respective arrow key is hit one more time. This works with a QLineEdit, for example. If the widget accepts the arrow key itself, it must also provide the possibility to put the focus back on the menu again by calling QWidget::focusNextPrevChild(). Futhermore, if the embedded widget closes the menu when the user made a selection, this can be done safely by calling

```
if ( isVisible() &&
    parentWidget() &&
    parentWidget()->inherits("QPopupMenu") )
    parentWidget()->close();
```

Returns the allocated menu identifier number (id if id >= 0).

See also removeItem() [p. 98].

# int QMenuData::insertItem (const QIconSet & icon, QCustomMenuItem \* custom, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a custom menu item custom with an icon and with optional id id, and optional index.

This only works with popup menus. It is not supported for menu bars. Ownership of *custom* is transferred to the popup menu.

If you want to connect a custom item to a certain slot, use connectItem().

Returns the allocated menu identifier number (id if id >= 0).

See also connectItem() [p. 90], removeItem() [p. 98] and QCustomMenuItem [p. 6].

#### int QMenuData::insertItem (QCustomMenuItem \* custom, int id = -1, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Inserts a custom menu item *custom* with optional id id, and optional index.

This only works with popup menus. It is not supported for menu bars. Ownership of *custom* is transferred to the popup menu.

If you want to connect a custom item to a certain slot, use connectItem().

Returns the allocated menu identifier number (id if id >= 0).

See also connectItem() [p. 90], removeItem() [p. 98] and QCustomMenuItem [p. 6].

#### int QMenuData::insertSeparator (int index = -1)

Inserts a separator at position index. The separator becomes the last menu item if index is negative.

In a popup menu a separator is rendered as a horizontal line. In a Motif menu bar a separator is spacing, so the rest of the items (normally just "Help") are drawn right-justified. In a Windows menu bar separators are ignored (to comply with the Windows style guidelines).

Examples: addressbook/mainwindow.cpp, mdi/application.cpp, menu/menu.cpp, progress/progress.cpp, qwerty/qwerty.cpp, scrollview/scrollview.cpp and showimg/showimg.cpp.

#### int QPopupMenu::insertTearOffHandle (int id = -1, int index = -1)

Inserts a tear-off handle into the menu. A tear-off handle is a special menu item that creates a copy of the menu when the menu is selected. This "torn-off" copy lives in a separate window. It contains the same menu items as the original menu, with the exception of the tear-off handle.

The handle item is assigned the identifier id or an automatically generated identifier if id is < 0. The generated identifiers (negative integers) are guaranteed to be unique within the entire application.

The *index* specifies the position in the menu. The tear-off handle is appended at the end of the list if *index* is negative.

Example: menu/menu.cpp.

#### bool QPopupMenu::isCheckable () const

Returns TRUE if the display of check marks on menu items is enabled; otherwise returns FALSE. See the "checkable" [p. 130] property for details.

#### bool QMenuData::isItemChecked (int id) const

Returns TRUE if the menu item with the id id has been checked; otherwise returns FALSE.

See also setItemChecked() [p. 99].

Examples: progress/progress.cpp and showing/showing.cpp.

#### bool QMenuData::isItemEnabled (int id) const

Returns TRUE if the item with identifier id is enabled; otherwise returns FALSE See also setItemEnabled() [p. 99].

### int QPopupMenu::itemHeight(int row) const [protected]

Calculates the height in pixels of the item in row row.

### int QPopupMenu::itemHeight (QMenuItem \* mi) const [protected]

This is an overloaded member function, provided for convenience. It behaves essentially like the above function. Calculates the height in pixels of the menu item mi.

#### int QMenuData::itemParameter (int id) const

Returns the parameter of the activation signal of item *id*.

If no parameter has been specified for this item with setItemParameter(), the value defaults to id.

See also connectItem() [p. 90], disconnectItem() [p. 91] and setItemParameter() [p. 99].

#### QPixmap \* QMenuData::pixmap (int id) const

Returns the pixmap that has been set for menu item id, or 0 if no pixmap has been set.

See also changeItem() [p. 89], text() [p. 99] and iconSet() [p. 91].

#### void QPopupMenu::popup ( const QPoint & pos, int indexAtPoint = 0 )

Displays the popup menu so that the item number *indexAtPoint* will be at the specified *global* position *pos*. To translate a widget's local coordinates into global coordinates, use QWidget::mapToGlobal().

When positioning a popup with exec() or popup(), bear in mind that you cannot rely on the popup menu's current size(). For performance reasons, the popup adapts its size only when necessary, so in many cases, the size before and after the show is different. Instead, use sizeHint(). It calculates the proper size depending on the menu's current contents.

Examples: listviews/listviews.cpp and qtimage/qtimage.cpp.

#### void QMenuData::removeItem ( int id )

Removes the menu item that has the identifier id.

See also removeItemAt() [p. 98] and clear() [p. 90].

#### void QMenuData::removeItemAt ( int index )

Removes the menu item at position index.

See also removeItem() [p. 98] and clear() [p. 90].

#### void QMenuData::setAccel ( const QKeySequence & key, int id )

Sets the accelerator key for the menu item id to key.

An accelerator key consists of a key code and a combination of the modifiers SHIFT, CTRL, ALT or UNICODE\_ACCEL (OR'ed or added). The header file quamespace.h contains a list of key codes.

Defining an accelerator key produces a text that is added to the menu item; for instance, CTRL + Key\_O produces "Ctrl+O". The text is formatted differently for different platforms.

Note that keyboard accelerators in Qt are not application-global, instead they are bound to a certain top-level window. For example, accelerators in QPopupMenu items only work for menus that are associated with a certain window. This is true for popup menus that live in a menu bar since their accelerators will then be installed in the menu bar itself. This also applies to stand-alone popup menus that have a top-level widget in their parentWidget() chain. The menu will then install its accelerator object on that top-level widget. For all other cases use an independent QAccel object.

#### Example:

If you need to translate accelerators, use QAccel::stringToKey():

```
fileMenu->setAccel( QAccel::stringToKey(tr("Ctrl+0")), 67 );
```

You can also specify the accelerator in the insertItem() function. You may prefer to use QAction to associate accelerators with menu items.

See also accel() [p. 89], insertItem() [p. 92], QAccel [Events, Actions, Layouts and Styles with Qt], qnamespace.h and QAction [Events, Actions, Layouts and Styles with Qt].

Example: menu/menu.cpp.

#### void QPopupMenu::setActiveItem(int i) [virtual]

Sets the currently active item to *i* and repaints as necessary.

#### void QPopupMenu::setCheckable (bool) [virtual]

Sets whether the display of check marks on menu items is enabled. See the "checkable" [p. 130] property for details.

#### void QMenuData::setItemChecked ( int id, bool check )

If *check* is TRUE, checks the menu item with id *id*; otherwise unchecks the menu item with id *id*. Calls QPopup-Menu::setCheckable(TRUE) if necessary.

See also isItemChecked() [p. 97].

Examples: grapher/grapher.cpp, mdi/application.cpp, menu/menu.cpp, progress/progress.cpp, scrollview/scrollview.cpp and showimg/showimg.cpp.

#### void QMenuData::setItemEnabled (int id, bool enable)

If enable is TRUE, enables the menu item with identifier id; otherwise disables the menu item with identifier id. See also isItemEnabled() [p. 97].

Examples: mdi/application.cpp, menu/menu.cpp, progress/progress.cpp and showimg/showimg.cpp.

#### bool QMenuData::setItemParameter (int id, int param)

Sets the parameter of the activation signal of item id to param.

If any receiver takes an integer parameter, this value is passed.

See also connectItem() [p. 90], disconnectItem() [p. 91] and itemParameter() [p. 97].

Example: mdi/application.cpp.

#### void QMenuData::setWhatsThis (int id, const QString & text)

Sets text as What's This help for the menu item with identifier id.

See also whatsThis() [p. 100].

Examples: application/application.cpp and mdi/application.cpp.

#### QString QMenuData::text(intid) const

Returns the text that has been set for menu item id, or a null string if no text has been set.

See also changeItem() [p. 89], pixmap() [p. 98] and iconSet() [p. 91].

Examples: qdir/qdir.cpp and showimg/showimg.cpp.

#### void QPopupMenu::updateItem(int id) [virtual]

Updates the item with identity id.

Reimplemented from QMenuData [p. 100].

#### QString QMenuData::whatsThis (int id) const

Returns the What's This help text for the item with identifier *id* or QString::null if no text has yet been defined. See also setWhatsThis() [p. 99].

# **Property Documentation**

#### bool checkable

This property holds whether the display of check marks on menu items is enabled.

When TRUE, the display of check marks on menu items is enabled. Checking is always enabled when in Windows-style.

See also QMenuData::setItemChecked() [p. 99].

Set this property's value with setCheckable() and get this property's value with isCheckable().

# **QProgressDialog Class Reference**

The QProgressDialog class provides feedback on the progress of a slow operation.

#include <qprogressdialog.h>

Inherits QDialog [p. 12].

#### **Public Members**

- **QProgressDialog** (QWidget \* creator = 0, const char \* name = 0, bool modal = FALSE, WFlags f = 0)
- **QProgressDialog** (const QString & labelText, const QString & cancelButtonText, int totalSteps, QWidget \* creator = 0, const char \* name = 0, bool modal = FALSE, WFlags f = 0)
- ~QProgressDialog ()
- void **setLabel** (QLabel \* label)
- void **setCancelButton** (QPushButton \* cancelButton)
- void **setBar** ( OProgressBar \* bar )
- bool wasCancelled () const
- int totalSteps () const
- int **progress**() const
- virtual OSize sizeHint () const
- OString labelText () const
- void **setAutoReset** (bool b)
- bool autoReset () const
- void **setAutoClose** (bool b)
- bool autoClose () const
- int minimumDuration() const

# **Public Slots**

- void cancel()
- void reset()
- void **setTotalSteps** (int totalSteps)
- void **setProgress** (int progress)
- void **setLabelText** (const QString &)
- void **setCancelButtonText** (const QString & cancelButtonText)
- void **setMinimumDuration** (int ms)

## Signals

■ void cancelled()

### **Properties**

- bool autoClose whether the dialog gets hidden by reset()
- bool autoReset whether the progress dialog calls reset() as soon as progress() equals totalSteps()
- QString labelText the label's text
- int minimumDuration the time that the progress should run for before the dialog opens
- int **progress** the current amount of progress made
- int totalSteps the total number of steps
- bool wasCancelled whether the dialog was cancelled *(read only)*

#### **Protected Slots**

■ void forceShow()

### **Detailed Description**

The QProgressDialog class provides feedback on the progress of a slow operation.

A progress dialog is used to give the user an indication of how long an operation is going to take to perform, and to indicate that the application has not frozen. It can also gives the user an opportunity to abort the operation.

A common problem with progress dialogs is that it is difficult to know when to use them; operations take different amounts of time on different computer hardware. QProgressDialog offers a solution to this problem: it estimates the time the operation will take (based on time for steps), and only shows itself if that estimate is beyond minimumDuration() (4 seconds by default).

Use setTotalSteps() (or the constructor) to set the number of "steps" in the operation and call setProgress() as the operation progresses. The step value can be chosen arbitrarily. It can be the number of files copied, the number of bytes received, the number of iterations through the main loop of your algorithm, or some other suitable unit. Progress starts at 0, and the progress dialog shows that the operation has completeed when you call setProgress() with totalSteps() as argument.

The dialog automatically resets and hides itself at the end of the operation. Use setAutoReset() and setAutoClose() to change this behavior.

There are two ways of using QProgressDialog: modal and non-modal.

Using a modal QProgressDialog is simpler for the programmer, but you have to call qApp->processEvents() to keep the event loop running to ensure that the application doesn't freeze. Do the operation in a loop, call setProgress() at intervals, and check for cancellation with wasCancelled(). For example:

```
if ( progress.wasCancelled() )
         break;
    //... copy one file
}
progress.setProgress( numFiles );
```

A non-modal progress dialog is suitable for operations that take place in the background, where the user is able to interact with the application. Such operations are typically based on QTimer (or QObject::timerEvent()), QSocketNotifier, or QUrlOperator; or performed in a separate thread. A QProgressBar in the status bar of your main window is often an alternative to a non-modal progress dialog.

You need an event loop to be running. Connect the cancelled() signal to a slot that stops the operation, and call setProgress() at intervals. For example:

```
Operation::Operation( QObject *parent = 0 )
    : QObject( parent ), steps( 0 )
   pd = new QProgressDialog( "Operation in progress.", "Cancel", 100 );
    connect( pd, SIGNAL(cancelled()), this, SLOT(cancel()) );
    t = new QTimer( this );
    connect( t, SIGNAL(timeout()), this, SLOT(perform()) );
    t->start( 0 );
}
void Operation::perform()
   pd->setProgress( steps );
    //... perform one percent of the operation
   steps++;
    if ( steps > pd->totalSteps() )
        t->stop();
}
void Operation::cancel()
    t->stop();
    //... cleanup
}
```

In both modes the progress dialog may be customized by replacing the child widgets with custom widgets by using setLabel(), setBar(), and setCancelButton(). The functions setLabelText() and setCancelButtonText() set the texts shown.



See also QDialog [p. 12], QProgressBar [Widgets with Qt], GUI Design Handbook: Progress Indicator and Dialog Classes.

#### **Member Function Documentation**

QProgressDialog::QProgressDialog (QWidget \* creator = 0, const char \* name = 0, bool modal = FALSE, WFlags f = 0)

Constructs a progress dialog.

Default settings:

- The label text is empty.
- The cancel button text is "Cancel".
- The total number of steps is 100.

The top level parent of the *creator* widget becomes the parent of the dialog. The *name*, *modal*, and the widget flags, *f*, are passed to the QDialog::QDialog() constructor. Note that if *modal* is FALSE (the default), you must have an event loop proceeding for any redrawing of the dialog to occur. If *modal* is TRUE, the dialog ensures that events are processed when needed.

See also labelText [p. 138], setLabel() [p. 136], setCancelButtonText() [p. 136], setCancelButton() [p. 136] and totalSteps [p. 138].

```
QProgressDialog::QProgressDialog (const QString & labelText, const QString & cancelButtonText, int totalSteps, QWidget * creator = 0, const char * name = 0, bool modal = FALSE, WFlags f = 0)
```

Constructs a progress dialog.

The *labelText* is text used to remind the user what is progressing.

The cancelButtonText is the text to display on the cancel button, or 0 if no cancel button is to be shown.

The totalSteps is the total number of steps in the operation of which this progress dialog shows the progress. For example, if the operation is to examine 50 files, this value would be 50. Before examining the first file, call setProgress(0). As each file is processed call setProgress(1), setProgress(2), etc., finally calling setProgress(50) after examining the last file.

The *name*, *modal*, and widget flags, *f*, are passed to the QDialog::QDialog() constructor. Note that if *modal* is FALSE (the default), you will need to have an event loop proceeding for any redrawing of the dialog to occur. If *modal* is TRUE, the dialog ensures that events are processed when needed.

The *creator* argument is the widget to use as the dialog's parent. If *creator* is not a top level widget the argument passed on to the QDialog constructor will be 0.

See also labelText [p. 138], setLabel() [p. 136], setCancelButtonText() [p. 136], setCancelButton() [p. 136] and totalSteps [p. 138].

#### QProgressDialog::~QProgressDialog()

Destroys the progress dialog.

#### bool QProgressDialog::autoClose() const

Returns TRUE if the dialog gets hidden by reset(); otherwise returns FALSE. See the "autoClose" [p. 137] property for details.

#### bool QProgressDialog::autoReset() const

Returns TRUE if the progress dialog calls reset() as soon as progress() equals totalSteps(); otherwise returns FALSE. See the "autoReset" [p. 137] property for details.

#### void QProgressDialog::cancel() [slot]

Resets the progress dialog. wasCancelled() becomes TRUE until the progress dialog is reset. The progress dialog becomes hidden.

#### void QProgressDialog::cancelled() [signal]

This signal is emitted when the cancel button is clicked. It is connected to the cancel() slot by default.

See also was Cancelled [p. 138].

Example: progress/progress.cpp.

#### void QProgressDialog::forceShow () [protected slot]

Shows the dialog if it is still hidden after the algorithm has been started and the minimumDuration is over. See also minimumDuration [p. 138].

#### QString QProgressDialog::labelText() const

Returns the label's text. See the "labelText" [p. 138] property for details.

#### int QProgressDialog::minimumDuration () const

Returns the time that the progress should run for before the dialog opens. See the "minimumDuration" [p. 138] property for details.

#### int QProgressDialog::progress() const

Returns the current amount of progress made. See the "progress" [p. 138] property for details.

#### void QProgressDialog::reset() [slot]

Resets the progress dialog. The progress dialog becomes hidden if autoClose() is TRUE.

See also autoClose [p. 137] and autoReset [p. 137].

#### void QProgressDialog::setAutoClose(bool b)

Sets whether the dialog gets hidden by reset() to b. See the "autoClose" [p. 137] property for details.

#### void QProgressDialog::setAutoReset(bool b)

Sets whether the progress dialog calls reset() as soon as progress() equals totalSteps() to *b*. See the "autoReset" [p. 137] property for details.

#### void QProgressDialog::setBar ( QProgressBar \* bar )

Sets the progress bar widget to bar. The progress dialog resizes to fit. The progress dialog takes ownership of the progress bar which will be deleted when necessary.

#### void QProgressDialog::setCancelButton ( QPushButton \* cancelButton )

Sets the cancel button to the push button, *cancelButton*. The progress dialog takes ownership of this button which will be deleted when necessary, so do not pass the address of an object that is on the stack, i.e. use new() to create the button.

See also setCancelButtonText() [p. 136].

#### void QProgressDialog::setCancelButtonText (const QString & cancelButtonText) [slot]

Sets the cancel button's text to *cancelButtonText*.

See also setCancelButton() [p. 136].

#### void QProgressDialog::setLabel (QLabel \* label)

Sets the label to *label*. The progress dialog resizes to fit. The label becomes owned by the progress dialog and will be deleted when necessary, so do not pass the address of an object on the stack.

See also labelText [p. 138].

Example: progress/progress.cpp.

#### void QProgressDialog::setLabelText ( const QString & ) [slot]

Sets the label's text. See the "labelText" [p. 138] property for details.

#### void QProgressDialog::setMinimumDuration(int ms) [slot]

Sets the time that the progress should run for before the dialog opens to ms. See the "minimumDuration" [p. 138] property for details.

#### void QProgressDialog::setProgress ( int progress ) [slot]

Sets the current amount of progress made to progress. See the "progress" [p. 138] property for details.

#### void QProgressDialog::setTotalSteps (int totalSteps) [slot]

Sets the total number of steps to totalSteps. See the "totalSteps" [p. 138] property for details.

#### QSize QProgressDialog::sizeHint() const [virtual]

Returns a size that fits the contents of the progress dialog. The progress dialog resizes itself as required, so you should not need to call this yourself.

#### int QProgressDialog::totalSteps() const

Returns the total number of steps. See the "totalSteps" [p. 138] property for details.

#### bool QProgressDialog::wasCancelled() const

Returns TRUE if the dialog was cancelled; otherwise returns FALSE. See the "wasCancelled" [p. 138] property for details.

## **Property Documentation**

#### bool autoClose

This property holds whether the dialog gets hidden by reset().

The default is TRUE.

See also autoReset [p. 137].

Set this property's value with setAutoClose() and get this property's value with autoClose().

#### bool autoReset

This property holds whether the progress dialog calls reset() as soon as progress() equals totalSteps().

The default is TRUE.

See also autoClose [p. 137].

Set this property's value with setAutoReset() and get this property's value with autoReset().

#### **QString labelText**

This property holds the label's text.

The default text is OString::null.

Set this property's value with setLabelText() and get this property's value with labelText().

#### int minimumDuration

This property holds the time that the progress should run for before the dialog opens.

The dialog will not appear if the anticipated duration of the progressing task is less than the minimum duration.

If set to 0, the dialog is always shown as soon as any progress is set. The default is 4000.

Set this property's value with setMinimumDuration() and get this property's value with minimumDuration().

#### int progress

This property holds the current amount of progress made.

For the progress dialog to work as expected, you should initially set this property to 0 and finally set it to QProgressDialog::totalSteps(); you can call setProgress() any number of times in-between.

Warning: If the progress dialog is modal (see QProgressDialog::QProgressDialog()), this function calls QApplication::processEvents(), so take care that this does not cause undesirable re-entrancy in your code. For example, don't use a QProgressDialog inside a paintEvent()!

See also totalSteps [p. 138].

Set this property's value with setProgress() and get this property's value with progress().

#### int totalSteps

This property holds the total number of steps.

The default is 0.

Set this property's value with setTotalSteps() and get this property's value with totalSteps().

#### bool wasCancelled

This property holds whether the dialog was cancelled.

Get this property's value with wasCancelled().

See also progress [p. 138].

# **QTabDialog Class Reference**

The QTabDialog class provides a stack of tabbed widgets.

#include <qtabdialog.h>

Inherits QDialog [p. 12].

#### **Public Members**

- QTabDialog (QWidget \* parent = 0, const char \* name = 0, bool modal = FALSE, WFlags f = 0)
- ~QTabDialog()
- virtual void **setFont** (const QFont & font)
- void addTab (QWidget \* child, const QString & label)
- void addTab (QWidget \* child, const QIconSet & iconset, const QString & label)
- void addTab (QWidget \* child, QTab \* tab)
- void **insertTab** (QWidget \* child, const QString & label, int index = -1)
- void insertTab (QWidget \* child, const QIconSet & iconset, const QString & label, int index = -1)
- void **insertTab** (QWidget \* child, QTab \* tab, int index = -1)
- void **changeTab** (QWidget \* w, const QString & label)
- void **changeTab** (QWidget \* w, const QIconSet & iconset, const QString & label)
- bool isTabEnabled (QWidget \* w) const
- void **setTabEnabled** ( QWidget \* w, bool enable )
- bool isTabEnabled (const char \* name) const (obsolete)
- void setTabEnabled (const char \* name, bool enable) (obsolete)
- void **showPage** (OWidget \* w)
- void removePage (QWidget \* w)
- QString tabLabel (QWidget \* w)
- QWidget \* currentPage() const
- void **setDefaultButton** (const QString & text)
- void setDefaultButton ()
- bool hasDefaultButton() const
- void **setHelpButton** (const QString & text)
- void setHelpButton ()
- bool hasHelpButton() const
- void **setCancelButton** (const QString & text)
- void **setCancelButton**()
- bool hasCancelButton() const

- void **setApplyButton** (const QString & text)
- void **setApplyButton**()
- bool hasApplyButton() const
- void **setOkButton** (const OString & text)
- void setOkButton()
- bool hasOkButton () const

## **Signals**

- void aboutToShow()
- void applyButtonPressed ()
- void cancelButtonPressed()
- void defaultButtonPressed ()
- void helpButtonPressed ()
- void **currentChanged** ( QWidget \*)
- void selected (const QString &) (obsolete)

#### **Protected Members**

- void **setTabBar** ( QTabBar \* tb )
- QTabBar \* tabBar () const

# **Detailed Description**

The QTabDialog class provides a stack of tabbed widgets.

A tabbed dialog is one in which several "pages" are available. The user selects which page to see and use by clicking on its tab or by pressing the indicated Alt+*letter* key combination.

QTabDialog provides a tab bar consisting of single row of tabs at the top; each tab has an associated widget which is that tab's "page". In addition, QTabDialog provides an OK button and the following optional buttons: Apply, Cancel, Defaults and Help.

QTabDialog doesn't provide for tabs on the sides or bottom, nor can you set or retrieve the visible page. If you need more functionality than QTabDialog provides, consider creating a QDialog and using a QTabBar with QTabWidgets.

The normal way to use QTabDialog is to do the following in the constructor:

- 1. Create a QTabDialog.
- 2. Create a QWidget for each of the pages in the tab dialog, insert children into it, set up geometry management for it, and use addTab() (or insertTab()) to set up a tab and keyboard accelerator for it.
- 3. Set up the buttons for the tab dialog using setOkButton(), setApplyButton(), setDefaultsButton(), setCancelButton() and setHelpButton().
- 4. Connect to the signals and slots.

If you don't call addTab() the page you have created will not be visible. Don't confuse the object name you supply to the QWidget constructor and the tab label you supply to addTab(); addTab() takes a name that indicates an accelerator and is meaningful and descriptive to the user, whereas the widget name is used primarily for debugging.

Almost all applications have to connect the applyButtonPressed() signal to something. applyButtonPressed() is emitted when either OK or Apply is clicked, and your slot must copy the dialog's state into the application.


There are also several other signals which may be useful:

- cancelButtonPressed() is emitted when the user clicks Cancel.
- defaultButtonPressed() is emitted when the user clicks Defaults; the slot it is connected to should reset the state of the dialog to the application defaults.
- helpButtonPressed() is emitted when the user clicks Help.
- aboutToShow() is emitted at the start of show(); if there is any chance that the state of the application may change between the creation of the tab dialog and the time show() is called, you must connect this signal to a slot that resets the state of the dialog.
- currentChanged() is emitted when the user selects some page.

Each tab is either enabled or disabled at any given time (see setTabEnabled()). If a tab is enabled the tab text is drawn in black and the user can select that tab. If it is disabled the tab is drawn in a different way and the user cannot select that tab. Note that even if a tab is disabled, the page can still be visible; for example, if all of the tabs happen to be disabled.

You can change a tab's label and iconset using changeTab(). A tab page can be removed with removePage() and shown with showPage(). The current page is given by currentPage().

Most of the functionality in QTabDialog is provided by a QTabWidget.



See also QDialog [p. 12] and Dialog Classes.

#### **Member Function Documentation**

QTabDialog::QTabDialog (QWidget \* parent = 0, const char \* name = 0, bool modal = FALSE, WFlags f = 0)

Constructs a QTabDialog with only an OK button. The *parent*, *name*, *modal* and widget flag, *f*, arguments are passed on to the QDialog constructor.

QTabDialog::~QTabDialog()

Destroys the tab dialog.

#### void QTabDialog::aboutToShow() [signal]

This signal is emitted by show() when it is time to set the state of the dialog's contents. The dialog should reflect the current state of the application when it appears; if there is any possibility that the state of the application may change between the time you call QTabDialog::QTabDialog() and QTabDialog::show(), you should set the dialog's state in a slot and connect this signal to it.

This applies mainly to QTabDialog objects that are kept around hidden, rather than being created, shown, and deleted afterwards.

See also applyButtonPressed() [p. 142], show() [p. 17] and cancelButtonPressed() [p. 143].

#### void QTabDialog::addTab ( QWidget \* child, const QString & label )

Adds another tab and page to the tab view.

The new page is *child*; the tab's label is *label*. Note the difference between the widget name (which you supply to widget constructors and to setTabEnabled(), for example) and the tab label. The name is internal to the program and invariant, whereas the label is shown on-screen and may vary according to language and other factors.

If the tab's *label* contains an ampersand, the letter following the ampersand is used as an accelerator for the tab, e.g. if the label is "Bro&wse" then Alt+W becomes an accelerator which will move the focus to this tab.

If you call addTab() after show() the screen will flicker and the user may be confused.

See also insertTab() [p. 144].

#### void QTabDialog::addTab (QWidget \* child, const QIconSet & iconset, const QString & label)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

This version of the function shows the iconset as well as the label on the tab of child.

#### void QTabDialog::addTab ( QWidget \* child, QTab \* tab )

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

This is a lower-level method for adding tabs, similar to the other addTab() method. It is useful if you are using setTabBar() to set a QTabBar subclass with an overridden QTabBar::paint() routine for a subclass of QTab.

The *child* is the widget to be placed on the new tab page. The *tab* is the tab to display on the tab page — normally this shows a label or an icon that identifies the tab page.

#### void QTabDialog::applyButtonPressed () [signal]

This signal is emitted when the Apply or OK button is clicked.

It should be connected to a slot (or several slots) that change the application's state according to the state of the dialog. See also cancelButtonPressed() [p. 143], defaultButtonPressed() [p. 143] and setApplyButton() [p. 145].

#### void QTabDialog::cancelButtonPressed() [signal]

This signal is emitted when the Cancel button is clicked. It is automatically connected to QDialog::reject(), which will hide the dialog.

The Cancel button should not change the application's state at all, so you should generally not need to connect it to any slot.

See also applyButtonPressed() [p. 142], defaultButtonPressed() [p. 143] and setCancelButton() [p. 146].

#### void QTabDialog::changeTab ( QWidget \* w, const QIconSet & iconset, const QString & label )

Changes tab page w's iconset to iconset and label to label.

#### void QTabDialog::changeTab ( QWidget \* w, const QString & label )

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Defines a new *label* for the tab of page w

#### void QTabDialog::currentChanged ( QWidget \* ) [signal]

This signal is emitted whenever the current page changes.

See also currentPage() [p. 143], showPage() [p. 148] and tabLabel() [p. 148].

#### QWidget \* QTabDialog::currentPage () const

Returns a pointer to the page currently being displayed by the tab dialog. The tab dialog does its best to make sure that this value is never 0 (but if you try hard enough, it can be).

#### void QTabDialog::defaultButtonPressed () [signal]

This signal is emitted when the Defaults button is pressed. It should reset the dialog (but not the application) to the "factory defaults".

The application's state should not be changed until the user clicks Apply or OK.

See also applyButtonPressed() [p. 142], cancelButtonPressed() [p. 143] and setDefaultButton() [p. 146].

#### bool QTabDialog::hasApplyButton() const

Returns TRUE if the tab dialog has an Apply button; otherwise returns FALSE.

See also setApplyButton() [p. 145], applyButtonPressed() [p. 142], hasCancelButton() [p. 144] and hasDefaultButton() [p. 144].

#### bool QTabDialog::hasCancelButton() const

Returns TRUE if the tab dialog has a Cancel button; otherwise returns FALSE.

See also setCancelButton() [p. 146], cancelButtonPressed() [p. 143], hasApplyButton() [p. 143] and hasDefaultButton() [p. 144].

#### bool QTabDialog::hasDefaultButton() const

Returns TRUE if the tab dialog has a Defaults button; otherwise returns FALSE.

See also setDefaultButton() [p. 146], defaultButtonPressed() [p. 143], hasApplyButton() [p. 143] and hasCancelButton() [p. 144].

#### bool QTabDialog::hasHelpButton() const

Returns TRUE if the tab dialog has a Help button; otherwise returns FALSE.

See also setHelpButton() [p. 147], helpButtonPressed() [p. 144], hasApplyButton() [p. 143] and hasCancelButton() [p. 144].

#### bool QTabDialog::hasOkButton() const

Returns TRUE if the tab dialog has an OK button; otherwise returns FALSE.

See also setOkButton() [p. 147], hasApplyButton() [p. 143], hasCancelButton() [p. 144] and hasDefaultButton() [p. 144].

#### void QTabDialog::helpButtonPressed() [signal]

This signal is emitted when the Help button is pressed. It could be used to present information about how to use the dialog.

See also applyButtonPressed() [p. 142], cancelButtonPressed() [p. 143] and setHelpButton() [p. 147].

#### void QTabDialog::insertTab ( QWidget \* child, const QString & label, int index = -1 )

Inserts another tab and page to the tab view.

The new page is *child*; the tab's label is *label*. Note the difference between the widget name (which you supply to widget constructors and to setTabEnabled(), for example) and the tab label. The name is internal to the program and invariant, whereas the label is shown on-screen and may vary according to language and other factors.

If the tab's *label* contains an ampersand, the letter following the ampersand is used as an accelerator for the tab, e.g. if the label is "Bro&wse" then Alt+W becomes an accelerator which will move the focus to this tab.

If *index* is not specified, the tab is simply added. Otherwise it is inserted at the specified position.

If you call insertTab() after show(), the screen will flicker and the user may be confused.

See also addTab() [p. 142].

# 

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

This version of the function shows the iconset as well as the label on the tab of child.

#### void QTabDialog::insertTab (QWidget \* child, QTab \* tab, int index = -1)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

This is a lower-level method for inserting tabs, similar to the other insertTab() method. It is useful if you are using setTabBar() to set a QTabBar subclass with an overridden QTabBar::paint() routine for a subclass of QTab.

The *child* is the widget to be placed on the new tab page. The *tab* is the tab to display on the tab page — normally this shows a label or an icon that identifies the tab page. The *index* is the position where this tab page should be inserted.

### bool QTabDialog::isTabEnabled (QWidget \* w) const

Returns TRUE if the page w is enabled; otherwise returns FALSE.

See also setTabEnabled() [p. 147] and QWidget::enabled [Widgets with Qt].

# bool QTabDialog::isTabEnabled (const char \* name) const

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

Returns TRUE if the page with object name name is enabled and FALSE if it is disabled.

If name is 0 or not the name of any of the pages, isTabEnabled() returns FALSE.

See also setTabEnabled() [p. 147] and QWidget::enabled [Widgets with Qt].

#### void QTabDialog::removePage ( QWidget \* w )

Removes page w from this stack of widgets. Does not delete w.

See also showPage() [p. 148], QTabWidget::removePage() [Widgets with Qt] and QWidgetStack::removeWidget() [Widgets with Qt].

# void QTabDialog::selected (const QString &) [signal]

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

This signal is emitted whenever a tab is selected (raised), including during the first show().

See also raise() [Widgets with Qt].

#### void QTabDialog::setApplyButton ( const QString & text )

Adds an Apply button to the dialog. The button's text is set to text.

The Apply button should apply the current settings in the dialog box to the application while keeping the dialog visible.

When Apply is clicked, the applyButtonPressed() signal is emitted.

If text is a null string, no button is shown.

See also setCancelButton() [p. 146], setDefaultButton() [p. 146] and applyButtonPressed() [p. 142].

### void QTabDialog::setApplyButton()

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Adds an Apply button to the dialog. The button's text is set to a localizable "Apply".

#### void QTabDialog::setCancelButton ( const QString & text )

Adds a Cancel button to the dialog. The button's text is set to text.

The cancel button should always return the application to the state it was in before the tab view popped up, or if the user has clicked Apply, back to the state immediately after the last Apply.

When Cancel is clicked, the cancelButtonPressed() signal is emitted. The dialog is closed at the same time.

If text is a null string, no button is shown.

See also setApplyButton() [p. 145], setDefaultButton() [p. 146] and cancelButtonPressed() [p. 143].

# void QTabDialog::setCancelButton()

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Adds a Cancel button to the dialog. The button's text is set to a localizable "Cancel".

#### void QTabDialog::setDefaultButton ( const QString & text )

Adds a Defaults button to the dialog. The button's text is set to text.

The Defaults button should set the dialog (but not the application) back to the application defaults.

When Defaults is clicked, the defaultButtonPressed() signal is emitted.

If text is a null string, no button is shown.

See also setApplyButton() [p. 145], setCancelButton() [p. 146] and defaultButtonPressed() [p. 143].

#### void QTabDialog::setDefaultButton()

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Adds a Defaults button to the dialog. The button's text is set to a localizable "Defaults".

# void QTabDialog::setFont ( const QFont & font ) [virtual]

Sets the font for the tabs to font.

If the widget is visible, the display is updated with the new font immediately. There may be some geometry changes, depending on the size of the old and new fonts.

Reimplemented from QWidget [Widgets with Qt].

### void QTabDialog::setHelpButton ( const QString & text )

Adds a Help button to the dialog. The button's text is set to text.

When Help is clicked, the helpButtonPressed() signal is emitted.

If text is a null string, no button is shown.

See also setApplyButton() [p. 145], setCancelButton() [p. 146] and helpButtonPressed() [p. 144].

# void QTabDialog::setHelpButton()

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Adds a Help button to the dialog. The button's text is set to a localizable "Help".

# void QTabDialog::setOkButton(const QString & text)

Adds an OK button to the dialog and sets the button's text to text.

When the OK button is clicked, the applyButtonPressed() signal is emitted, and the current settings in the dialog box should be applied to the application. The dialog then closes.

If text is a null string, no button is shown.

See also setCancelButton() [p. 146], setDefaultButton() [p. 146] and applyButtonPressed() [p. 142].

#### void QTabDialog::setOkButton()

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Adds an OK button to the dialog. The button's text is set to a localizable "OK".

#### void QTabDialog::setTabBar ( QTabBar \* tb) [protected]

Replaces the QTabBar heading the dialog by the given tab bar, tb. Note that this must be called before any tabs have been added, or the behavior is undefined.

See also tabBar() [p. 148].

#### void QTabDialog::setTabEnabled ( QWidget \* w, bool enable )

If enable is TRUE the page w is enabled; otherwise w is disabled. The page's tab is redrawn appropriately.

QTabWidget uses QWidget::setEnabled() internally, rather than keeping a separate flag.

Note that even a disabled tab/page may be visible. If the page is already visible QTabWidget will not hide it; if all the pages are disabled QTabWidget will show one of them.

See also isTabEnabled() [p. 145] and QWidget::enabled [Widgets with Qt].

#### void QTabDialog::setTabEnabled ( const char \* name, bool enable )

**This function is obsolete.** It is provided to keep old source working. We strongly advise against using it in new code.

Finds the page with object name *name*, enables/disables it according to the value of *enable* and redraws the page's tab appropriately.

QTabDialog uses QWidget::setEnabled() internally, rather than keeping a separate flag.

Note that even a disabled tab/page may be visible. If the page is already visible QTabDialog will not hide it; if all the pages are disabled QTabDialog will show one of them.

The object name is used (rather than the tab label) because the tab text may not be invariant in multi-language applications.

See also is Tab Enabled () [p. 145] and QWidget:: enabled [Widgets with Qt].

### void QTabDialog::showPage ( QWidget \* w )

Ensures that widget w is shown. This is useful mainly for accelerators.

Warning: If used carelessly, this function can easily surprise or confuse the user.

See also QTabBar::currentTab [Widgets with Qt].

#### QTabBar \* QTabDialog::tabBar () const [protected]

Returns the currently set QTabBar.

See also setTabBar() [p. 147].

# QString QTabDialog::tabLabel (QWidget \* w)

Returns the text in the tab for page w.

The QToolBar class provides a movable panel containing widgets such as tool buttons.

```
#include <qtoolbar.h>
Inherits QDockWindow [p. 23].
```

#### **Public Members**

- QToolBar (const QString & label, QMainWindow \*, ToolBarDock = DockTop, bool newLine = FALSE, const char \* name = 0) (obsolete)
- **QToolBar** (const QString & label, QMainWindow \* mainWindow, QWidget \* parent, bool newLine = FALSE, const char \* name = 0, WFlags f = 0)
- QToolBar ( QMainWindow \* parent = 0, const char \* name = 0 )
- void addSeparator()
- QMainWindow \* mainWindow () const
- virtual void **setStretchableWidget** (QWidget \* w)
- virtual void **setLabel** (const OString &)
- QString label () const
- virtual void **clear** ()

# **Properties**

■ QString label — the label of the toolbar

# **Detailed Description**

The QToolBar class provides a movable panel containing widgets such as tool buttons.

A toolbar is a panel that contains a set of controls, usually represented by small icons. It's purpose is to provide quick access to frequently used commands or options. Within a QMainWindow the user can drag toolbars within and between the dock areas. Toolbars can also be dragged out of any dock area to float freely as top level windows.

QToolBar is a specialization of QDockWindow, and so provides all the functionality of a QDockWindow.

To use QToolBar you simply create a QToolBar as a child of a QMainWindow, create a number of QToolButton widgets (or other widgets) in left to right (or top to bottom) order and call addSeparator() when you want a separator. When a toolbar is floated the caption used is the label given in the constructor call. This can be changed with setLabel().

```
QToolBar * fileTools = new QToolBar( this, "file operations" );
fileTools->setLabel( "File Operations" );
fileOpenAction->addTo( fileTools );
fileSaveAction->addTo( fileTools );
```

This extract from the application/application.cpp example shows the creation of a new toolbar as a child of a QMain-Window and adding two QActions.

You may use most widgets within a toolbar, with QToolButton and QComboBox being the most common.

QToolBars, like QDockWindows, are located in QDockAreas or float as top level windows. QMainWindow provides four QDockAreas (top, left, right and bottom). When you create a new toolbar (as in the example above) as a child of a QMainWindow the toolbar will be added to the top dock area. You can move it to another dock area (or float it) by calling QMainWindow::moveDockWindow(). QDock areas lay out their windows in Lines.

If the main window is resized so that the area occupied by the toolbar is too small to show all its widgets a little arrow button (which looks like a right-pointing chevron, 'ż') will appear at the right or bottom of the toolbar depending on its orientation. Clicking this button pops up a menu that shows the 'overflowing' items.

Usually a toolbar will get precisely the space it needs. However, with setHorizontalStretchable(), setVerticalStretchable() or setStretchableWidget() you can tell the main window to expand the toolbar to fill all available space in the specified orientation.

The toolbar arranges its buttons either horizontally or vertically (see orientation() for details). Generally, QDockArea will set the orientation correctly for you, but you can set it yourself with setOrientation() and track any changes by connecting to the orientationChanged() signal.

You can use the clear() method to remove all items from a toolbar.

See also QToolButton [p. 153], QMainWindow [p. 58], Parts of Isys on Visual Design, GUI Design Handbook: Tool Bar and Main Window and Related Classes.

#### **Member Function Documentation**

```
QToolBar::QToolBar (const QString & label, QMainWindow *, ToolBarDock = DockTop, bool newLine = FALSE, const char * name = 0)
```

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

```
QToolBar::QToolBar (const QString & label, QMainWindow * mainWindow,
QWidget * parent, bool newLine = FALSE, const char * name = 0, WFlags f = 0)
```

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Constructs an empty horizontal toolbar.

The toolbar is a child of *parent* and is managed by *mainWindow*. The *label* and *newLine* parameters are passed straight to QMainWindow::addDockWindow(). *name* is the object name and *f* is the widget flags.

Use this constructor if you want to create torn-off (undocked, floating) toolbars or toolbars in the status bar.

## QToolBar::QToolBar (QMainWindow \* parent = 0, const char \* name = 0)

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Constructs an empty toolbar, with parent parent and name name, in its parent's top dock area, without any label and without requiring a newline.

#### void QToolBar::addSeparator()

Adds a separator to the right/bottom of the toolbar.

Examples: fileiconview/mainwindow.cpp, helpviewer/helpwindow.cpp, qfd/fontdisplayer.cpp and scribble/scribble.cpp.

#### void QToolBar::clear() [virtual]

Deletes all the toolbar's child widgets.

# QString QToolBar::label() const

Returns the label of the toolbar. See the "label" [p. 152] property for details.

# QMainWindow \* QToolBar::mainWindow () const

Returns a pointer to the QMainWindow which manages this toolbar.

#### void QToolBar::setLabel ( const QString & ) [virtual]

Sets the label of the toolbar. See the "label" [p. 152] property for details.

#### void QToolBar::setStretchableWidget ( QWidget \* w ) [virtual]

Sets the widget w to be expanded if this toolbar is requested to stretch.

The request to stretch might occur because QMainWindow right-justifies the dock it's in, or because this toolbar's isVerticalStretchable() or isHorizontalStretchable() is set to TRUE.

If you call this function and the toolbar is not yet stretchable, setStretchable() is called.

See also QMainWindow::rightJustification [p. 74], setVerticalStretchable() [p. 30] and setHorizontalStretchable() [p. 29].

Examples: fileiconview/mainwindow.cpp and helpviewer/helpwindow.cpp.

# **Property Documentation**

# **QString label**

This property holds the label of the toolbar.

If the toolbar is floated the label becomes the toolbar window's caption. There is no default label text. Set this property's value with setLabel() and get this property's value with label().

# **QToolButton Class Reference**

The QToolButton class provides a quick-access button to commands or options, usually used inside a QToolBar.

#include <qtoolbutton.h>

Inherits QButton [Widgets with Qt].

# **Public Members**

- **QToolButton** (QWidget \* parent, const char \* name = 0)
- **QToolButton** (const QIconSet & iconSet, const QString & textLabel, const QString & grouptext, QObject \* receiver, const char \* slot, QToolBar \* parent, const char \* name = 0)
- **QToolButton** (ArrowType type, QWidget \* parent, const char \* name = 0)
- ~QToolButton()
- void setOnIconSet (const QIconSet &) (obsolete)
- void setOffIconSet (const QIconSet &) (obsolete)
- void setIconSet (const QIconSet & set, bool on) (obsolete)
- QIconSet onIconSet () const (obsolete)
- QIconSet offIconSet () const (obsolete)
- QIconSet iconSet (bool on ) const (obsolete)
- virtual void **setIconSet** (const QIconSet &)
- QIconSet iconSet () const
- bool **usesBigPixmap** () const
- bool usesTextLabel() const
- QString **textLabel**() const
- void **setPopup** (QPopupMenu \* popup)
- QPopupMenu \* **popup** () const
- void **setPopupDelay** (int delay)
- int popupDelay () const
- void **openPopup**()
- void **setAutoRaise** (bool enable)
- bool autoRaise() const

# **Public Slots**

■ virtual void **setUsesBigPixmap** (bool enable)

- virtual void **setUsesTextLabel** (bool enable)
- virtual void **setTextLabel** (const QString & newLabel, bool tipToo)
- virtual void **setToggleButton** (bool enable)
- virtual void **setOn** (bool enable)
- void toggle()
- void **setTextLabel** (const OString &)

# **Properties**

- bool autoRaise whether auto-raising is enabled
- QIconSet **iconSet** the icon set providing the icon shown on the button
- QIconSet offIconSet the icon set that is used when the button is in an "off" state (obsolete)
- bool **on** whether this tool button is on
- QIconSet onIconSet the icon set that is used when the button is in an "on" state (obsolete)
- int **popupDelay** the time delay between pressing the button and the appearance of the associated popup menu in milliseconds
- QString **textLabel** the label of this button
- bool toggleButton whether this tool button is a toggle button
- bool usesBigPixmap whether this toolbutton uses big pixmaps
- bool **usesTextLabel** whether the toolbutton displays a text label below the button pixmap

### **Protected Members**

■ bool uses3D () const

# **Detailed Description**

The QToolButton class provides a quick-access button to commands or options, usually used inside a QToolBar.

A tool button is a special button that provides quick-access to specific commands or options. As opposed to a normal command button, a tool button usually doesn't normally show a text label, but an icon. Its classic usage is to select tools, for example the "pen" tool in a drawing program. This would be implemented with a QToolButton as toggle button (see setToggleButton()).

QToolButton supports auto-raising. In auto-raise mode, the button draws a 3D frame only when the mouse points at it. The feature is automatically turned on when a button is used inside a QToolBar. Change it with setAutoRaise().

A tool button's icon is set as QIconSet. This makes it possible to specify different pixmaps for the disabled and active state. The disabled pixmap is used when the button's functionality is not available. The active pixmap is displayed when the button is auto-raised because the user is pointing at it.

The button's look and dimension is adjustable with setUsesBigPixmap() and setUsesTextLabel(). When used inside a QToolBar, the button automatically adjusts to QMainWindow's settings (see QMainWindow::setUsesTextLabel() and QMainWindow::setUsesBigPixmaps()).

A tool button can offer additional choices in a popup menu. The feature is sometimes used with the "Back" button in a web browser. After pressing the button down for awhile, a menu pops up showing all possible pages to browse back.

QToolButton Class Reference 155

With QToolButton you can set a popup menu using setPopup(). The default delay is 600ms; you may adjust it with setPopupDelay().

See also QPushButton [Widgets with Qt], QToolBar [p. 149], QMainWindow [p. 58], GUI Design Handbook: Push Button and Basic Widgets.

#### **Member Function Documentation**

QToolButton::QToolButton (QWidget \* parent, const char \* name = 0)

Constructs an empty tool button with parent parent and name name.

QToolButton::QToolButton (const QIconSet & iconSet, const QString & textLabel, const QString & grouptext, QObject \* receiver, const char \* slot, QToolBar \* parent, const char \* name = 0)

Constructs a tool button that is a child of parent (which must be a QToolBar) and named name.

The tool button will display *iconSet*, with its text label and tool tip set to *textLabel* and its status bar message set to *grouptext*. It will be connected to the *slot* in object *receiver*.

QToolButton::QToolButton (ArrowType type, QWidget \* parent, const char \* name = 0)

Constructs a tool button as an arrow button. The ArrowType *type* defines the arrow direction. Possible values are LeftArrow, RightArrow, UpArrow and DownArrow.

An arrow button has auto-repeat turned on by default.

The parent and name arguments are sent to the QWidget constructor.

QToolButton::~QToolButton()

Destroys the object and frees any allocated resources.

bool QToolButton::autoRaise() const

Returns TRUE if auto-raising is enabled; otherwise returns FALSE. See the "autoRaise" [p. 159] property for details.

QIconSet QToolButton::iconSet() const

Returns the icon set providing the icon shown on the button. See the "iconSet" [p. 159] property for details.

OIconSet OToolButton::iconSet (bool on) const

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

156

Since Qt 3.0, QIconSet contains both the On and Off icons.

For ease of porting, this function ignores the *on* parameter and returns the iconSet property. If you relied on the *on* parameter, you probably want to update your code to use the QIconSet On/Off mechanism.

### QIconSet QToolButton::offIconSet() const

Returns the icon set that is used when the button is in an "off" state. See the "offIconSet" [p. 159] property for details.

# QIconSet QToolButton::onIconSet () const

Returns the icon set that is used when the button is in an "on" state. See the "onIconSet" [p. 159] property for details.

### void QToolButton::openPopup()

Opens (pops up) the associated popup menu. If there is no such menu, this function does nothing. This function does not return until the popup menu has been closed by the user.

# QPopupMenu \* QToolButton::popup() const

Returns the associated popup menu, or 0 if no popup menu has been defined.

See also setPopup() [p. 157].

# int QToolButton::popupDelay() const

Returns the time delay between pressing the button and the appearance of the associated popup menu in milliseconds. See the "popupDelay" [p. 160] property for details.

#### void QToolButton::setAutoRaise ( bool enable )

Sets whether auto-raising is enabled to enable. See the "autoRaise" [p. 159] property for details.

#### void QToolButton::setIconSet ( const QIconSet & ) [virtual]

Sets the icon set providing the icon shown on the button. See the "iconSet" [p. 159] property for details.

#### void QToolButton::setIconSet ( const QIconSet & set, bool on )

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

**This function is obsolete.** It is provided to keep old source working. We strongly advise against using it in new code.

Since Qt 3.0, QIconSet contains both the On and Off icons.

For ease of porting, this function ignores the *on* parameter and sets the iconSet property. If you relied on the *on* parameter, you probably want to update your code to use the QIconSet On/Off mechanism.

157

See also iconSet [p. 159] and QIconSet::State [Graphics with Qt].

#### void QToolButton::setOffIconSet ( const QIconSet & )

Sets the icon set that is used when the button is in an "off" state. See the "offIconSet" [p. 159] property for details.

#### void QToolButton::setOn ( bool enable ) [virtual slot]

Sets whether this tool button is on to enable. See the "on" [p. 159] property for details.

#### void QToolButton::setOnIconSet ( const QIconSet &)

Sets the icon set that is used when the button is in an "on" state. See the "onIconSet" [p. 159] property for details.

# void QToolButton::setPopup ( QPopupMenu \* popup )

Associates the popup menu popup with this tool button.

The popup will be shown each time the tool button has been pressed down for a certain amount of time. A typical application example is the "back" button in some web browsers's tool bars. If the user clicks it, the browser simply browses back to the previous page. If the user holds the button down for a while, the tool button shows a menu containing the current history list.

Ownership of the popup menu is not transferred to the tool button.

See also popup() [p. 156].

#### void QToolButton::setPopupDelay (int delay)

Sets the time delay between pressing the button and the appearance of the associated popup menu in milliseconds to *delay*. See the "popupDelay" [p. 160] property for details.

#### void QToolButton::setTextLabel ( const QString & ) [slot]

Sets the label of this button. See the "textLabel" [p. 160] property for details.

#### void QToolButton::setTextLabel (const QString & newLabel, bool tipToo) [virtual slot]

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Sets the label of this button to newLabel and automatically sets it as tool tip too if tipToo is TRUE.

# void QToolButton::setToggleButton(bool enable) [virtual slot]

Sets whether this tool button is a toggle button to enable. See the "toggleButton" [p. 160] property for details.

### void QToolButton::setUsesBigPixmap (bool enable) [virtual slot]

Sets whether this toolbutton uses big pixmaps to enable. See the "usesBigPixmap" [p. 160] property for details.

# void QToolButton::setUsesTextLabel(bool enable) [virtual slot]

Sets whether the toolbutton displays a text label below the button pixmap to *enable*. See the "usesTextLabel" [p. 160] property for details.

# QString QToolButton::textLabel() const

Returns the label of this button. See the "textLabel" [p. 160] property for details.

## void QToolButton::toggle () [slot]

Toggles the state of this tool button.

This function has no effect on non-toggling buttons.

See also toggleButton [p. 160] and toggled() [Widgets with Qt].

#### bool QToolButton::uses3D() const [protected]

Returns TRUE if this button should be drawn using raised edges; otherwise returns FALSE.

See also drawButton() [Widgets with Qt].

#### bool QToolButton::usesBigPixmap() const

Returns TRUE if this toolbutton uses big pixmaps; otherwise returns FALSE. See the "usesBigPixmap" [p. 160] property for details.

#### bool QToolButton::usesTextLabel() const

Returns TRUE if the toolbutton displays a text label below the button pixmap; otherwise returns FALSE. See the "usesTextLabel" [p. 160] property for details.

# **Property Documentation**

#### bool autoRaise

This property holds whether auto-raising is enabled.

The default is disabled (i.e. FALSE).

Set this property's value with setAutoRaise() and get this property's value with autoRaise().

#### **QIconSet iconSet**

This property holds the icon set providing the icon shown on the button.

Setting this property sets QToolButton::pixmap to a null pixmap. There is no default iconset.

See also pixmap [Widgets with Qt], toggleButton [p. 160] and on [p. 159].

Set this property's value with setIconSet() and get this property's value with iconSet().

#### QIconSet offIconSet

This property holds the icon set that is used when the button is in an "off" state.

This property is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

Since Qt 3.0, QIconSet contains both the On and Off icons. There is now an QToolButton::iconSet property that replaces both QToolButton::onIconSet and QToolButton::offIconSet.

For ease of porting, this property is a synonym for QToolButton::iconSet. You probably want to go over your application code and use the QIconSet On/Off mechanism.

See also iconSet [p. 159] and QIconSet::State [Graphics with Qt].

Set this property's value with setOffIconSet() and get this property's value with offIconSet().

#### bool on

This property holds whether this tool button is on.

This property has no effect on non-toggling buttons. The default is FALSE (i.e. off).

See also toggleButton [p. 160] and toggle() [p. 158].

Set this property's value with setOn().

#### QIconSet onIconSet

This property holds the icon set that is used when the button is in an "on" state.

This property is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

Since Qt 3.0, QIconSet contains both the On and Off icons. There is now an QToolButton::iconSet property that replaces both QToolButton::onIconSet and QToolButton::offIconSet.

For ease of porting, this property is a synonym for QToolButton::iconSet. You probably want to go over your application code and use the QIconSet On/Off mechanism.

See also iconSet [p. 159] and QIconSet::State [Graphics with Qt].

Set this property's value with setOnIconSet() and get this property's value with onIconSet().

### int popupDelay

This property holds the time delay between pressing the button and the appearance of the associated popup menu in milliseconds.

Usually this is around half a second. A value of 0 will add a special section to the toolbutton that can be used to open the popupmenu.

See also setPopup() [p. 157].

Set this property's value with setPopupDelay() and get this property's value with popupDelay().

### **QString** textLabel

This property holds the label of this button.

Setting this property automatically sets the text as tool tip too. There is no default text.

Set this property's value with setTextLabel() and get this property's value with textLabel().

# bool toggleButton

This property holds whether this tool button is a toggle button.

Toggle buttons have an on/off state similar to check boxes. A tool button is not a toggle button by default.

See also on [p. 159] and toggle() [p. 158].

Set this property's value with setToggleButton().

#### bool usesBigPixmap

This property holds whether this toolbutton uses big pixmaps.

QToolButton automatically connects this property to the relevant signal in the QMainWindow in which it resides. We strongly recommend that you use QMainWindow::setUsesBigPixmaps() instead.

This property's default is TRUE.

**Warning:** If you set some buttons (in a QMainWindow) to have big pixmaps and others to have small pixmaps, QMainWindow may not get the geometry right.

Set this property's value with setUsesBigPixmap() and get this property's value with usesBigPixmap().

#### bool usesTextLabel

This property holds whether the toolbutton displays a text label below the button pixmap.

The default is FALSE.

QToolButton automatically connects this slot to the relevant signal in the QMainWindow in which is resides. Set this property's value with setUsesTextLabel() and get this property's value with usesTextLabel().

The QToolTip class provides tool tips (balloon help) for any widget or rectangular part of a widget.

#include <qtooltip.h>

Inherits Qt [Additional Functionality with Qt].

# **Public Members**

- **QToolTip** ( QWidget \* widget, QToolTipGroup \* group = 0 )
- QWidget \* parentWidget () const
- QToolTipGroup \* group () const

# **Static Public Members**

- void add (QWidget \* widget, const QString & text)
- void add (QWidget \* widget, const QString & text, QToolTipGroup \* group, const QString & longText)
- void remove (QWidget \* widget)
- void add ( OWidget \* widget, const QRect & rect, const QString & text )
- void **add** ( QWidget \* widget, const QRect & rect, const QString & text, QToolTipGroup \* group, const QString & groupText )
- void **remove** (QWidget \* widget, const QRect & rect)
- QString textFor (QWidget \* widget, const QPoint & pos = QPoint ())
- void hide ()
- QFont font ()
- void **setFont** (const QFont & font)
- QPalette palette ()
- void **setPalette** (const QPalette & palette)
- void setEnabled (bool enable) (obsolete)
- bool enabled () (obsolete)
- void **setGloballyEnabled** (bool enable)
- bool isGloballyEnabled ()

#### **Protected Members**

- virtual void **maybeTip** (const QPoint & p)
- void **tip** (const QRect & rect, const QString & text)
- void tip (const QRect & rect, const QString & text, const QString & groupText)
- void clear()

# **Detailed Description**

The QToolTip class provides tool tips (balloon help) for any widget or rectangular part of a widget.

The tip is a short, single line of text reminding the user of the widget's or rectangle's function. It is drawn immediately below the region in a distinctive black-on-yellow combination.

QToolTipGroup provides a way for tool tips to display another text elsewhere (most often in a status bar).

At any point in time, QToolTip is either dormant or active. In dormant mode the tips are not shown and in active mode they are. The mode is global, not particular to any one widget.

QToolTip switches from dormant to active mode when the user hovers the mouse on a tip-equipped region for a second or so and remains active until the user either clicks a mouse button, presses a key, lets the mouse hover for five seconds or moves the mouse outside *all* tip-equipped regions for at least a second.

The QToolTip class can be used in three different ways:

- 1. Adding a tip to an entire widget.
- 2. Adding a tip to a fixed rectangle within a widget.
- 3. Adding a tip to a dynamic rectangle within a widget.

To add a tip to a widget, call the static function QToolTip::add() with the widget and tip as arguments:

```
QToolTip::add( quitButton, "Leave the application" );
```

This is the simplest and most common use of QToolTip. The tip will be deleted automatically when *quitButton* is deleted, but you can remove it yourself, too:

```
QToolTip::remove( quitButton );
```

You can also display another text (typically in a status bar), courtesy of QToolTipGroup. This example assumes that g is a QToolTipGroup \* and is already connected to the appropriate status bar:

To add a tip to a fixed rectangle within a widget, call the static function QToolTip::add() with the widget, rectangle and tip as arguments. (See the tooltip/tooltip.cpp example.) Again, you can supply a QToolTipGroup \* and another text if you want.

Both of these are one-liners and cover the vast majority of cases. The third and most general way to use QToolTip uses a pure virtual function to decide whether to pop up a tool tip. The tooltip/tooltip.cpp example demonstrates this, too. This mode can be used to implement tips for text that can move as the user scrolls, for example.

To use QToolTip like this, you need to subclass QToolTip and reimplement maybeTip(). QToolTip calls maybeTip() when a tip should pop up, and maybeTip decides whether to show a tip.

Tool tips can be globally disabled using QToolTip::setGloballyEnabled() or disabled in groups with QToolTip-Group::setEnabled().

You can retreive the text of a tooltip for a given position within a widget using textFor().

The global tooltip font and palette can be set with the static setFont() and setPalette() functions respectively.

See also QStatusBar [Widgets with Qt], QWhatsThis [Widgets with Qt], QToolTipGroup [p. 168], GUI Design Handbook: Tool Tip and Help System.

#### **Member Function Documentation**

# QToolTip::QToolTip (QWidget \* widget, QToolTipGroup \* group = 0)

Constructs a tool tip object. This is necessary only if you need tool tips on regions that can move within the widget (most often because the widget's contents can scroll).

widget is the widget you want to add dynamic tool tips to and group (optional) is the tool tip group they should belong to.

**Warning:** QToolTip is not a subclass of QObject, so the instance of QToolTip is not deleted when *widget* is deleted. See also maybeTip() [p. 166].

### void QToolTip::add (QWidget \* widget, const QString & text) [static]

Adds a tool tip to widget. text is the text to be shown in the tool tip.

This is the most common entry point to the QToolTip class; it is suitable for adding tool tips to buttons, check boxes, combo boxes and so on.

Examples: qdir/qdir.cpp, scribble/scribble.cpp and tooltip/tooltip.cpp.

# 

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Adds a tool tip to widget and to tool tip group group.

text is the text shown in the tool tip and longText is the text emitted from group.

Normally, longText is shown in a status bar or similar.

#### void QToolTip::add ( QWidget \* widget, const QRect & rect, const QString & text ) [static]

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Adds a tool tip to a fixed rectangle, rect, within widget. text is the text shown in the tool tip.

# 

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Adds a tool tip to an entire widget and to tool tip group group. The tooltip will disappear when the mouse leaves the rect.

text is the text shown in the tool tip and groupText is the text emitted from group.

Normally, *groupText* is shown in a status bar or similar.

# void QToolTip::clear() [protected]

Immediately removes all tool tips for this tooltip's parent widget.

# bool QToolTip::enabled () [static]

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

## **QFont QToolTip::font()** [static]

Returns the font common to all tool tips.

See also setFont() [p. 167].

#### QToolTipGroup \* QToolTip::group () const

Returns the tool tip group this QToolTip is a member of or 0 if it isn't a member of any group.

The tool tip group is the object responsible for maintaining contact between tool tips and a status bar or something else which can show the longer help text.

See also parentWidget() [p. 166] and QToolTipGroup [p. 168].

### void QToolTip::hide() [static]

Hides any tip that is currently being shown.

Normally, there is no need to call this function; QToolTip takes care of showing and hiding the tips as the user moves the mouse.

#### bool QToolTip::isGloballyEnabled () [static]

Returns whether tool tips are enabled globally.

See also setGloballyEnabled() [p. 167].

# void QToolTip::maybeTip (const QPoint & p) [virtual protected]

This pure virtual function is half of the most versatile interface QToolTip offers.

It is called when there is a possibility that a tool tip should be shown and must decide whether there is a tool tip for the point *p* in the widget that this QToolTip object relates to. If so, maybeTip() must call tip() with the rectangle the tip applies to, the tip's text and optionally the QToolTipGroup details.

p is given in that widget's local coordinates. Most maybeTip() implementations will be of the form:

```
if ( ) {
    tip( , );
}
```

The first argument to tip() (a rectangle) must encompass p, i.e. the tip must apply to the current mouse position; otherwise QToolTip's operation is undefined.

Note that the tip will disappear once the mouse moves outside the rectangle you give to tip(), and will not reappear if the mouse moves back in - maybeTip() is called again instead.

See also tip() [p. 167].

Example: tooltip/tooltip.cpp.

## QPalette QToolTip::palette () [static]

Returns the palette common to all tool tips.

See also setPalette() [p. 167].

## QWidget \* QToolTip::parentWidget () const

Returns the widget this QToolTip applies to.

The tool tip is destroyed automatically when the parent widget is destroyed.

See also group() [p. 165].

# void QToolTip::remove (QWidget \* widget) [static]

Removes the tool tip from widget.

If there is more than one tool tip on *widget*, only the one covering the entire widget is removed.

# void QToolTip::remove (QWidget \* widget, const QRect & rect) [static]

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Removes the tool tip for rect from widget.

If there is more than one tool tip on widget, only the one covering rectangle rect is removed.

# void QToolTip::setEnabled (bool enable) [static]

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

#### void QToolTip::setFont ( const QFont & font ) [static]

Sets the font for all tool tips to font.

See also font() [p. 165].

## void QToolTip::setGloballyEnabled (bool enable) [static]

If *enable* is TRUE sets all tool tips to be enabled (shown when needed); if *enable* is FALSE sets all tool tips to be disabled (never shown).

By default, tool tips are enabled. Note that this function affects all tool tips in the entire application.

See also QToolTipGroup::enabled [p. 170].

### void QToolTip::setPalette ( const QPalette & palette ) [static]

Sets the palette for all tool tips to palette.

See also palette() [p. 166].

#### QString QToolTip::textFor (QWidget \* widget, const QPoint & pos = QPoint ()) [static]

Returns the text for widget at position pos, or a null string if there is no tool tip for the widget.

#### void QToolTip::tip ( const QRect & rect, const QString & text ) [protected]

Immediately pops up a tip saying *text* and removes the tip once the cursor moves out of rectangle *rect* (which is given in the coordinate system of the widget this QToolTip relates to).

The tip will not reappear if the cursor moves back; your maybeTip() has to reinstate it each time.

# 

This is an overloaded member function, provided for convenience. It behaves essentially like the above function.

Immediately pops up a tip saying *text* and removes that tip once the cursor moves out of rectangle *rect. groupText* is the text emitted from the group.

The tip will not reappear if the cursor moves back; your maybeTip() has to reinstate it each time.

The QToolTipGroup class collects tool tips into related groups.

#include <qtooltip.h>

Inherits QObject [Additional Functionality with Qt].

# **Public Members**

- QToolTipGroup (QObject \* parent, const char \* name = 0)
- **■** ~QToolTipGroup()
- bool delay () const
- bool enabled () const

# **Public Slots**

- void **setDelay** (bool)
- void **setEnabled** (bool)

# Signals

- void **showTip** (const QString & longText)
- void removeTip()

# **Properties**

- bool delay whether the display of the group text is delayed
- bool **enabled** whether tool tips in the group are enabled

# **Detailed Description**

The QToolTipGroup class collects tool tips into related groups.

Tool tips can display two texts: one in the tip and (optionally) one that is typically in a status bar. QToolTipGroup provides a way to link tool tips to this status bar.

QToolTipGroup has practically no API; it is used only as an argument to QToolTip's member functions, for example like this:

This example makes the object myLabel (which you have to supply) display (one assumes, though you can make myLabel do anything, of course) the strings "Give the giraffe a meal" and "Give the gorilla a meal" while the relevant tool tips are being displayed.

Deleting a tool tip group removes the tool tips in it.

See also Help System.

#### **Member Function Documentation**

# QToolTipGroup::QToolTipGroup (QObject \* parent, const char \* name = 0)

Constructs a tool tip group with parent parent and name name.

#### QToolTipGroup::~QToolTipGroup()

Destroys this tool tip group and all tool tips in it.

#### bool QToolTipGroup::delay() const

Returns TRUE if the display of the group text is delayed; otherwise returns FALSE. See the "delay" [p. 170] property for details.

# bool QToolTipGroup::enabled () const

Returns TRUE if tool tips in the group are enabled; otherwise returns FALSE. See the "enabled" [p. 170] property for details.

#### void QToolTipGroup::removeTip() [signal]

This signal is emitted when a tool tip in this group is hidden. See the QToolTipGroup documentation for an example of use.

See also showTip() [p. 170].

# void QToolTipGroup::setDelay(bool) [slot]

Sets whether the display of the group text is delayed. See the "delay" [p. 170] property for details.

### void QToolTipGroup::setEnabled ( bool ) [slot]

Sets whether tool tips in the group are enabled. See the "enabled" [p. 170] property for details.

# void QToolTipGroup::showTip (const QString & longText) [signal]

This signal is emitted when one of the tool tips in the group is displayed. *longText* is the extra text for the displayed tool tip.

See also removeTip() [p. 169].

# **Property Documentation**

# bool delay

This property holds whether the display of the group text is delayed.

This property's default is TRUE.

Set this property's value with setDelay() and get this property's value with delay().

#### bool enabled

This property holds whether tool tips in the group are enabled.

This property's default is TRUE.

Set this property's value with setEnabled() and get this property's value with enabled().

The QWizard class provides a framework for wizard dialogs.

#include <qwizard.h>
Inherits QDialog [p. 12].

#### **Public Members**

- QWizard (QWidget \* parent = 0, const char \* name = 0, bool modal = FALSE, WFlags f = 0)
- ~QWizard ()
- virtual void addPage (QWidget \* page, const QString & title)
- virtual void **insertPage** (QWidget \* page, const QString & title, int index)
- virtual void **removePage** (QWidget \* page)
- QString title (QWidget \* page) const
- void setTitle (QWidget \* page, const QString & title)
- OFont titleFont () const
- void **setTitleFont** (const QFont &)
- virtual void **showPage** (QWidget \* page)
- QWidget \* currentPage() const
- QWidget \* page (int index) const
- int pageCount () const
- int indexOf (QWidget \* page) const
- virtual bool appropriate (QWidget \* page) const
- virtual void **setAppropriate** ( OWidget \* page, bool appropriate )
- QPushButton \* backButton () const
- QPushButton \* **nextButton**() const
- QPushButton \* finishButton () const
- QPushButton \* cancelButton() const
- QPushButton \* helpButton() const

# **Public Slots**

- virtual void **setBackEnabled** ( OWidget \* page, bool enable )
- virtual void **setNextEnabled** (QWidget \* page, bool enable)
- virtual void **setFinishEnabled** ( QWidget \* page, bool enable )
- virtual void **setHelpEnabled** (QWidget \* page, bool enable)
- virtual void setFinish (QWidget \*, bool) (obsolete)

# Signals

- void **helpClicked** ()
- void **selected** (const QString &)

# **Properties**

■ QFont **titleFont** — the font used for page titles

#### **Protected Members**

- virtual void layOutButtonRow (QHBoxLayout \* layout)
- virtual void layOutTitleRow (QHBoxLayout \* layout, const QString & title)

#### **Protected Slots**

- virtual void back()
- virtual void **next**()
- virtual void help()

# **Detailed Description**

The QWizard class provides a framework for wizard dialogs.

A wizard is a special type of input dialog that consists of a sequence of dialog pages. A wizard's purpose is to assist a user by automating a task by walking the user through the process step by step. Wizards are useful for complex or infrequently occurring tasks that people may find difficult to learn or do.

QWizard provides page titles and displays Next, Back, Finish, Cancel, and Help push buttons, as appropriate to the current position in the page sequence.

Create and populate dialog pages that inherit from QWidget and add them to the wizard using addPage(). Use insert-Page() to add a dialog page at a certain position in the page sequence. Use removePage() to remove a page from the page sequence.

Use currentPage() to retrieve a pointer to the currently displayed page. page() returns a pointer to the page at a certain position in the page sequence.

Use pageCount() to retrieve the total number of pages in the page sequence. indexOf() will return the index of a page in the page sequence.

QWizard provides functionality to mark pages as appropriate (or not) in the current context with setAppropriate(). The idea is that a page may be irrelevant and should be skipped depending on the data entered by the user on a preceding page.

It is generally considered good design to provide a greater number of simple pages with fewer choices rather than a smaller number of complex pages.

Example code is available here: wizard/wizard.cpp wizard/wizard.h

See also Abstract Widget Classes, Dialog Classes and Organizers.

#### **Member Function Documentation**

# QWizard::QWizard (QWidget \* parent = 0, const char \* name = 0, bool modal = FALSE, WFlags f = 0)

Constructs an empty wizard dialog. The parent, name, modal and f arguments are passed to the QDialog constructor.

# QWizard::~QWizard()

Destroys the object and frees any allocated resources, including all pages and controllers.

# void QWizard::addPage (QWidget \* page, const QString & title) [virtual]

Adds page to the end of the page sequence, with the title, title.

# bool QWizard::appropriate ( QWidget \* page ) const [virtual]

Called when the Next button is clicked; this virtual function returns TRUE if *page* is relevant for display in the current context; otherwise it is ignored by QWizard and returns FALSE. The default implementation returns the value set using setAppropriate(). The ultimate default is TRUE.

Warning: The last page of the wizard will be displayed if no page is relevant in the current context.

#### void QWizard::back() [virtual protected slot]

Called when the user clicks the Back button; this function shows the preceding relevant page in the sequence. See also appropriate() [p. 173].

### QPushButton \* QWizard::backButton() const

Returns a pointer to the Back button of the dialog.

By default, this button is connected to the back() slot, which is virtual so you can reimplement it in a QWizard subclass.

#### QPushButton \* QWizard::cancelButton () const

Returns a pointer to the Cancel button of the dialog.

By default, this button is connected to the QDialog::reject() slot, which is virtual so you can reimplement it in a QWizard subclass.

# QWidget \* QWizard::currentPage () const

Returns a pointer to the current page in the sequence. Although the wizard does its best to make sure that this value is never 0, it can be if you try hard enough.

## QPushButton \* QWizard::finishButton () const

Returns a pointer to the Finish button of the dialog.

By default, this button is connected to the QDialog::accept() slot, which is virtual so you can reimplement it in a QWizard subclass.

### void QWizard::help () [virtual protected slot]

Called when the user clicks the Help button, this function emits the helpClicked() signal.

# QPushButton \* QWizard::helpButton() const

Returns a pointer to the Help button of the dialog.

By default, this button is connected to the help() slot, which is virtual so you can reimplement it in a QWizard subclass.

# void QWizard::helpClicked () [signal]

This signal is emitted when the user clicks on the Help button.

# int QWizard::indexOf (QWidget \* page) const

Returns the sequence index of page page. If the page is not part of the wizard -1 is returned.

# void QWizard::insertPage ( QWidget \* page, const QString & title, int index ) [virtual]

Inserts *page* at index *index* into the page sequence, with title *title*. If index is -1, the page will be appended to the end of the wizard's page sequence.

#### void QWizard::layOutButtonRow ( QHBoxLayout \* layout ) [virtual protected]

This virtual function is responsible for adding the bottom divider and buttons below it.

layout is the vertical layout of the entire wizard.

# void QWizard::layOutTitleRow (QHBoxLayout \* layout, const QString & title) [virtual protected]

This virtual function is responsible for laying out the title row and adding the vertical divider between the title and the wizard page. *layout* is the vertical layout for the wizard, and *title* is the title for this page. This function is called every

time title changes.

### void QWizard::next() [virtual protected slot]

Called when the user clicks the Next button, this function shows the next relevant page in the sequence.

See also appropriate() [p. 173].

# QPushButton \* QWizard::nextButton () const

Returns a pointer to the Next button of the dialog.

By default, this button is connected to the next() slot, which is virtual so you can reimplement it in a QWizard subclass.

# QWidget \* QWizard::page (int index) const

Returns a pointer to the page at position index in the sequence, or 0 if index is out of range. The first page has index 0.

### int QWizard::pageCount() const

Returns the number of pages in the wizard.

# void QWizard::removePage ( QWidget \* page ) [virtual]

Removes page from the page sequence but does not delete the page. If page is currently being displayed, QWizard will display the page before it in the wizard, or the first page if this was the first page.

## void QWizard::selected ( const QString & ) [signal]

This signal is emitted when the current page changes. The parameter contains the title of the page.

# void QWizard::setAppropriate (QWidget \* page, bool appropriate) [virtual]

If *appropriate* is TRUE then page *page* is considered relevant in the current context and should be displayed in the page sequence; otherwise *page* should not be displayed in the page sequence.

See also appropriate() [p. 173].

# void QWizard::setBackEnabled ( QWidget \* page, bool enable ) [virtual slot]

If enable is TRUE, page page has a Back button; otherwise page has no Back button. By default all pages have this button.

# void QWizard::setFinish ( QWidget \*, bool ) [virtual slot]

This function is obsolete. It is provided to keep old source working. We strongly advise against using it in new code.

Use setFinishEnabled instead

## void QWizard::setFinishEnabled (QWidget \* page, bool enable) [virtual slot]

If enable is TRUE, page page has a Finish button; otherwise page has no Finish button. By default no pages have this button.

# void QWizard::setHelpEnabled (QWidget \* page, bool enable) [virtual slot]

If enable is TRUE, page page has a Help button; otherwise page has no Help button. By default all pages have this button.

# void QWizard::setNextEnabled ( QWidget \* page, bool enable ) [virtual slot]

If enable is TRUE, page page has a Next button; otherwise page has no Next button. By default all pages have this button.

# void QWizard::setTitle ( QWidget \* page, const QString & title )

Sets the title for page page to title.

#### void QWizard::setTitleFont ( const QFont & )

Sets the font used for page titles. See the "titleFont" [p. 177] property for details.

# void QWizard::showPage ( QWidget \* page ) [virtual]

Makes page the current page and emits the selected() signal.

Example: wizard/wizard.cpp.

### QString QWizard::title (QWidget \* page) const

Returns the title of page page.

#### **QFont QWizard::titleFont() const**

Returns the font used for page titles. See the "titleFont" [p. 177] property for details.

# **Property Documentation**

# **QFont titleFont**

This property holds the font used for page titles.

The default is QApplication::font().

Set this property's value with setTitleFont() and get this property's value with titleFont().

# **QWorkspace Class Reference**

The QWorkspace widget provides a workspace window that can contain decorated windows, e.g. for MDI.

This class is part of the workspace module.

```
#include <qworkspace.h>
```

Inherits QWidget [Widgets with Qt].

# **Public Members**

- **QWorkspace** (QWidget \* parent = 0, const char \* name = 0)
- ~QWorkspace ()
- QWidget \* activeWindow () const
- QWidgetList windowList () const
- bool scrollBarsEnabled () const
- void **setScrollBarsEnabled** (bool enable)

# **Public Slots**

- void cascade()
- void tile()

# **Signals**

■ void windowActivated (QWidget \* w)

# **Properties**

■ bool **scrollBarsEnabled** — whether the workspace provides scrollbars

# **Detailed Description**

The QWorkspace widget provides a workspace window that can contain decorated windows, e.g. for MDI.

An MDI (multiple document interface) application has one main window with a menu bar. The central widget of this window is a workspace. The workspace itself contains zero, one or more document windows, each of which displays a document.

The workspace itself is an ordinary Qt widget. It has a standard constructor that takes a parent widget and an object name. The parent window is usually a QMainWindow, but it need not be.

Document windows (i.e. MDI windows) are also ordinary Qt widgets which have the workspace as parent widget. When you call show(), hide(), showMaximized(), setCaption(), etc. on a document window, it is shown, hidden, etc. with a frame, caption, icon and icon text, just as you'd expect. You can provide widget flags which will be used for the layout of the decoration or the behaviour of the widget itself.

To change the geometry of the MDI windows it is necessary to make the function calls to the parentWidget() of the widget, as this will move or resize the decorated window.

A document window becomes active when it gets the keyboard focus. You can activate it using setFocus(), and the user can activate it by moving focus in the normal ways. The workspace emits a signal windowActivated() when it detects the activation change, and the function activeWindow() always returns a pointer to the active document window.

The convenience function windowList() returns a list of all document windows. This is useful to create a popup menu "Windows" on the fly, for example.

QWorkspace provides two built-in layout strategies for child windows: cascade() and tile(). Both are slots so you can easily connect menu entries to them.

If you want your users to be able to work with document windows larger than the actual workspace, set the scroll-BarsEnabled property to TRUE.

If the top-level window contains a menu bar and a document window is maximised, QWorkspace moves the document window's minimize, restore and close buttons from the document window's frame to the workspace window's menu bar. It then inserts a window operations menu at the extreme left of the menu bar.

See also Main Window and Related Classes and Organizers.

#### **Member Function Documentation**

QWorkspace::QWorkspace (QWidget \* parent = 0, const char \* name = 0)

Constructs a workspace with a parent and a name.

QWorkspace::~QWorkspace()

Destroys the workspace and frees any allocated resources.

#### QWidget \* QWorkspace::activeWindow () const

Returns the active window, or 0 if no window is active.

Example: mdi/application.cpp.

### void QWorkspace::cascade() [slot]

Arranges all child windows in a cascade pattern.

See also tile() [p. 180].

Example: mdi/application.cpp.

# bool QWorkspace::scrollBarsEnabled () const

Returns TRUE if the workspace provides scrollbars; otherwise returns FALSE. See the "scrollBarsEnabled" [p. 180] property for details.

### void QWorkspace::setScrollBarsEnabled ( bool enable )

Sets whether the workspace provides scrollbars to enable. See the "scrollBarsEnabled" [p. 180] property for details.

### void QWorkspace::tile() [slot]

Arranges all child windows in a tile pattern.

See also cascade() [p. 180].

Example: mdi/application.cpp.

# void QWorkspace::windowActivated (QWidget \* w) [signal]

This signal is emitted when the window widget w becomes active. Note that w can be null, and that more than one signal may be fired for one activation event.

See also activeWindow() [p. 179] and windowList() [p. 180].

# QWidgetList QWorkspace::windowList () const

Returns a list of all windows.

Example: mdi/application.cpp.

# **Property Documentation**

#### bool scrollBarsEnabled

This property holds whether the workspace provides scrollbars.

If this property is set to TRUE, it is possible to resize child windows over the right or the bottom edge out of the visible area of the workspace. The workspace shows scrollbars to make it possible for the user to access those windows. If this property is set to FALSE (the default), resizing windows out of the visible area of the workspace is not permitted.

Set this property's value with setScrollBarsEnabled() and get this property's value with scrollBarsEnabled().

# **Index**

1	0	OM D 100
about()	appropriate()	QMenuData, 130
QMessageBox, 107	QMainWindow, 65	childEvent()
aboutQt()	QWizard, 173	QMainWindow, 66
QMessageBox, 108	area()	clear()
aboutToHide()	QDockWindow, 26	QMenuData, 79, 90, 119
QPopupMenu, 118	autoClose	QToolBar, 151
aboutToShow()	QProgressDialog, 137	QToolTip, 165
QPopupMenu, 118	autoClose()	CloseMode
QTabDialog, 142	QProgressDialog, 135	QDockWindow, 26
accel()	autoRaise	closeMode
QMenuData, 89, 118	QToolButton, 159	QDockWindow, 31
accept()	autoRaise()	closeMode()
QDialog, 15	QToolButton, 155	QDockWindow, 27
activated()	autoReset	columns()
QMenuBar, 79	QProgressDialog, 137	QPopupMenu, 120
QPopupMenu, 119	autoReset()	connectItem()
activateItemAt()	QProgressDialog, 135	QMenuData, 90, 120
QMenuData, 89		contentsPreview
activeWindow()	back()	QFileDialog, 50
QWorkspace, 179	OWizard, 173	count
add()	backButton()	QDockArea, 22
QToolTip, 164, 165	QWizard, 173	count()
addDockWindow()	bottomDock()	QDockArea, 20
QMainWindow, 65	QMainWindow, 66	QMenuData, 91
addFilter()	boxLayout()	createDockWindowMenu()
QFileDialog, 40	QDockWindow, 26	QMainWindow, 66
addLeftWidget()	buttonText()	critical()
QFileDialog, 40	QMessageBox, 108	QMessageBox, 108, 109
addPage()	Q1120000Q02011, 100	currentChanged()
QWizard, 173	cancel()	QTabDialog, 143
addRightWidget()	QProgressDialog, 135	currentPage()
QFileDialog, 40	cancelButton()	QTabDialog, 143
addSeparator()	QWizard, 173	QWizard, 174
QToolBar, 151	cancelButtonPressed()	customColor()
addTab()	QTabDialog, 143	QColorDialog, 4
QTabDialog, 142		customCount()
addToolBar()	cancelled()	QColorDialog, 4
QMainWindow, 65	QProgressDialog, 135	customize()
addToolButton()	cascade()	QMainWindow, 66
QFileDialog, 40	QWorkspace, 180	Qiram vindovi, oo
addWidgets()	centralWidget()	1 f 1 D D 16
QFileDialog, 40	QMainWindow, 66	defaultButtonPressed()
adjustSize()	changeItem()	QTabDialog, 143
QMessageBox, 108	QMenuData, 89, 90, 119	defaultUp
applyButtonPressed()	changeTab()	QMenuBar, 86
QTabDialog, 142	QTabDialog, 143	delay
Atanniaiog, 147	checkable	QToolTipGroup, 170

11.0	0.115	1.1.7. 0
delay()	finishButton()	helpButton()
QToolTipGroup, 169	QWizard, 174	QWizard, 174
DialogCode	fixedExtent() QDockWindow, 27	helpButtonPressed()
QDialog, 14 dir()	font()	QTabDialog, 144 helpClicked()
OFileDialog, 41	QToolTip, 165	QWizard, 174
dirEntered()	forceShow()	hide()
		QMenuBar, 79
QFileDialog, 41 dirPath	QProgressDialog, 135 fullSpan()	QToolTip, 165
QFileDialog, 50	QCustomMenuItem, 7	highlighted()
dirPath()	QGustoniwenuitem, 7	QMenuBar, 79
QFileDialog, 41	getColor()	QPopupMenu, 121
disconnectItem()	QColorDialog, 4	horizontallyStretchable
QMenuData, 91, 120	getDouble()	QDockWindow, 31
dock()	QInputDialog, 55	QDock vindo vi, or
QDockWindow, 27	getExistingDirectory()	
dockWindowList()	QFileDialog, 42	Icon
QDockArea, 20	getInteger()	QMessageBox, 106
dockWindowPositionChanged()	QInputDialog, 55	icon
QMainWindow, 67	getItem()	QMessageBox, 113
DockWindows	QInputDialog, 56	icon()
QMainWindow, 64	getLocation()	QMessageBox, 109
dockWindows()	QMainWindow, 67	iconPixmap
QMainWindow, 67	getOpenFileName()	QMessageBox, 113
dockWindowsMovable	QFileDialog, 42	iconPixmap()
QMainWindow, 74	getOpenFileNames()	QMessageBox, 109
dockWindowsMovable()	QFileDialog, 43	iconProvider()
QMainWindow, 67	getRgba()	QFileDialog, 44
done()	QColorDialog, 4	iconSet
QDialog, 15	getSaveFileName()	QToolButton, 159
drawContents()	QFileDialog, 43	iconSet()
QMenuBar, 79	getText()	QMenuData, 91, 121
QPopupMenu, 120	QInputDialog, 56	QToolButton, 155
drawItem()	group()	idAt()
QPopupMenu, 120	QToolTip, 165	QMenuData, 91
	HandlePosition	QPopupMenu, 121, 122 indexOf()
empty	QDockArea, 19	QMenuData, 91
QDockArea, 22	handlePosition	QWizard, 174
enabled	QDockArea, 22	infoPreview
QToolTipGroup, 170	handlePosition()	QFileDialog, 50
enabled()	QDockArea, 20	information()
QToolTip, 165	hasApplyButton()	QMessageBox, 109, 110
QToolTipGroup, 169	QTabDialog, 143	insertItem()
exec()	hasCancelButton()	QMenuData, 80–84, 92–96,
QDialog, 15	QTabDialog, 144	122–126
QPopupMenu, 120, 121 extension()	hasDefaultButton()	insertPage()
QDialog, 16	QTabDialog, 144	QWizard, 174
QDialog, 10	hasDockWindow()	insertSeparator()
fileHighlighted()	QDockArea, 20	QMenuData, 84, 96, 126
QFileDialog, 41	QMainWindow, 68	insertTab()
fileSelected()	hasHelpButton()	QTabDialog, 144, 145
QFileDialog, 41	QTabDialog, 144	insertTearOffHandle()
filesSelected()	hasOkButton()	QPopupMenu, 127
QFileDialog, 41	QTabDialog, 144	isCheckable()
filterSelected()	heightForWidth()	QPopupMenu, 127
QFileDialog, 42	QMenuBar, 79	isCloseEnabled()
findItem()	help()	QDockWindow, 27
QMenuData, 91	QWizard, 174	isContentsPreviewEnabled()

QFileDialog, 44	layOutButtonRow()	QWizard, 175
isCustomizable()	QWizard, 174	numScreens()
QMainWindow, 68	layOutTitleRow()	QDesktopWidget, 10
isDefaultUp()	QWizard, 174	office m Cot
QMenuBar, 85	leftDock()	offIconSet
isDockEnabled()	QMainWindow, 69	QToolButton, 159
QMainWindow, 68	lineUp()	offIconSet()
isDockMenuEnabled()	QDockArea, 21	QToolButton, 156 offset
QMainWindow, 68	lineUpDockWindows()	
isDockWindowAccepted()	QMainWindow, 69	QDockWindow, 31 offset()
QDockArea, 20	lineUpToolBars()	QDockWindow, 28
isEmpty()	QMainWindow, 69	on
QDockArea, 21	mainWindow()	QToolButton, 159
isGloballyEnabled()	QToolBar, 151	onIconSet
QToolTip, 165	maybeTip()	QToolButton, 159
isHorizontallyStretchable()	QToolTip, 166	onIconSet()
QDockWindow, 27	menu identifier, 88	QToolButton, 156
isHorizontalStretchable()	menuAboutToShow()	opaqueMoving
QDockWindow, 27	QMainWindow, 69	QDockWindow, 32
isInfoPreviewEnabled()	menuBar()	QMainWindow, 74
QFileDialog, 44 isItemActive()	QMainWindow, 69	opaqueMoving()
**	menuContentsChanged()	QDockWindow, 28
QMenuData, 97 isItemChecked()	QMenuBar, 85	QMainWindow, 70
QMenuData, 97, 127	QMenuData, 97	openPopup()
isItemEnabled()	menuDelPopup()	QToolButton, 156
QMenuData, 85, 97, 127	QMenuData, 97	orientation
isMovingEnabled()	menuInsPopup()	QDockArea, 22
QDockWindow, 27	QMenuData, 97	orientation()
isResizeEnabled()	menuStateChanged()	QDialog, 16
QDockWindow, 27	QMenuBar, 85	QDockArea, 21
isSeparator()	QMenuData, 97	QDockWindow, 28
QCustomMenuItem, 7	message()	orientationChanged()
isSizeGripEnabled()	QMessageBox, 110	QDockWindow, 28
QDialog, 16	minimumDuration	-
isStretchable()	QProgressDialog, 138	page()
QDockWindow, 28	minimumDuration()	QWizard, 175
isTabEnabled()	QProgressDialog, 135	pageCount()
QTabDialog, 145	Mode	QWizard, 175
isVerticallyStretchable()	QFileDialog, 39	paint()
QDockWindow, 28	mode	QCustomMenuItem, 7
isVerticalStretchable()	QFileDialog, 50	palette()
QDockWindow, 28	mode()	QToolTip, 166
isVirtualDesktop()	QFileDialog, 44	parentWidget()
QDesktopWidget, 10	moveDockWindow()	QToolTip, 166
itemHeight()	QDockArea, 21	pixmap()
QPopupMenu, 127	QMainWindow, 69	QFileIconProvider, 52
itemParameter()	moveToolBar()	QMenuData, 98, 128
QMenuData, 97, 127	QMainWindow, 70	pixmapSizeChanged()
, ,	movingEnabled	QMainWindow, 70
1.1.1	QDockWindow, 31	Place
label	I!	QDockWindow, 26
QToolBar, 152	newLine	place
label()	QDockWindow, 31	QDockWindow, 32
QToolBar, 151	newLine()	place()
labelText OProgress Dialog 128	QDockWindow, 28	QDockWindow, 28
QProgressDialog, 138	next()	placeChanged()
labelText()  QProgressDialog, 135	QWizard, 175 nextButton()	QDockWindow, 29
Attaktessmank, 133	nextbutton()	popup()

QPopupMenu, 128 QToolbutton, 156         screenGemetry() QDesktopWidget, 11 screenNember()         QProgressDialog, 136 QMainWindow, 71 screenNember()         QProgressDialog, 136 QProgressDialog, 39         QProgressDialog, 45 selectable()         QProgressDialog, 45 Selectable()         SerCloseMode()         QPileDialog, 29 QPileDialog, 39         QWorkspace, 180 QVorkspace, 180 Selectable()         SerCloseMode()         QPileDialog, 29 QPileDialog, 45 Selectable()         QPileDialog, 45 Selectable()         SerContentsPreview()         QPileDialog, 45 Selectable()         QPileDialog, 45 Selectable()         Selectable()         QPileDialog, 45 Selectable()         Selectable()         QPileDialog, 45 Selectable()         QPileDialog, 45 Selectable()         Selectable()         QPileDialog, 45 Selectable()         Selectable()         QPileDialog, 45 Selectable()         Selectable()         QPileDialog, 50 QPileDialog, 51         QPileDialog, 51 Selectable()         QPileDialog, 51 Selectable()         QPileDialog, 51 Selectable()         QPileDialog, 51 Selectable()         Selectable()         QPileDialog, 51 Selectable()         QPileDialog, 45 Selectable()         Selectable()         QPileDialog, 45 Selectable()         Selectable()         QPileDialog, 45 Selectable()         Selectable()         QPileDialog, 45 Selectable			
popupbelay	QPopupMenu, 128		
Optolibutton, 160   OpesktopWidget, 11   serCheckable() OptopUpDelay()   scrollbarsEnabled   Optolibutton, 156   Opwrkspace, 180   SetCloseMode()   Optolibutton, 156   Opwrkspace, 180   SetCloseMode()   OptockWindow, 29   Optolibutton, 156   Opwrkspace, 180   SetContentsPreview()   OptockWindow, 29   Opwrkspace, 180   SetContentsPreview()   OptockWindow, 29   Opwrkspace, 180   Opwrksp	- · · · · · · · · · · · · · · · · · · ·		
popupbelay()         scrollBarten, 156         Optopherun, 129           PreviewMode         9(Workspace, 180         setCloseMode()           OFileblailog, 39         OWorkspace, 180         setCloseMode()           OFileblailog, 50         OFileblailog, 45         setContentSPreview()           OFileblailog, 50         OFileblailog, 45         setContentSPreviewEnabled()           OFileblailog, 44         Ofabbialog, 145         setCustomColor()           ObesktopWidget, 10         OWizard, 175         oColorbialog, 46           OprogressDialog, 138         selectedFile         setDefaultButton()           OprogressDialog, 135         SelectedFiles         setDefaultUp()           OprogressDialog, 135         SelectedFiles()         setDefaultUp()           OprogressDialog, 135         SelectedFiles()         setDefaultUp()           OprogressDialog, 136         OFileblalog, 45         setDefaultUp()           Query()         SelectedFiles()         setDir()           Query()         SelectedFiles()         setDir()           Query()         SelectedFiles()         setDir()           Quilago, 16         SelectedFiles()         setDir()           Quilago, 16         QFileblalog, 45         SetDir()           Quilago, 16         QFileblalog, 45 </td <td></td> <td></td> <td>ę ,</td>			ę ,
OTOolButton, 156			
PreviewMode         scrollBars&nabled()         Obockwindow, 29           OFilebialog, 39         OWorkspace, 180         setContentsPreview()           previewMode         selectAll()         QFilebialog, 45         setContentsPreview(habled()           previewMode()         selected()         OFilebialog, 45         setContentsPreview(habled()           previewMode()         Selected()         OFilebialog, 45         setContentsPreview(habled()           previewMode()         Selected()         OFilebialog, 45         setContentsPreview(habled()           prinaryScreen()         QWizard, 175         QColor/bialog, 46         setDefaultButton()           progress         QFilebialog, 51         QTabbialog, 146         setDefaultUp()           QProgressDialog, 138         selectedfile()         setDefaultUp()           QProgressDialog, 138         selectedfile(s)         setDefaultUp()           QProgressDialog, 135         QFilebialog, 51         QHenuBar, 85           QProgressDialog, 135         selectedfile(s)         setDefaultUp()           QWesageBox, 110         QFilebialog, 51         QFilebialog, 45         QFilebialog, 45           QDialog, 16         Setectedfile(r)         SetDock(malland)           QDialog, 16         Separator         SetDock(malland)           QMa			·
OFIleDialog, 39 PreviewMode PreviewMode (PileDialog, 50 PreviewMode (PileDialog, 50 PreviewMode())         selected() PreviewMode()         Selected() PreviewMode()         QFileDialog, 45 SetContentsPreviewChabled() PreviewMode()         QFileDialog, 45 SetContentsPreviewChabled() PreviewMode()         QFileDialog, 45 SetContentsPreviewChabled() PreviewMode()         QFileDialog, 45 SetContentsPreviewChabled() Preview Mode()         QFileDialog, 45 SetContentsPreviewChabled() Preview Mode()         QFileDialog, 45 SetContentsPreviewChabled()         QFileDialog, 45 SetContentsPreviewChabled()         QFileDialog, 45 SetContentsPreviewChabled()         QColorbialog, 5 SetContentsPreviewChabled()         SetDectantsPreviewChabled()         SetDectantsPreviewChabled(	,	<del>-</del>	
previewMode OFileDialog, 45 orientall() Selectall() Selected() Sel			
GFileDialog, 50 previewMode() QFileDialog, 44 PrimaryScreen() QFileDialog, 44 PrimaryScreen() QDesktopWidget, 10 progress QDesktopWidget, 10 progress QProgressDialog, 138 Progress() QProgressDialog, 135 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 146 QProgressDialog, 151 QDialog, 16 remove() QDockArea, 21 QDockArea, 21 QDockArea, 21 QMenuBat, 85 Separator QMenuBat, 85, 98, 128 removeImm() QMenuData, 98, 128 removePage() QRobulbata, 85, 98, 128 removePage() QRobulbata, 98, 128 reset() QProgressDialog, 135 reset() QProgressDialog, 135 reset() QProgressDialog, 135 reset() QProgressDialog, 135 reset() QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 restlatication QMainWindow, 70 rightLustification QMainWindow, 71 QProgressDialog, 136 QProgressD		- · · · · · · · · · · · · · · · · · · ·	**
previewMode() QFileDialog, 44 QFileDialog, 45 QFileDialog, 45 QFileDialog, 45 QFileDialog, 45 QFileDialog, 45 QFileDialog, 45 QFileDialog, 55 selectedFile QFileDialog, 51 QFileDialog, 51 QFileDialog, 15 QFileDialog, 16 QFi	-		- 9.
GPIEDIalog, 44 PrimaryScreen() QDesktopWidget, 10 progress QDesktopWidget, 10 progress QProgressDialog, 138 progress() QProgressDialog, 138 progress() QProgressDialog, 138 Porgress() QProgressDialog, 138 Porgress() QProgressDialog, 135 QProgressDialog, 145 QProgressDialog, 15 QProgressDialog, 135 QProgressDialog, 136 QP			
primaryScreen()         QWisard, 175         QColorDialog, 5           QDesktopWidget, 10         selectedFile         setDefaulRutton()           progress         QFileDialog, 51         QTabDialog, 146           oprogressDialog, 138         selectedFile()         setDefaulRup()           oprogressOprogress()         QFileDialog, 45         QMenuBar, 85           oprogressDialog, 135         selectedFiles         setDelay()           query()         selectedFiles()         setDectp()           QMessageBox, 110         OFileDialog, 45         QFileDialog, 46           oprogressDialog, 16         selectedFiler         setDockEnabled()           reject()         QFileDialog, 45         QMainWindow, 71           oprogressDialog, 16         selectedFiler         setDockMenuEnabled()           remove()         QFileDialog, 45         QMainWindow, 7           QDockArea, 21         Separator         setDockWindowsMovable()           Qbankwindow, 70         QMenuBar, 85         setEnabled()           removeItem()         Separator         setExtension()           QMenuData, 85, 98, 128         QMenuBar, 85         setExtension()           query()         SetAcceptDockWindow()         prilepialog, 46           removeToplata, 175         QbockArea, 21	*		- 9.
ObeskropWidget, 10         selectedFile         setDefaultButton ()           progress         QFileDialog, 51         QTabDialog, 146           QProgressDialog, 138         selectedFile()         setDefaultUp()           QProgressDialog, 135         SelectedFiles         SetDefaultUp()           QProgressDialog, 135         SelectedFiles         setDefaultUp()           Query()         SelectedFiles         setDefaultQp()           QMessageBox, 110         QFileDialog, 45         QFileDialog, 46           SelectedFilter         setDockEnabled()         QFileDialog, 45         QFileDialog, 46           reject()         QPileDialog, 45         QMainWindow, 71         SetDockMenuBad()         QMainWindow, 71           cemovelouseWindow()         QMenuBar, 78         QMainWindow, 72         Separator         SetDockMenuEnabled()           QDockArea, 21         Separator         SetEmbled()         QMiniWindow, 72         SetEmbled()           cemoveltemAt()         SetAccell()         QMenuBar, 85         SetEmbled()           QMenuBat, 85, 98, 128         QMenuBar, 85         SetEmbled()           cemoveltemAt()         SetAccell()         SetAccell()         SetEmbled()           QMinumbata, 98, 128         QMenuBar, 85         SetEilter()         SetEilter()      <		<del>-</del>	
progress QProgressDialog, 138         SelectedFile()         setDefaultUp()           progress()         QProgressDialog, 135         selectedFiles         setDefaultUp()           QProgressDialog, 135         selectedFiles         setDefaultUp()           query()         selectedFiles()         setDefaultUp()           query()         selectedFiles()         setDefaultUp()           QMessageBox, 110         QFileDialog, 45         QFileDialog, 46           gelectedFilter         setDockEnabled()           QDialog, 16         selectedFilter()         setDockEnabled()           remove()         QFileDialog, 45         QMainWindow, 71           QToolTip, 166         Separator         setDockWindowMowable()           QDockArea, 21         QMenuBar, 78         QMainWindow, 72           QDockArea, 21         QMenuBar, 86         QToolTip, 167           removeltem()         Separator         setExtension()           QMenuData, 85, 98, 128         QMenuBar, 85         setExtension()           QMenuData, 98, 128         QMenuBar, 85         setExtension()           QTabDialog, 145         QDockArea, 21         QFileDialog, 46           QWizard, 175         setAcceptDockWindow()         QFileDialog, 46           QProgressDialog, 145         QProgresDialog		- · · · · · · · · · · · · · · · · · · ·	
OProgressDialog, 138         selectedFile()         setDefaultUp()           progress()         QFileDialog, 45         QMenuBar, 85           QProgressDialog, 135         selectedFiles         setDelay()           query()         selectedFiles()         setDir()           QMessageBox, 110         QFileDialog, 45         QFileDialog, 46           reject()         GPileDialog, 51         setDockEnabled()           QDialog, 16         selectedFilter()         setDockMenuEnabled()           query()         QDoladog, 16         setDockMenuEnabled()           query()         QPrileDialog, 45         QMainWindow, 71           QDoladog, 16         selectedFilter()         setDockMenuEnabled()           QMockArea, 21         QMenuBar, 85         setDockWindowsMovable()           QDockArea, 21         separator         QMainWindow, 72           QMenuData, 85, 98, 128         QMenuBar, 86         QToolTip, 167           removettemAt()         setAccel()         QToolTip, 167           QMenuData, 98, 128         QMenuBar, 85         setExtension()           removeTemoveTip()         QMenuBar, 85         setExtension()           QTabDialog, 145         QDockArea, 21         setFilter()           QWizard, 175         setApplyButton()         qetFileD			
progress() QFileDialog, 45 QProgressDialog, 135 QProgressDialog, 135 QPrileDialog, 51 QPrileDialog, 51 QPrileDialog, 51 QPrileDialog, 51 QPrileDialog, 51 QPrileDialog, 45 QProgressDialog, 46 QProgressDialog, 46 QProgressDialog, 47 QPrileDialog, 46 QProgressDialog, 47 QPrileDialog, 46 QProgressDialog, 47 QProgressDialog, 48 QProgressDialog, 49 QProgressDialog, 49 QProgressDialog, 49		2 0,	
OProgressDialog, 135         selectedFiles ()         SetDiay()           query()         selectedFiles()         setDir()           QMessageBox, 110         OFileDialog, 45         QFileDialog, 46           reject()         QFileDialog, 51         QFileDialog, 46           reject()         QFileDialog, 51         QMainWindow, 71           QDialog, 16         selectedFilter ()         setDockMenuEnabled()           qToolTip, 166         Separator         setDockWindow, 71           removeDockWindow()         QMenuBar, 78         QMainWindow, 72           QDockArea, 21         Separator         setEnabled()           QMenuBar, 86         QToolTip, 167           removeItem()         Separator         setExtension()           QMenuData, 85, 98, 128         QMenuBar, 86         QToolTip, 167           removeItemAt()         setAccel()         QDialog, 16           QMenuData, 98, 128         QMenuData, 98, 128         setFilter()           removePage()         setAcceptDockWindow()         QFileDialog, 46           QWizard, 175         setAcciviterm()         SetFilter()           QToolTip,Group, 169         setAcciviterm()         QFileDialog, 47           removeToolBar()         QTabDialog, 145, 146         setFiliter()			=
query()         selectedFiles()         setDir()           QMessageBox, 110         QFileDialog, 45         QFileDialog, 46           selectedFilter         setDockEnabled()           reject()         QFileDialog, 51         QMainWindow, 71           QDialog, 16         selectedFilter()         setDockMenuEnabled()           remove()         QFileDialog, 45         OMainWindow, 70           QToolTip, 166         Separator         setDockWindowsMovable()           QMenuBar, 78         QMainWindow, 70         QMenuBar, 86         QToolTip, 167           removeltem()         separator         setEnabled()           QMenuBar, 85         setExtension()         setExtension()           QMenuData, 85, 98, 128         QMenuBar, 85         setExtension()           removeltemAt()         setAccel()         setAlog, 46           QMenuData, 98, 128         QMenuBar, 85         setExtension()           QMenuData, 98, 128         QMenuBar, 98, 128         setFilter()           QMizard, 175         setAcceptDockWindow()         QFileDialog, 46           QWizard, 175         setActiveftem()         QFileDialog, 46           QWizard, 175         setActiveftem()         QFileDialog, 47           QMainWindow, 70         QTabDialog, 145, 146         setFilt		<del>-</del>	
query()         selectedFiles()         setDir()           QMessageBox, 110         QFileDialog, 45         QFileDialog, 46           reject()         selectedFilter         setDockEnabled()           QDialog, 16         selectedFilter()         setDockMenuEnabled()           remove()         QFileDialog, 45         QMainWindow, 71           QToolTip, 166         Separator         setDockWindowMovaMovable()           QMockArea, 21         QMenuBar, 78         QMainWindow, 72           QMenuBat, 86         QToolTip, 167           removeItem()         separator()         getEanbled()           QMenuBata, 85, 98, 128         QMenuBar, 85         setExtension()           removeItemAt()         setAccel()         QDialog, 16           YemoveTemAt()         setAccel()         QDialog, 16           YemoveTemAt()         setAcceptDockWindow()         SetFilter()           QMenuData, 98, 128         QMenuData, 98, 128         setFilter()           YemoveTemoveTege()         setAcceptDockWindow()         QFileDialog, 46           QWizard, 175         setAcceptDockWindow()         QFileDialog, 46           YemoveTip()         QPopupMenu, 129         setFinish()           QMainWindow, 70         setAppropriate()         setFinish()	QProgressDialog, 135		•
QMessageBox, 110 QFileDialog, 45 selectedFilter reject() QPieDialog, 51 QPieDialog, 51 QPieDialog, 51 QMainWindow, 71 QDialog, 16 remove() QFileDialog, 45 QFileDialog, 45 QMainWindow, 71 QDialog, 16 Separator QMenuBat, 78 QMenuBar, 78 QMenuBar, 78 QMenuBar, 86 QToolTip, 166 Separator QMenuBar, 78 QMenuBar, 86 QMainWindow, 70 QMenuBar, 86 QMenuBar, 86 QToolTip, 167 removeItem() QMenuBata, 85, 98, 128 QMenuBar, 85 removeItemAt() QMenuBata, 85, 98, 128 QMenuBata, 98, 128 removePage() QTabDialog, 145 QWizard, 175 removeTip() QMianWindow, 70 QMounuBata, 98, 128 QMenuBata, 98, 128 removePage() QTabDialog, 145 QWizard, 175 removeTip() QToolTipGroup, 169 removeToolBar() QMainWindow, 70 rereadDir() QMainWindow, 70 QMainWindow, 70 QVizard, 176 reset() QProgressDialog, 45 QProgressDialog, 135 QProgressDialog, 136 QDockWindow, 32 QToolButton, 156 QDockWindow, 32 QToolButton, 156 QDockWindow, 32 resizeEnabled QDockWindow, 32 QToolButton, 156 QDockWindow, 32 QToolButton, 156 QDockWindow, 32 resizeEnabled QDockWindow, 32 QToolButton, 156 QDockWindow, 32 QToolButton, 156 QDockWindow, 32 QToolButton, 156 QDockWindow, 32 resizeEnabled QDockWindow, 32 QToolButton, 156 QDockWindow, 32 QToolTip, 167 result() QDialog, 16 QWizard, 175 QToolTip, 167 result() QMainWindow, 70 QWizard, 175 QToolTip, 167 restlepEnabled() QWizard, 175 QUockWindow, 29 restPiedEnabled() QWizard, 175 QToolTip, 167 restPiedEnabled() QWizard, 176 restPiedEna	auery()		
reject() QPialog, 16 QDialog, 16 QDialog, 16 QDialog, 16 QDialog, 16 SelectedFilter () QFileDialog, 45 QMainWindow, 71 QDialog, 16 QFileDialog, 45 QMainWindow, 71 QDialog, 16 Separator QFileDialog, 45 QMainWindow, 71 QMenuBar, 78 QMainWindow, 72 QDockArea, 21 QMainWindow, 70 QMenuBar, 86 QToolTip, 167 removeItem() QMenuBata, 85, 98, 128 QMenuBar, 85 QMenuBat, 85 QMenuBat, 85 QMenuBat, 85 QMenuData, 98, 128 QMenuBat, 98, 128 QMenuData, 98, 128 QMizard, 175 PemovePage() QTabDialog, 145 QWizard, 175 SetActiveItem() QFileDialog, 47 PereworToplGroup, 169 SetApplyButton() QMoinWindow, 70 SetApplyButton() QMainWindow, 70 QTabDialog, 145, 146 SetFinishEnabled() QWizard, 176 PereworToplGat() QMainWindow, 70 QWizard, 175 QWizard, 176 PereworToplGate, 135 QProgressDialog, 145 QWizard, 175 QDockWindow, 29 SetAutoClose() QProgressDialog, 135 QProgressDialog, 136 QDockWindow, 29 SetFixedExtentWidth() QProgressDialog, 45 QProgressDialog, 136 QDockWindow, 29 ProgressDialog, 45 QProgressDialog, 136 QDockWindow, 29 SetFixedExtentWidth() QPrigleDialog, 45 Power SetBackEnabled() SetBackInabled() SetBackInabled() SetBackInabled() SetGloballyEnabled() QMainWindow, 70 QProgressDialog, 136 QProgressDialog, 147 PrightLustification QMainWindow, 70 QMainWindow, 70 QMainWindow, 70 QMainWindow, 70 QMainWindow, 71 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 146 SetHorizontallyStretchable() SetHorizontallyStretchable() SetHorizontallyStretchable() SetHorizontallyStretchable()	- ·		•
reject()         QFileDialog, 51         QMainWindow, 71           QDialog, 16         selectedFilter()         setDockMenuEnabled()           remove()         QFileDialog, 45         QMainWindow, 71           QToolTip, 166         Separator         setDockWindowsMovable()           removeDockWindow()         QMenuBar, 78         QMainWindow, 72           QDockArea, 21         separator ()         QToolTip, 167           removeItem()         separator()         QToolTip, 167           QMenuData, 85, 98, 128         QMenuBar, 85         setExtension()           removeItemAt()         setAccel()         QDialog, 16           QMenuData, 98, 128         QMenuData, 98, 128         setFilter()           removePage()         setAcceptDockWindow()         QFileDialog, 46           QWizard, 175         setAcctiveItem()         setFilters()           QWizard, 175         setActiveItem()         setFilters()           quincertip()         QPopupmenu, 129         setFiliters()           quincertip()         QPopupmenu, 129         setFilter()           quincertip()         QPopupmenu, 129         setFiliters()           quincertip()         QRialpiButton()         setFilters()           QWizard, 175         setFilters()         setFilters()	Qiviessagebox, 110		
QDialog, 16 remove() QFileDialog, 45 QMainWindow, 71 QMenuBar, 78 QMenuBar, 78 QMainWindow, 70 QMenuBar, 86 QToolTrip, 167 removeltem() QMenuData, 85, 98, 128 QMenuBar, 85 removeltemA() QMenuData, 98, 128 QMenuBar, 85 QMenuBar, 85 QMenuBar, 85 QMenuData, 98, 128 RemovePage() QTabDialog, 145 QWizard, 175 QFileDialog, 45 QWizard, 175 QFileDialog, 45 QMoundary QFileDialog, 47 QFileDialog, 47 QFileDialog, 47 QFileDialog, 45 QMianWindow, 70 QFileDialog, 45 QMianWindow, 70 QFileDialog, 45 QFileD	reject()		**
remove() QFileDialog, 45 QMainWindow, 71 QToolTip, 166 Separator setDockWindows() QMenuBar, 78 QMainWindow, 70 QMenuBar, 86 QMainWindow, 72 separator setEnabled() QMainWindow, 70 QMenuBar, 86 QToolTip, 167 removeltem() QMenuData, 85, 98, 128 QMenuBar, 85 removeltemAt() QMenuData, 98, 128 QMenuBar, 85 removeltemAt() QMenuData, 98, 128 QMenuData, 98, 128 removePage() QMenuData, 98, 128 QMenuData, 98, 128 removePage() QTabDialog, 145 QWizard, 175 removeTip() QMortipGroup, 169 removeToolBar() QMainWindow, 70 removeToolBar() QMainWindow, 70 resortDir() QFileDialog, 45 QWizard, 175 reset() QFileDialog, 45 QWizard, 175 reset() QFileDialog, 45 QWizard, 175 reset() QFileDialog, 45 QWizard, 175 resizeEnabled QDockWindow, 20 resizeEnabled QDockWindow, 22 resizeEnabled QDockWindow, 32 QForgressDialog, 135 QProgressDialog, 136 resizeEnabled QDockWindow, 32 QFileDialog, 45 QProgressDialog, 136 resizeEnabled QDockWindow, 32 QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 136 resizeEnabled QDockWindow, 32 QForgressDialog, 136 resizeEnabled QDockWindow, 32 QForgressDialog, 136 QProgressDialog, 136 resizeEnabled QDockWindow, 32 QForgressDialog, 136 QFabDialog, 147 resizeDabled QMainWindow, 70			
QToolTip, 166         Separator (Prove Dock Window)         Separator (Prove Dock Window)         SetDock Windows Movable(Prove Dock Window)           QDockArea, 21         Separator (Prove Dock Window)         QMainWindow, 72         SetBabled(Prove Dock Window)         QMainWindow, 72           QMainWindow, 70         QMenuBar, 86         QToolTip, 167         QToolTip, 167           Pemovelterm(Prove Dock Prove Dock Pr	=		
RemoveDockWindow()	**	- 5.	
QDockArea, 21 separator setEnabled() QMainWindow, 70 QMenuBar, 86 QToolTip, 167 removeItem() QMenuData, 85, 98, 128 QMenuBar, 85 setExtension() QMenuData, 98, 128 QMenuBar, 85 setExtension() QMenuData, 98, 128 QMenuData, 98, 128 setFilter() removePage() QMenuData, 98, 128 QMenuData, 98, 128 setFilter() QMenuData, 98, 128 QMenuData, 98, 128 setFilter() QMainWindow, 175 setActiveItem() QWizard, 175 setActiveItem() QTabDialog, 145 QDockArea, 21 setFiliters() QWizard, 175 setActiveItem() QToolTipGroup, 169 setApplyButton() QMainWindow, 70 QTabDialog, 145, 146 setFinishEnabled() QMizard, 176 rereadDir() QMizard, 175 QWizard, 175 rereadDir() QProgressDialog, 45 QWizard, 175 reset() QProgressDialog, 135 QProgressDialog, 136 setFixedExtentHeight() QProgressDialog, 135 QProgressDialog, 136 QCustomMenuItem, 7 resortDir() QDockWindow, 32 QToolButton, 156 SetFixedExtentWidth() QDockWindow, 29 setAutoRaise() setFixedExtentWidth() QPrileDialog, 45 QProgressDialog, 136 QCustomMenuItem, 7 resortDir() setAutoReset() QDialog, 16 QWizard, 175 QCustomMenuItem, 7 resortDir() setBackEnabled() setGloballyEnabled() QDialog, 16 QWizard, 175 QToolTip, 167 result() setBar() QMainWindow, 70 QProgressDialog, 136 QToolTip, 167 result() QMainWindow, 70 QProgressDialog, 136 QToolTip, 167 rightDustification QMainWindow, 70 QProgressDialog, 136 QToolTip, 167 rightJustification() setButton() QMainWindow, 71 QProgressDialog, 136 SetHelpButton() QMainWindow, 71 QProgressDialog, 136 SetHorizontallyStretchable() QMainWindow, 71 QProgressDialog, 136 SetHorizontallyStretchable() QDockWindow, 29 setHorizontallStretchable() SetHorizontallStretchable()			· · · · · · · · · · · · · · · · · · ·
QMainWindow, 70         QMenuBar, 86         QToolTip, 167           removeItem()         separator()         QToolTipGroup, 170           QMenuData, 85, 98, 128         QMenuBar, 85         setExtension()           removeItemAt()         setAccel()         QDialog, 16           QMenuData, 98, 128         QMenuData, 98, 128         setFilter()           removePage()         setAcceptDockWindow()         QFileDialog, 46           QTabDialog, 145         QDockArea, 21         setFilters()           QWizard, 175         setActvietlerm()         QFileDialog, 47           removeTip()         QPopupMenu, 129         setFinish()           QToolTipGroup, 169         setApplyButton()         QWizard, 176           removeToolBar()         QTabDialog, 145, 146         setFinishEnabled()           QMainWindow, 70         setAppropriate()         QWizard, 176           rereadDir()         QMainWindow, 71         setFixedExtentHeight()           QFileDialog, 45         QWizard, 175         QDockWindow, 29           reset()         setAutoClose()         setFixedExtentWidth()           QProgressDialog, 135         QProgressDialog, 136         QDockWindow, 29           resizeEnabled         setAutoRese()         setFixedExtentWidth()           QDialog, 16 <t< td=""><td></td><td>-</td><td></td></t<>		-	
removeItem() QMenuData, 85, 98, 128 QMenuBar, 85 removeItemAt() QMenuData, 98, 128 removePage() SetAcceptDockWindow() QTabDialog, 145 QWizard, 175 SetActiveItem() QToolTipGroup, 169 removeTip() QToolTipGroup, 169 removeToolBar() QMainWindow, 70 QTabDialog, 145, 146 QFileDialog, 45 QWizard, 176 reeadDir() QFileDialog, 45 QWizard, 175 QProgressDialog, 135 QProgressDialog, 135 QProgressDialog, 135 QProgressDialog, 136 QDockWindow, 29 resizeEnabled QDockWindow, 32 QToolButton, 156 QProgressDialog, 45 QProgressDialog, 136 QProgressDialog, 147 QFileDialog, 45 QProgressDialog, 136 QDockWindow, 29 resortDir() SetAutoRaise() QProgressDialog, 147 QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 137 result() QDialog, 16 QWizard, 175 QProgressDialog, 136 QProgressDialog, 147 QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 147 QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 147 SetBar() QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 147 SetBar() QMainWindow, 70 QMainWindow, 70 QMainWindow, 70 QMainWindow, 74 QMessageBox, 111 SetCancelButton() QMainWindow, 71 QProgressDialog, 136 QPockWindow, 29 SetHorizontalStretchable() QMainWindow, 71 QProgressDialog, 136 SetHorizontalStretchable() SetCancelButton() QMainWindow, 71 QProgressDialog, 136 SetHorizontalStretchable()			
QMenuData, 85, 98, 128         QMenuBar, 85         setExtension()           removeltemAt()         setAccel()         QDialog, 16           QMenuData, 98, 128         QMenuData, 98, 128         setFilter()           removePage()         setAcceptDockWindow()         QFileDialog, 46           QTabDialog, 145         QDockArea, 21         setFilters()           QWizard, 175         setActiveItem()         QFileDialog, 47           removeTip()         QPopupMenu, 129         setFinish()           QToolTipGroup, 169         setApplyButton()         QWizard, 176           removeToolBar()         QTabDialog, 145, 146         setFinishEnabled()           QMainWindow, 70         setAppropriate()         QWizard, 176           rereadDir()         QMainWindow, 71         setFixedExtentHeight()           QFileDialog, 45         QWizard, 175         QDockWindow, 29           resice()         setAutoClose()         setFixedExtentWidth()           QProgressDialog, 135         QProgressDialog, 136         QDockWindow, 29           resizeEnabled         setAutoRaise()         setFiredExtentWidth()           QPicleDialog, 45         QProgressDialog, 136         QCustomMenutem, 7           resortDir()         setAutoReset()         QTabDialog, 147           QFileDialog, 4	- · · · · · · · · · · · · · · · · · · ·		
removeltemAt()			
QMenuData, 98, 128 removePage() QTabDialog, 145 QWizard, 175 setAcceptDockWindow() QTileDialog, 46 QTabDialog, 145 QWizard, 175 setActiveItem() QToolTipGroup, 169 removeToolBar() QMainWindow, 70 rereadDir() QFileDialog, 45 QWizard, 175 setAppropriate() QFileDialog, 45 QWizard, 176 rereadDir() QFileDialog, 45 QWizard, 176 QWizard, 176 reset() QProgressDialog, 135 QProgressDialog, 135 QProgressDialog, 136 QProgressDialog, 45 QProgressDialog, 45 QProgressDialog, 45 QProgressDialog, 45 QProgressDialog, 45 QProgressDialog, 136 QProgressDialog, 45 QProgressDialog, 136 QDockWindow, 29 resive() QProgressDialog, 135 QProgressDialog, 136 QDockWindow, 29 resiveIn() QProgressDialog, 45 QProgressDialog, 136 QDockWindow, 29 resiveIn() QProgressDialog, 45 QProgressDialog, 136 QCustomMenuItem, 7 resortDir() QFileDialog, 45 QProgressDialog, 136 QCustomMenuItem, 7 result() QProgressDialog, 136 QProgressDialog, 136 QToolTip, 167 result() QDialog, 16 QWizard, 175 QToolTip, 167 rightDock() QMainWindow, 70 QProgressDialog, 136 QTabDialog, 147 rightJustification QMainWindow, 74 QMessageBox, 111 QWizard, 176 rightJustification() QMainWindow, 71 QProgressDialog, 136 QCuscomMonuItem, 7 rightJustification() QMainWindow, 71 QProgressDialog, 136 QDockWindow, 29 restCancelButton() QMainWindow, 71 QProgressDialog, 136 QDockWindow, 29 restCancelButton() QProgressDialog, 136 QDockWindow, 29 restCancelButton() QDockWindow, 29 restCancelButton() QDockWindow, 29 restCancelButton() Reference CarealButton() R			
removePage() QTabDialog, 145 QWizard, 175 QWizard, 175 setActiveItem() QToolTipGroup, 169 removeToolBar() QMainWindow, 70 QFileDialog, 145 QProgressDialog, 135 QProgressDialog, 135 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 145 QProgressDialog, 136 QProgressDialog, 147 QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 136 QDockWindow, 29 resizeEnabled QDockWindow, 32 QToolButton, 156 QCustomMenuItem, 7 QFileDialog, 45 QProgressDialog, 136 QUstomMenuItem, 7 QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 136 QProolTip, 167 result() QDialog, 16 QWizard, 175 QProgressDialog, 136 QProgress		**	
QTabDialog, 145 QWizard, 175 setActiveItem() QFileDialog, 47 removeTip() QPopupMenu, 129 setFinish() QToolTipGroup, 169 emoveToolBar() QMainWindow, 70 rereadDir() QFileDialog, 145, 146 QFileDialog, 45 reset() QFileDialog, 45 QWizard, 175  reset() QProgressDialog, 135 QProgressDialog, 135 QProgressDialog, 136 QDockWindow, 32 resizeEnabled QDockWindow, 32 QFileDialog, 45 QProgressDialog, 156 QProgressDialog, 157  resortDir() QFileDialog, 45 QProgressDialog, 136 QFileDialog, 45 QFileDialog, 45 QProgressDialog, 136 QFileDialog, 45 QProgressDialog, 136 QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 136 QTabDialog, 147 result() QDialog, 16 QWizard, 175 QProgressDialog, 136 QToolTip, 167 residDock() QMainWindow, 70 QProgressDialog, 136 QToolTip, 167 rightDustification QMainWindow, 74 QMessageBox, 111 QWizard, 176 rightJustification() QMainWindow, 71 QProgressDialog, 136 SetCancelButton() QMainWindow, 29 SetHorizontallyStretchable() SetCancelButtonText() OpnockWindow, 29 SetHorizontalStretchable() SetCancelButtonText() OpnockWindow, 29 CPoolEWindow, 20 CPOOLEWINDO			
QWizard, 175 removeTip() QPopupMenu, 129 setFinish() QToolTipGroup, 169 removeToolBar() QMainWindow, 70 rereadDir() QFileDialog, 45 reset() QFileDialog, 45 reset() QProgressDialog, 135 resizeEnabled QDockWindow, 32 resortDir() QFileDialog, 45 QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 137 resortDir() QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 137 resizeEnabled QDockWindow, 32 QToolButton, 156 QCustomMenuItem, 7 resortDir() QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 146 qProgressDialog, 147 QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 147 rightJustification QMainWindow, 74 rightJustification() QMainWindow, 71 QProgressDialog, 136 QProgressDialog, 147 rightJustification() QMainWindow, 74 QMessageBox, 111 QWizard, 176 rightJustification() QMainWindow, 71 QProgressDialog, 136 QPockWindow, 29 setHorizontallyStretchable() QProgressDialog, 146 setHorizontallyStretchable() QPockWindow, 29 SetHorizontalStretchable()			
removeTip() QPopupMenu, 129 setFinish() QToolTipGroup, 169 setApplyButton() QWizard, 176 removeToolBar() QTabDialog, 145, 146 setFinishEnabled() QMainWindow, 70 setAppropriate() QWizard, 176 rereadDir() QMainWindow, 71 setFixedExtentHeight() QFileDialog, 45 QWizard, 175 QDockWindow, 29 reset() setAutoClose() setFixedExtentWidth() QProgressDialog, 135 QProgressDialog, 136 QDockWindow, 29 resizeEnabled setAutoRaise() setFont() QDockWindow, 32 QToolButton, 156 QCustomMenuItem, 7 resortDir() setAutoReset() QTabDialog, 147 QFileDialog, 45 QProgressDialog, 136 QToolTip, 167 result() setBackEnabled() setGloballyEnabled() QDialog, 16 QWizard, 175 QToolTip, 167 rightDock() setBar() setButton() QMainWindow, 70 QProgressDialog, 136 QTabDialog, 147 rightJustification setButtonText() setHelpEnabled() QMainWindow, 74 QMessageBox, 111 QWizard, 176 rightJustification() setCancelButton() setHorizontallyStretchable() QMainWindow, 71 QProgressDialog, 136 QDockWindow, 29 setCancelButton() SetHorizontalStretchable() setCancelButton() SetHorizontalStretchable() setCancelButtonText() SetHorizontalStretchable() setCancelButtonText() SetHorizontalStretchable() SetCancelButtonText() OPockWindow, 29		=	
QToolTipGroup, 169 removeToolBar() QMainWindow, 70 rereadDir() QFileDialog, 45 reset() QProgressDialog, 135 resizeEnabled QDockWindow, 32 resortDir() QFileDialog, 45 QFileDialog, 45 QProgressDialog, 135 QProgressDialog, 136 QPockWindow, 29 restAutoRaise() QDockWindow, 32 resortDir() QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 147 QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 result() QDialog, 16 QWizard, 175 QProgressDialog, 136 QProgressDialog, 136 QDialog, 16 QWizard, 175 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QToolTip, 167 rightDock() SetBar() QMainWindow, 70 QProgressDialog, 136 QTabDialog, 147 rightJustification QMainWindow, 74 QMessageBox, 111 QWizard, 176 rightJustification() QMainWindow, 71 QProgressDialog, 136 QDockWindow, 29 setCancelButton() QMainWindow, 71 QProgressDialog, 146 SetHorizontallyStretchable() Screen()			- 9.
removeToolBar() QMainWindow, 70 setAppropriate() QMainWindow, 71 rereadDir() QFileDialog, 45 QWizard, 175 QPileDialog, 45 QProgressDialog, 135 QProgressDialog, 136 QDockWindow, 29 resizeEnabled QDockWindow, 32 QToolButton, 156 QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 147 QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 136 QCustomMenuItem, 7 resortDir() SetAutoReset() QFileDialog, 45 QProgressDialog, 136 QToolTip, 167 result() QDialog, 16 QWizard, 175 QVizard, 175 QToolTip, 167 rightDock() QMainWindow, 70 QProgressDialog, 136 QProgressDialog, 136 QToolTip, 167 rightJustification QMainWindow, 70 QProgressDialog, 136 QTabDialog, 147 rightJustification() QMainWindow, 74 QMessageBox, 111 QWizard, 176 rightJustification() QMainWindow, 71 QProgressDialog, 136 QTabDialog, 147 setHorizontallyStretchable() QMainWindow, 71 QProgressDialog, 136 QDockWindow, 29 SetHorizontalStretchable() Secreen()			•
QMainWindow, 70setAppropriate()QWizard, 176rereadDir()QMainWindow, 71setFixedExtentHeight()QFileDialog, 45QWizard, 175QDockWindow, 29reset()setAutoClose()setFixedExtentWidth()QProgressDialog, 135QProgressDialog, 136QDockWindow, 29resizeEnabledsetAutoRaise()setFont()QDockWindow, 32QToolButton, 156QCustomMenuItem, 7resortDir()setAutoReset()QTabDialog, 147QFileDialog, 45QProgressDialog, 136QToolTip, 167result()setBackEnabled()setGloballyEnabled()QDialog, 16QWizard, 175QToolTip, 167rightDock()setBar()setHelpButton()QMainWindow, 70QProgressDialog, 136QTabDialog, 147rightJustificationsetButtonText()setHelpEnabled()QMainWindow, 74QMessageBox, 111QWizard, 176rightJustification()setCancelButton()setHorizontallyStretchable()QMainWindow, 71QProgressDialog, 136QDockWindow, 29screen()SetHorizontalStretchable()	removeToolBar()		= -
rereadDir() QFileDialog, 45 QWizard, 175 QWockWindow, 29 reset() QProgressDialog, 135 QProgressDialog, 136 QProgressDialog, 135 QProgressDialog, 136 QDockWindow, 29 resizeEnabled QDockWindow, 32 QToolButton, 156 QCustomMenuItem, 7 QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 136 QCustomMenuItem, 7 QFileDialog, 45 QProgressDialog, 136 QTabDialog, 147 QProgressDialog, 136 QToolTip, 167 result() QDialog, 16 QWizard, 175 QProgressDialog, 136 rightDock() QMainWindow, 70 QProgressDialog, 136 QTabDialog, 147 rightJustification QMainWindow, 74 QMessageBox, 111 QWizard, 176 rightJustification() QMainWindow, 71 QProgressDialog, 136 QTabDialog, 147 rightJustification() QMainWindow, 74 QMessageBox, 111 QWizard, 176 rightJustification() QMainWindow, 71 QProgressDialog, 136 QPockWindow, 29 SetCancelButton() QProgressDialog, 146 setHorizontallyStretchable() setCancelButton() QProgressDialog, 146 SetHorizontalStretchable()	QMainWindow, 70	<del>-</del>	
QFileDialog, 45 reset() setAutoClose() QProgressDialog, 135 QProgressDialog, 136 QCustomMenuItem, 7 resortDir() SetAutoReset() QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 result() QDialog, 16 QWizard, 175 QProgressDialog, 136 QToolTip, 167 rightDock() SetBar() QMainWindow, 70 QProgressDialog, 136 QToolTip, 167 setHelpButton() QMainWindow, 70 QProgressDialog, 136 QTabDialog, 147 rightJustification QMainWindow, 74 QMessageBox, 111 QWizard, 176 rightJustification() QMainWindow, 71 QProgressDialog, 136 QProgressDialog, 146 SetCancelButton() QProgressDialog, 146	rereadDir()		= :
reset() QProgressDialog, 135 QProgressDialog, 136 QDockWindow, 29 resizeEnabled QDockWindow, 32 QToolButton, 156 QCustomMenuItem, 7 resortDir() QFileDialog, 45 QProgressDialog, 136 QProgressDialog, 136 QCustomMenuItem, 7 QFileDialog, 45 QProgressDialog, 136 QToolTip, 167 result() QDialog, 16 QWizard, 175 rightDock() QMainWindow, 70 QProgressDialog, 136 QProgressDialog, 136 QToolTip, 167 setBar() QWizard, 175 setHelpButton() QMainWindow, 70 QProgressDialog, 136 QTabDialog, 147 rightJustification QMainWindow, 74 QMessageBox, 111 QWizard, 176 rightJustification() QMainWindow, 71 QProgressDialog, 136 QProgressDialog, 136 QDockWindow, 29 QTabDialog, 146 setCancelButton() QProgressDialog, 136 QDockWindow, 29 SetHorizontalStretchable() SetCancelButtonText() QDockWindow, 29	QFileDialog, 45		
QProgressDialog, 135  resizeEnabled QDockWindow, 32 QToolButton, 156 QCustomMenuItem, 7  resortDir() QFileDialog, 45  result() QDialog, 16  rightDock() QMainWindow, 70 QMainWindow, 74  rightJustification QMainWindow, 74  rightJustification() QMainWindow, 71  QMainWindow, 71  QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QTabDialog, 147  result() setBar() QWizard, 175 QrabDialog, 147  result() setBar() QProgressDialog, 136 QTabDialog, 147  result() setHelpButton() QProgressDialog, 136 QTabDialog, 147  result() setHelpEnabled() QMessageBox, 111 QWizard, 176  result() setCancelButton() QProgressDialog, 136 QDockWindow, 29  QTabDialog, 146 setHorizontalStretchable() setCancelButtonText() SetCancelButtonText() SetHorizontalStretchable() SetCancelButtonText() SetCancelButtonText() SetHorizontalStretchable()  QDockWindow, 29	reset()	,	
resizeEnabled QDockWindow, 32 QToolButton, 156 QCustomMenuItem, 7 resortDir() QFileDialog, 45 QFileDialog, 45  result() QDialog, 16 QDialog, 16 QMainWindow, 70 QMainWindow, 70 QMainWindow, 74 rightJustification QMainWindow, 74 QMainWindow, 74 QMainWindow, 71 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QMessageBox, 111 QWizard, 176 setHorizontallyStretchable() QMainWindow, 71 QProgressDialog, 136 QProgressDialog, 146 SetHorizontalStretchable() SetCancelButton() QProgressDialog, 146 SetHorizontalStretchable()	QProgressDialog, 135		
QDockWindow, 32 resortDir() setAutoReset() QTabDialog, 147 QFileDialog, 45 QProgressDialog, 136 QToolTip, 167 result() QDialog, 16 QDialog, 16 QWizard, 175 QMainWindow, 70 QMainWindow, 70 QMainWindow, 74 QMainWindow, 74 rightJustification() QMainWindow, 71 QMainWindow, 71 QProgressDialog, 136 QToolTip, 167 setBar() setBar() QProgressDialog, 136 QTabDialog, 147 setHelpEnabled() QMessageBox, 111 QWizard, 176 rightJustification() setCancelButton() QMainWindow, 71 QProgressDialog, 136 QDockWindow, 29 screen() QTabDialog, 146 setHorizontalStretchable() setCancelButtonText() SetCancelButtonText() QProgressDialog, 136 QDockWindow, 29 QTabDialog, 146 SetCancelButtonText() SetCancelButtonText() QDockWindow, 29	resizeEnabled		=
resortDir() QFileDialog, 45 QFrogressDialog, 136 QProgressDialog, 136 QProolTip, 167 result() QDialog, 16 QDialog, 16 rightDock() QMainWindow, 70 QMainWindow, 70 QMainWindow, 74 QMainWindow, 74 rightJustification() QMainWindow, 74 QMessageBox, 111 QWizard, 176 rightJustification() QMainWindow, 71 QProgressDialog, 136 QProgressDialog, 136 QWizard, 176 restHelpEnabled() QMessageBox, 111 QWizard, 176 restHorizontallyStretchable() QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 146 setHorizontalStretchable() serecancelButton() SerecancelButton() SerecancelButton() QProgressDialog, 146 SetHorizontalStretchable()	QDockWindow, 32		
QFileDialog, 45  result()  QDialog, 16  rightDock()  QMainWindow, 70  QMainWindow, 74  rightJustification()  QMainWindow, 74  rightJustification()  QMainWindow, 71  QMainWindow, 71  QMainWindow, 71  QProgressDialog, 136  QProgressDialog, 136  QProgressDialog, 136  QRessageBox, 111  QWizard, 176  setHelpEnabled()  QWizard, 176  setCancelButton()  QProgressDialog, 136  QProgressDialog, 136  QProgressDialog, 136  QProgressDialog, 136  QProgressDialog, 136  QProgressDialog, 146  setHorizontalStretchable()  serCancelButton()  SetCancelButton()  QProgressDialog, 146  SetHorizontalStretchable()	resortDir()		
result() QDialog, 16 QDialog, 16 rightDock() QMainWindow, 70 rightJustification QMainWindow, 74 rightJustification() QMainWindow, 74 QMainWindow, 74 QMessageBox, 111 QWizard, 176 restButton() QMainWindow, 74 QMessageBox, 111 QWizard, 176 setCancelButton() QMainWindow, 71 QProgressDialog, 136 QProgressDialog, 136 QDockWindow, 29 QTabDialog, 146 setCancelButton() QProgressDialog, 136 QDockWindow, 29 Sercen()  SetCancelButton() QProgressDialog, 146 SetHorizontalStretchable() SetCancelButton() QProgressDialog, 146 SetHorizontalStretchable()	QFileDialog, 45		
QDialog, 16 rightDock() QMainWindow, 70 rightJustification QMainWindow, 74 rightJustification() QMainWindow, 74 rightJustification() QMainWindow, 74 rightJustification() QMainWindow, 74 rightJustification() QMainWindow, 71 QMessageBox, 111 QWizard, 176 setCancelButton() QProgressDialog, 136 QProgressDialog, 136 QDockWindow, 29 QTabDialog, 146 setCancelButton() SetCancelButton() SetCancelButton() QProgressDialog, 136 QDockWindow, 29 Sercen() QProgressDialog, 146 SetHorizontalStretchable()	result()		
rightDock() QMainWindow, 70 QMainWindow, 70 rightJustification QMainWindow, 74 rightJustification() QMainWindow, 74 rightJustification() QMainWindow, 71 QMessageBox, 111 QWizard, 176 setCancelButton() QMainWindow, 71 QProgressDialog, 136 QDockWindow, 29 QTabDialog, 146 setCancelButton() SetCancelButton() QProgressDialog, 136 QDockWindow, 29 Sereen() QProgressPuttonText() QProgressWindow, 29	QDialog, 16		•
QMainWindow, 70 rightJustification QMainWindow, 74 rightJustification() QMainWindow, 74 rightJustification() QMainWindow, 71 QMessageBox, 111 rightJustification() QMainWindow, 71 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 136 QProgressDialog, 146 SetHorizontalStretchable() screen() SetCancelButtonText() SetCancelButtonText() OProckWindow, 29	rightDock()	- · · · · · · · · · · · · · · · · · · ·	
rightJustification QMainWindow, 74 rightJustification() QMainWindow, 71 QMessageBox, 111 QWizard, 176 setCancelButton() QMainWindow, 71 QProgressDialog, 136 QProgressDialog, 146 screen() setCancelButton() QProgressDialog, 146 setHorizontalStretchable() SetCancelButtonText() QProgressDialog, 146 SetCancelButtonText() SetCancelButtonText() QProgressDialog, 146 SetCancelButtonText() SetCancelButtonText() QProgressDialog, 146 SetCancelButtonText()	QMainWindow, 70		*
QMainWindow, 74 rightJustification() QMainWindow, 71 QMessageBox, 111 QWizard, 176 setHorizontallyStretchable() QProgressDialog, 136 QPockWindow, 29  QTabDialog, 146 setCancelButtonText() QPockWindow, 29  ODockWindow, 29	rightJustification		
rightJustification()  QMainWindow, 71  QProgressDialog, 136  QProgressDialog, 136  QDockWindow, 29  Screen()  SetCancelButton()  SetHorizontallyStretchable()  QDockWindow, 29  SetCancelButtonText()  ODockWindow, 29			
QMainWindow, 71 QProgressDialog, 136 QDockWindow, 29 QTabDialog, 146 setHorizontalStretchable() sercancelButtonText() QProgressDialog, 136 QDockWindow, 29 QDockWindow, 29			
QTabDialog, 146 setHorizontalStretchable() screen() setCancelButtonText() ODockWindow 29	QMainWindow, 71		
screen() setCancalButtonText() ODockWindow 29	0		
QDesktopWidget, 10			
	QDesktopWidget, 10	v	,

setIcon()	QFileDialog, 48	setViewMode()
QMessageBox, 111	setProgress()	QFileDialog, 49
setIconPixmap()	QProgressDialog, 137	setWhatsThis()
QMessageBox, 111	setResizeEnabled()	QMenuData, 99, 130
setIconProvider()	QDockWindow, 30	setWidget()
QFileDialog, 47	setResult()	QDockWindow, 30
setIconSet()	QDialog, 16	show()
		**
QToolButton, 156 setId()	setRightJustification()	QDialog, 17
•	QMainWindow, 72	QMenuBar, 86
QMenuData, 99	setScrollBarsEnabled()	showDockMenu()
setInfoPreview()	QWorkspace, 180	QMainWindow, 72
QFileDialog, 47	setSelectedFilter()	showExtension()
setInfoPreviewEnabled()	QFileDialog, 48	QDialog, 17
QFileDialog, 48	setSelection()	showHiddenFiles
setItemChecked()	QFileDialog, 49	QFileDialog, 51
QMenuData, 99, 129	setSeparator()	showHiddenFiles()
setItemEnabled()	QMenuBar, 86	QFileDialog, 49
QMenuData, 85, 99, 129	setShowHiddenFiles()	showPage()
setItemParameter()	QFileDialog, 49	QTabDialog, 148
QMenuData, 99, 129	setSizeGripEnabled()	QWizard, 176
setLabel()	QDialog, 17	showTip()
QProgressDialog, 136	setStretchableWidget()	QToolTipGroup, 170
QToolBar, 151	QToolBar, 151	sizeGripEnabled
setLabelText()	setTabBar()	QDialog, 17
QProgressDialog, 136	QTabDialog, 147	sizeHint()
setMinimumDuration()	setTabEnabled()	QCustomMenuItem, 8
QProgressDialog, 137	QTabDialog, 147, 148	QProgressDialog, 137 standardIcon()
setMode()	setText()	
QFileDialog, 48 setMovingEnabled()	QMessageBox, 111 setTextFormat()	QMessageBox, 111 statusBar()
QDockWindow, 29	QMessageBox, 111	QMainWindow, 72
setNewLine()	setTextLabel()	stretchable
QDockWindow, 29	QToolButton, 157	QDockWindow, 32
setNextEnabled()	setTitle()	QDockwindow, 32
QWizard, 176	QWizard, 176	
setOffIconSet()	setTitleFont()	tabBar()
QToolButton, 157	QWizard, 176	QTabDialog, 148
setOffset()	setToggleButton()	tabLabel()
QDockWindow, 29	QToolButton, 158	QTabDialog, 148
setOkButton()	setToolBarsMovable()	text
QTabDialog, 147	QMainWindow, 72	QMessageBox, 113
setOn()	setTotalSteps()	text()
QToolButton, 157	QProgressDialog, 137	QMenuData, 99, 130
setOnIconSet()	setUpLayout()	QMessageBox, 111
QToolButton, 157	QMainWindow, 72	textFor()
setOpaqueMoving()	setUrl()	_QToolTip, 167
QDockWindow, 30	QFileDialog, 49	textFormat
QMainWindow, 72	setUsesBigPixmap()	QMessageBox, 113
setOrientation()	QToolButton, 158	textFormat()
QDialog, 16	setUsesBigPixmaps()	QMessageBox, 111
QDockWindow, 30	QMainWindow, 72	textLabel
setPalette()	setUsesTextLabel()	QToolButton, 160
QToolTip, 167	QMainWindow, 72	textLabel()
setPopup()	QToolButton, 158	QToolButton, 158
QToolButton, 157	setVerticallyStretchable()	tile()
setPopupDelay()	QDockWindow, 30	QWorkspace, 180
QToolButton, 157	setVerticalStretchable()	tip() QToolTip, 167
setPreviewMode()	QDockWindow, 30	title()

Index 186

QWizard, 176	QDockWindow, 30	QDockWindow, 32
titleFont	updateItem()	ViewMode
QWizard, 177	QMenuData, 100	QFileDialog, 39
titleFont()	QPopupMenu, 130	viewMode
QWizard, 176	url()	QFileDialog, 51
toggle()	QFileDialog, 49	viewMode()
QToolButton, 158	uses3D()	QFileDialog, 49
toggleButton	QToolButton, 158	visibilityChanged()
QToolButton, 160	usesBigPixmap	QDockWindow, 30
toolBarPositionChanged()	QToolButton, 160	
QMainWindow, 73	usesBigPixmap()	warning()
toolBars()	QToolButton, 158	QMessageBox, 112
QMainWindow, 73	usesBigPixmaps	wasCancelled
toolBarsMovable()	QMainWindow, 74	QProgressDialog, 138
QMainWindow, 73	usesBigPixmaps()	wasCancelled()
toolTipGroup()	QMainWindow, 73	QProgressDialog, 137
QMainWindow, 73	usesTextLabel	whatsThis()
topDock()	QMainWindow, 75	OMainWindow, 73
QMainWindow, 73	QToolButton, 160	QMenuData, 100, 130
totalSteps	usesTextLabel()	widget()
QProgressDialog, 138	QMainWindow, 73	QDockWindow, 31
totalSteps()	QToolButton, 158	windowActivated()
QProgressDialog, 137	usesTextLabelChanged()	QWorkspace, 180
	QMainWindow, 73	windowList()
undock()	verticallyStretchable	QWorkspace, 180